LESSON LEARNED – EROSION AND SEDIMENT CONTROL PART 1-LAWS AND REGULATIONS

Ting Guo, DelDOT E&S Engineer Mary Hamilton, DelDOT E&S Program Manager March 10, 2020

How Much Does Erosion and Sediment Control for DOT Projects Cost?

Jan 1st, 2003



Ec0301 58a

By Gayle F. Mitchell, Ting Guo, and Nida Igiz

Manmade accelerated soil erosion and the resulting suspension of soil particles in water or air can have detrimental environmental and societal results. Sediment has been identified as the single most common water pollutant, and increased dust is a major contributor to air pollution. Consequently, processes, procedures, practices, and products have been developed, promulgated, studied, and implemented to minimize erosion and resulting sedimentation and dust.

Summary


The average of total reported annual ESC expenditures in 2000 on state highway projects for 30 state DOTs was \$9,010,000. The year's total ESC expenditures for the 30 states were approximately \$270 million. Erosion and sediment costs as a function of total highway construction project costs averaged 3%. The majority of states reporting three years of erosion and sediment costs indicate that they are increasing.

Future plans are to update the data and encourage all states to participate. Data for the benefit side need to be developed and cost/benefit ratios estimated. In addition, plans are to extend the study to other sectors.

Gayle F. Mitchell, Ph.D., P.E., is a professor in the Civil Engineering Department at Ohio University in Athens, OH.

Ting Guo and Nida Igiz are graduate students at Ohio University.

DNREC – DeIDOT Environmental Associations





Why are we doing this?

- Land disturbance over 5,000 sq ft needs an approved Sediment and Stormater Management Plan (SSMP).
- Project disturbance over 1 acre needs to file a NOI (NPDES Construction General Permit), and close out the project by filing a NOT.


Delaware Law

TITLE 7 Conservation Agricultural and Soil Conservation; Drainage and Reclamation of Lowlands CHAPTER 40. Erosion and Sediment Control CHAPTER 60. Environmental Control


Delaware Sediment and Stormwater Regulations (DSSR)

DEPARTMENT OF NATURAL RESOURCES AND ENVIRONMENTAL CONTROL Division of Watershed Stewardship Statutory Authority: 7 Delaware Code, Chapter 40 (7 Del.C. Ch.40) 7 DE Admin. Code 5101 Sediment and Stormwater Regulations

7 Del.C. Ch. 60, Environmental Control7 DE Admin. Code 7201, Regulations Governing the Control of Water Pollution



Delegated Agencies Under DNREC



DelDOT as a Delegated Agency


- The above agencies have delegation of Sediment and Stormwater Program elements consisting of plan review/approval, construction inspection, and maintenance inspection for their geographic boundaries. Re-delegation occurs every 5 years.
- DelDOT is one of the Delegated Agencies by DNREC
- Major project (as determined by the Stormwater Engineer) needs CCR (Certified Construction Reviewer, Gold Card Holder) assigned. Minor project use a DelDOT self review form.
- Blue Card holder (DNREC's contractor training program) is needed for all projects that has an approved Sediment and Stormwater Management Plan (SSMP).
- Subject to DNREC's Re-delegation Review and EPA's Audit (unannounced visit)

DNREC VS. DELDOT

- DNREC (and other delegated agencies) geared mostly towards development work
- DelDOT is the owner of the project



BASIC ES2M PROCESS



APPROVED SEDIMENT AND STORMATER MANAGEMENT PLAN (SSMP)

- It is very important to keep a current SSMP on site.
- The first thing regulatory agent will ask is a current SSMP and a copy of NOI (if applicable).
- ESLs are great resources for redlines and revisions.



DELAWARE CONSTRUCTION GENERAL PERMIT

- Applies to any disturbances > 1 acre (NOI / NOT)
- Focus on Pollution Prevention



DELDOT SPECIFICATIONS & STANDARD CONSTRUCTION DETAILS

- Specifications DIVISION 900 EROSION, SEDIMENT AND STORMWATER MEASURES
 - 901 EROSION, SEDIMENT, AND STORMWATER MANAGEMENT SECTION
 - 902 PUMPING OPERATIONS SECTION
 - 903 POLLUTION PREVENTION SECTION
 - 904 RESERVED SECTION
 - 905 SEDIMENT TRAPPING DEVICES SECTION
 - 906 DEWATERING PRACTICES SECTION
 - 907 WATER CONTROL PRACTICES SECTION
 - 908 SOIL STABILIZATION PRACTICES SECTION
 - 909 WATERWAY CONSTRUCTION PRACTICES SECTION
 - 910 STORMWATER MANAGEMENT FACILITIES SECTION
 - 911 PLANTINGS
- Construction Details Section IV Erosion (E-1 through E-21)

BEFORE WEEKLY INSPECTION STARTS:

- ES2M Pre-Construction Meeting
 - Set up weekly inspection schedule
 - Any E&S concerns
 - Notification for BMP construction
- Initial Inspections
 - Required by DSSR
 - Perimeter Control (LOC)
 - E&S Control (Stream Diversion if applicable)
 - Prior to any earth disturbance
 - Pollution prevention elements

CONSTRUCTION SITE INSPECTION FOR E&S

- 3rd Party E&S Inspectors (Consultants, weekly)/Regulatory Inspections (E&S program, unannounced)
 - Rating Form
 Similar to Maryland's
 Different sections carry a weighted percentage
 - Non-Rating Form
 Based on Rating Form and DNREC's form ("U" or "S")
 Even one "U" will result "Non-Compliance"
- Facility Construction Checklist (Permanent BMPs)
- Self-Inspection Form (DeIDOT Construction Inspector non-CCR weekly/rain event inspections)
- Vegetative Evaluation (April and October)
- SWPPPTrack (CCR forms, Self-Inspection forms, VE, BMP checklists and other forms)
- New Specifications and Details

Tot whether Date Year Tot well well A-Del Communion CONTRACT NAME: Muse with well well Tot well well Tot well well Tot well well Tot well well well Tot well well well well well Tot well well well well well well well wel	Century Engineering, Inc ES2M INSPECTION REPORT 550 Bay Road, Dover, DE 19901	302-734-9188 302-245-1891		f gletown Rd., Suite 300 DE 19713	ES2M Inspec	tion Rating Form	1	Ph. 302.781-5900 FAX:302.781.5901	
CE NEXTOR Heideline (A. Dell Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) Delic Cale) (Caulor, Page) THE Delic Cale) (Caulor, Page) Delic Cale) (Delic Cale)		01301			DATI	3/5/2020	CONTRACT NO:	T200809001	
INFECTION Dut code (densure Tage) INCOM OUTON Densure Tage Densu	FROM: JENIFER JOSEPH CONTRACTOR: A-Del Construction		_	Greggo & Ferrara	CON	RACT NAME: I-	95 N213 Carr Road & S	R 3 Marsh Road	
INIT TAN TAN TAN TAN TAN WE 001.01 NIMPTONE 228/2020 FAIL PAIL Bell Bell Briticley (G&F-ESCS) MINE ACTIVE EASONTORENERTONE VET.V NUB* 057 MINE COMPLATE NUB* 057 MINE DIVENT NUB* 057 MINE COMPLATE NUB* 057 MINE COMPLATE NUB* 057 MINE COMPLATE NUB* 057 MINE COMPLATE NUB* 057 MINE NUB* COMPLATE NUB* 050 MINE STATE OF LAST PLAN NUB* 2127/2020 EXPHINATION: 2152/2021 MINE COMPLATE NUB* NUB* COMPLATE NUB* OUT DIVE NUB* OUT DIVE COMPLET NUB* OUT DIVE DIVE NUB* OUT DIVE COMPLET NUB* OUT DIVE DIVE DIVE DIVE DIVE DIVE DIVE <t< td=""><td></td><td></td><td>FROM</td><td>Rob Roop</td><td></td><td></td><td>Greggo & Fer</td><td>rara</td></t<>			FROM	Rob Roop			Greggo & Fer	rara	
Implementations	8:00 AM 9:00 AM BATE OF LAST			AECOM	Pr		Ben Brindley (G&	Ben Brindley (G&F-ESCS)	
Image: Non-Complexion Image: Annow Setting the Annow Setting to Complexion Image: Annow Seting to Complexion Image: Anno	STATUS: ACTIVE REASON FOR INSPECTION: WEEKLY NOI# 6057					2/27/2020		5/2021	
WESD SSW-9 BHFEMENTATION & MUNITANCE OF REGION & STEDUEN CONTROL ENVICES and FAS STATUS KEY S Satisfactory U Unsatisfactory Leave blank (//M.d. CCCR RATING/NON- BATENCE CONTROL ENVICES Leave blank (//M.d. Weighted Average Percentage (2 + 3)/2 s 50% divided by number of 200% Section 4 x 20% 2000 (2 - 28 - 28 - 89 - 29) Weighted Average Percentage (2 + 3)/2 s 50% divided by number of 200% Section 5 x 10% 0.00 Section 5 x 10% 0.00 Total Rating Percentage (2 + 3)/2 s 50% divided by number of 200% 12.11 Section 5 x 10% 0.00 Total Rating Percentage (2 + 3)/2 s 50% divided by number of 200% 12.11 Section 5 x 10% 0.00 0 Section 5 x 10% 0.00	GENERAL SITE COMPLIANCE NON-COMPLIANT TEMPERATURE 43		STA	ATUS: ACTIVE X INACTIVI	E COMPLETE		NOI#		
Statisfactory U Uusatisfactory Leeve blank (f N/A Number of voltage Number of voltage Section Number of voltage Section 1 20% 20.00 2 28 28 100.00 2 28 28 100.00 2 3 22 28 89.29 0 Weighted Average Percentage (4 + 3)/2 x 50% 47.32 8 4 32 38 4 23 38 4 26 0 0 0 0 0 5 0 10 0.00 0 0 0 0 0 5 0 10 0.00 <				KEASON FOR EVEN AND ECTIONS					
1 26 26 1 2 28 28 100.00 3 25 28 89.29 Weighted Average Percentage (2 + 3)/2 x 50% divided by number of sections rated 47.32 8 4 23 38 12.11 C 5 0 10 00 D D 5 0 10 0.00 D D D 70tal Rating Percentage (Add Box A, B and C) 70TAL 79.43 SELECT ONE & Highlight RTING: 100 - 90 \$9.99 - 80 X 79.99 - 70 69.99 - 60 50.99% is non-compliant. CC: AE KATE SCHWANDER CCR Rob Roop No:: 2017/10/26 065 CCR Rob Roop				Section		and the second se			
2 28 28 100.00 3 25 28 89.29 Weighted Average Percentage (2 + 3)/2 x 50% divided by number of sections rated 47.32 B 4 23 38 12.11 C 5 0 10 0.00 D 0 0.00 D Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 SELECT ONE & Highlight CCR 100 - 90 189.99 - 80 17.999 - 70 169.99 - 60 159.99 - 0 SELECT ONE & Highlight CCR RATING: 100 - 90 189.99 - 80 17.999 - 70 169.99 - 60 159.99 - 0 SELECT ONE & Highlight CCR Rob Roop No: 2017/10/26 065				1	26	26	>	A	
CCR RATING FORMS A 100 - 90 B 3.99 - 80 X 19.99 - 70 Correction 5 x 10% Section 4 x 20% Section 5 x 10% Correction 5 x 10% Corection 5 x 10% <td></td> <td></td> <td></td> <td colspan="3"></td> <td>and the second se</td> <td></td>							and the second se		
CCR RATING FORMS RATING FORMS RATING FORMS RATING: 100 - 90 89.99 - 80 10 0.00 0.00 0.00 0.00 0.00 0.00 0.0						and the second se			
CCR RATING/NON- RATING FORMS						28	89.29		
CCR RATING/NON- RATING FORMS divided by number of sections rated 47.32 B 4 23 38 12.11 C 5 0 10 0.00 D Total Rating Percentage (Add Box A, B and C) TOTAL 79.43					·	M			
4 23 38 Section 4 x 20% 12.11 5 0 10 Section 5 x 10% 0.00 D Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 RATING: 100 - 90 89.99 - 80 X 79.99 - 70 69.99 - 60 59.99 - 0 K Highlight CC: CC: <t< td=""><td></td><td></td><td colspan="2"></td><td></td><td>ed</td><td>47 32</td><td>в</td></t<>						ed	47 32	в	
Section 5 x 10% 0.00 D Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 RATING: 100 - 90 89.99 - 80 x 79.99 - 70 69.99 - 60 SELECT ONE CC: CCR: CO: CCR: CO: CCR: CO: CCR: CO: CCR:				the second se		and the second division of the second divisio			
Section 5 x 10% 0.00 D Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 RATING: 100 - 90 89.99 - 80 x 79.99 - 70 69.99 - 60 SELECT ONE CC: CCR: CO: CCR: CO: CCR: CO: CCR: CO: CCR:					Section 4 x 20%		12.11	С	
Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 Total Rating Percentage (Add Box A, B and C) TOTAL 79.43 RATING: 100 - 90 89.99 - 80 X 79.99 - 70 69.99 - 60 SELECT ONE CC: CCR: CCR: CCR: CO: CCR: CCR: CCR: CCR: CCR: CO: CCR:				5	0	10	>	1	
RATING FORIDS RATING: 100 - 90 89.99 - 80 x 79.99 - 70 69.99 - 60 59.99 - 0 & Highlight CC: AE KATIE SCHWANDER CCR: 03-05-2020 CCR CCR No.: 2017/10/26 065					An an an an an an an an		0.00	D	
RATING: 100 - 90 89.99 - 80 X 79.99 - 70 69.99 - 60 59.99 - 0 SELECT ONE S 69.99% is non-compliant. \$ 69.99% is non-compliant. \$ 69.99% is non-compliant. CC: \$ 69.99% is non-compliant. CCR Rob Roop AE KATIE SCHWANDER CCR: \$ CCR \$ CCR \$ CCR \$ Rob Roop				Total Rating Perce	entage (Add Box A, B and	C) TOTAL	79.43		
CC: CC: D D3-05-2020 CCR Rob Roop AE KATIE SCHWANDER CCR: UD 03-05-2020 No.: 2017/10/26 065									
				KATIE SCHWANDER	ccr:	to the		CCR Rob Roop	

Regular, timely inspections are critical - conduct inspections weekly and after every rainfall event of ½ inch or more. Inspection data Site location: 7201701301 Million Rei Trail						
Inspection data						
Site location: $\boxed{7201701301}$ million Ba: $\boxed{7ai1}$						
Routine inspection for week ending 2/9 - 2/15/2020						
Pre-rain during [post rain] repection and time elapsed since rain: 8 00/3	ХИЛАЛ					
Pre-rain during [post rain inspection and time elapsed since rain: 8 101/3 Date: 7/3/2020 Time: 7AM.	XAN/II					
Inspected by (name and title); Signature: Mithe Jun Matthew Schneider, Inspector	., ., ., .,					
OK? problem identified action taken						
1. Erosion control practices in place and functioning? (mulch, seeding, blankets) S-AS PER SSMP						
2. Sediment traps, barriers and basins clean and the sediment transmission trans	DELDOT E&S SITE INSPECTION FORM					
3. Sediment controls in place at site perimeter and storm of S	DECLILAD, TIMELY INSDECTIONS ADD CDITICAL CONDUCT DEDUCTIONS WEREY VA					
4. Discharge points free of any noticeable pollutant in S WITHIN 24 HOURS OF A RAIN EVENT GREATER THAN OR EQUAL TO 0.50'	REGULAR, TIMELY INSPECTIONS ARE CRITICAL – CONDUCT INSPECTIONS WEEKLY & WITHIN 24 HOURS OF A RAIN EVENT GREATER THAN OR EQUAL TO 0.50" IN A 24 HOUR					
5. Sediment, mud and debris being cleaned from public roads? Is there a stable, rocked entrance to the site? Are there adequate provisions to prevent mud tracking off site? S CONTRACT NO: T209901206 PROJECT NAME: Billys December Test Project	et					
DATE: 03/06/2020 TIME IN: 12:00 TIME OUT: 14:00 NOI:						
Sediment & Stormwater Management Plan (SSMP)						
1. Is the Sediment & Stormwater Mgt Plan (SSMP) current? U - Redline/Revision	Required					
Erosion & Sediment Controls						
2. Are erosion control practices in place and function? (mulching, soil stabilizers, seeding, blankets) U - Repair, Replace,	or Modify					
3. All sediment control devices installed as per SSMP? (CSIC, DISC, CFLs) U - Not Installed Per	SSMP					
4. Are sediment traps and basins functionality properly? (stabilized, capacity <= 50%, outlets installed) S - As Per SSMP						
5. Are outfall discharge points free of any sediment? S - As Per SSMP						

EXAMPLE

DELDOT PERMANENT SWM FACILITIES

- BMP Checklist
- Permanent BMP List (M&O)
- Most Common BMP's Used
 - Infiltration Basin and Trench
 - Bioswales and Vegetated Channels
- Lesser BMP's Used
 - Bioretention
 - Underground Infiltration



CONFUSING, BUT NEED TO BE AWARE * EPA FINES

