

# **2009 Winter Workshop – New Pavement Technologies**

**February 26, 2009**

**Polytech, Woodside**

**Jim Pappas**

**Materials & Research**

# Warm Mix Asphalt

- ◆ Through modification, mixes can be produced and placed at lower temperatures (190°F - 250°F).
- ◆ Results have shown nationally that performance is not adversely affected by the lower production and placement temperatures.

# WMA (cont)

## ◆ Some potential benefits of WMA:

- Lower production temperatures.
- Lower energy costs for supplier.
- Lower prices Department pays.
- Less fumes.
- Less emissions.
- Less temperature loss.
- Extended paving season.
- Use over crack sealant material.

## **WMA** (cont)

- ◆ Only concern raised to date has been possible moisture damage within the pavement.
- ◆ Caused by the possible lack of completely dry aggregates due to the lower production temperatures.
- ◆ State tests have varied on this issue.

## WMA (cont)

- ◆ Even with lower mix temperatures, performance of materials is the same as conventional HMA.
- ◆ Additives at plant modify viscosity of the asphalt binder.
  - Additives can be waxed based materials or foaming operations using water.
- ◆ May be able to modify roller activities?

## **WMA** (cont)

- ◆ For DelDOT, one WMA location to date.
- ◆ Marrows Road in Newark.
- ◆ Diamond Materials produced and placed the material.
- ◆ Mix temperature was 245°F; less than 5°F temperature loss from plant to location.

# WMA (cont)

## ◆ Future of WMA in Delaware:

- Several possible locations have been scoped.
- DRAFT specification is being written.
  - ◆ Modification method will be up to supplier.
  - ◆ New item numbers will be used.
- Contracts out in 2009.

◆ National thinking is that in the coming years, 100% of production could be WMA.

# Precast-Prestressed Concrete Pavement

- ◆ Roadway slabs that are cast off-site.
- ◆ Varying widths, depths, and lengths can be cast.
- ◆ Dimensions are mostly controlled by transportation.
- ◆ Varying reinforcement can be used.
- ◆ Various methods available – some are proprietary.

## **PPCP - Location** (cont)

- ◆ Looked for an application for the last few years.
- ◆ Several locations have been reviewed by industry, FHWA, and consultants.
- ◆ Most posed some logistical issue.
- ◆ Finally, a location was reviewed and seemed to be a good candidate.

## **PPCP - Location** (cont)

- ◆ Location has adequate work space.
- ◆ Multi-lanes so traffic can be maintained during construction.
- ◆ High traffic count location to test the reliability of the PPCP.
- ◆ Large enough quantity to make the project attractive to bidders.

## **PPCP - Location** (cont)

- ◆ SR 896 NBR & SR 40 EBR
- ◆ Severe deterioration of the existing PCC joints due to ASR.
- ◆ Has been on the Pavement Management list for rehabilitation.
- ◆ Rehab needed both at intersection and other joints in the area.

## PPCP - Location (cont)

- ◆ Construction Contract is a combination of PPCP and conventional high-early strength PCC patches.
- ◆ Plan is to have contractor pour conventional PCC patches while PPCP are being prepared.

# PROJECT OVERVIEW: Location




# PROJECT OVERVIEW – Fact Sheet



## Fact Sheet:

- **Functional Class – Principal Arterial.**
- **AADT – 37,679; % Trucks – 9%.**
- **Existing Pavement Section – 12” PCC over 8” stone.**
- **Replace failing jointed plain concrete pavement within the right and left turn lanes with Precast-Prestressed Concrete Pavement (PPCP). 8” PPCP over 4” pervious concrete**

# PROJECT OVERVIEW – PPCP Replacement Area



EXISTING PCC



CAST-IN-PLACE



PPCP REPLACEMENT AREA

# PPCP – Project Development (cont)

## ◆ Construction

- Proposed Schedule: Sunday evening through Friday morning.
- Restricted Working Hours: 7:30 PM – 5:30 AM
- All lanes restored to unrestricted use at the end of each workday.

# PPCP – Project Development (cont)

## ◆ Additional Project Points ....

- ✓ 10 precast suppliers had expressed an interest in this project.
- ✓ Contract was advertised to supply and install PPCP panels. Design alternates will not be considered.
- ✓ Optimum size for panel fabrication - 8' L X 24' W & 8' L X 12' W
- ✓ Contract timing will permit 6-8 weeks for fabrication.
- ✓ Stored Material Payments in accordance w/ Standard Specifications.
- ✓ An on-site area will be made available for material storage.

# DeIDOT Expectations

- ◆ Success of a new product/process.
- ◆ New option for PCC patching.
- ◆ Gain further experience.
- ◆ Department is always open to new ideas and technologies.

**Thanks to the following for their work on this project....**

**North District Construction  
Pavement Management**





Thank you for your time and  
attention....

Any questions or comments?