



NOTES

- 1). TREE PRUNING IS TO BE PERFORMED BY AN I.S.A. CERTIFIED ARBORIST, CERTIFIED NURSERY PROFESSIONAL, OR UNDER THE DIRECTION THEREOF. DO NOT HEAVILY PRUNE TREES AT PLANTING.
- 2). PRUNE ALL DEAD, BROKEN, & CROSSING BRANCHES FOLLOWING INSTALLATION.
- 3). DIG BASE OF PLANTING PIT A MINIMUM OF TWO AND A MAXIMUM THREE TIMES THE SIZE OF THE ROOT BALL.
- 4). A MINIMUM OF 3'-0" IS REQUIRED FROM THE MIDDLE OF THE TREE TO ANY PERMANENT STRUCTURE (I.E. CURB, SIDEWALK, BUILDING, ETC...)
- 5). LIMB TREE TO 7'-0" FOR PEDESTRIAN CLEARANCE WHEN PLANTING ADJACENT TO SIDEWALKS.

STAKE & GUY TREES. REFER TO SPECIFICATIONS FOR MATERIAL GUIDELINES

SET ROOT BALL FLUSH TO GRADE OR 1" TO 2" ABOVE GRADE IF SOILS ARE SLOW TO DRAIN AND SO THAT TRUNK FLAIR IS VISIBLE. DO NOT COVER THE TOP OF THE ROOT BALL WITH SOIL.

TAMP SOIL AROUND THE ROOT BALL BASE WITH FOOT PRESSURE SO ROOT BALL DOES NOT SHIFT.

MULCH IN ACCORDANCE WITH SPECIFICATIONS. DO NOT PLACE MULCH AGAINST THE TRUNK.

MIX SOIL EXCAVATED FROM PIT WITH APPROVEMENT AMMENDMENTS AS PER SPECIFICATIONS AND USE AS BACKFILL DURING INSTALLATION OF TREE.

REMOVE BURLAP AND BASKETS TO 1/2 OF THE ROOT BALL. DO NOT BURY EXCESS BURLAP, ROPE OR REMNANTS OF BASKET IN THE PLANTING PIT.

TREE PLANTING DETAIL



DELAWARE
DEPARTMENT OF TRANSPORTATION

PLANTING DETAILS				APPROVED	SIGNATURE ON FILE <small>CHIEF ENGINEER</small>	5/31/2017 <small>DATE</small>	
STANDARD NO.	L-1 (2017)	SHT.	2	OF	3	RECOMMENDED	
						SIGNATURE ON FILE <small>DESIGN ENGINEER</small>	5/18/2017 <small>DATE</small>