


GUARDRAIL REFLECTOR



W-BEAM BEARING PLATE

NOTES:


- 1). GUARDRAIL REFLECTORS ON TYPE 1 AND 3 GUARDRAIL SHALL BE INSTALLED IN THE CENTER SLOT HOLES WHERE POSTS ARE NOT LOCATED. GUARDRAIL REFLECTORS ON TYPE 2 GUARDRAIL ARE TO BE INSTALLED IN THE CENTER SLOT HOLES LOCATED ON THE SPLICE ONLY. GUARDRAIL REFLECTORS ON THRIE BEAM GUARDRAIL ARE TO BE LOCATED ON THE UPPER MOST CENTER SLOT HOLE LOCATED ON THE SPLICE ONLY.
- 2). GUARDRAIL REFLECTORS SHALL NOT BE INSTALLED WITHIN THE LIMITS OF GUARDRAIL END TERMINALS.
- 3). GUARDRAIL REFLECTOR SPACING SHALL BE NO LESS THAN 50 FEET.
- 4). GUARDRAIL REFLECTORS PLACED ON THE RIGHT SIDE OF A TWO-WAY TWO-LANE ROADWAY SHALL DISPLAY WHITE RETROREFLECTIVE SHEETING TO BOTH DIRECTIONS OF TRAVEL.
- 5). GUARDRAIL REFLECTORS PLACED ON THE LEFT SIDE OF A DIVIDED HIGHWAY OR RAMP SHALL DISPLAY YELLOW RETROREFLECTIVE SHEETING TO THE APPROACHING DIRECTION OF TRAVEL AND RED RETROREFLECTIVE SHEETING TO THE WRONG DIRECTION OF TRAVEL.
- 6). GUARDRAIL REFLECTORS PLACED ON THE RIGHT SIDE OF A DIVIDED HIGHWAY OR RAMP SHALL DISPLAY WHITE RETROREFLECTIVE SHEETING TO THE APPROACHING DIRECTION OF TRAVEL AND RED RETROREFLECTIVE SHEETING TO THE WRONG DIRECTION OF TRAVEL.




 ENGINEERING SUPPORT 09/01/2020
 RECOMMENDED DATE

REFLECTOR AND W-BEAM BEARING PLATE			
STANDARD NO.	B-13 (2020)	SHT. 9	OF 12

REVIEWED 
 DEPUTY DIRECTOR - DESIGN 09/01/2020
 DATE

APPROVED 
 CHIEF ENGINEER 09/01/2020
 DATE