

Louis H. Tunnell House c. 1920
Route 9 (tax map #3-34-5-135.1)
Figure 36; Plate 17
CRS #S-8008

Description: The Louis H. Tunnell House is a small one story, rectangular three bay, wood framed dwelling with two additions extending to the north. Resting on concrete block piers, the main block has exterior walls covered in metal cladding below an overhanging gabled roof with metal clad eaves, sheathed in composite shingles. The southern elevation faces Route 9 and forms a three bay facade composed of an axial sash entrance door between 1/1 sash windows. The eastern and western elevations or gable ends of the main block each contain a 1/1 sash window. Window and door surrounds are of molded wood. A shed roofed addition extends the width of the main block one bay to the north, and is lighted by a 1/1 sash window in the eastern elevation and a sash entrance door in the western elevation. Metal cladding covers the exterior walls of the shed roofed addition. A flat roofed addition extends the width of the shed roofed addition one more bay to the north, with walls covered in vertical board paneling and a 1/1 sash window on the eastern elevation. The exterior chimney is located on the western elevation south of the ridge of the main block and is covered with stucco. One outbuilding stands on this property, a rectangular one story, wood framed shed. It is located to the northwest of the dwelling, with plywood covering the exterior walls and composite shingles covering the shed roof. A double leaf entrance door of vertical flush boarding is centered on the southern elevation.

Martha Norwood House late 19th c.
Route 9 (tax map #3-34-5-139)
Figure 36; Plate 18
CRS #S-8009

Description: The Martha Norwood House is a wood framed dwelling composed of a two story gable roofed main block and a two story gable roofed rear ell, with a one story shed roofed addition filling in the space bordered by the arms of the ell. Corrugated metal stripping conceals the foundation below clapboard covered exterior walls. Composite shingles sheathe the roof slopes, where two concrete block chimneys rise from the ridge, one at the eastern end of the main block and one at the northern end of the rear ell. The southeastern elevation faces Route 9 and forms a three bay facade. On the first story of the facade a four light sash entrance door is centered between 2/2 sash windows, and the three bays of the second story consist of squared 2/2 sash windows. On the gable end elevations of the main block, facing northeast and southwest, there are no windows. On the northeastern elevation of the rear ell a 1/1 sash window occupies the second story. On the southwestern



Plate 18. Martha Norwood House (3-34-5-139), From the South.



Plate 19. Beatrice Wiltbanks House (3-34-5-189), From the Southeast.

elevation, a 1/1 sash window and sash entrance door are located in the one story shed roofed addition. In the second story of the rear ell on the southwestern elevation is a 1/1 sash window. Doors and windows are set in plain surrounds, each with a small hood mold. A small wood framed, screened porch is located on the northeast elevation at the juncture of the main block and the rear ell. One outbuilding stands on this property, a one story rectangular wood framed shed. Located to the northwest of the dwelling, the shed has walls covered with vertical boards and a gable roof covered with corrugated metal. The door, on the eastern elevation, is constructed of vertical boards.

Beatrice Wiltbanks House c. 1930s
Route 285 (tax map #3-34-5-189)
Figure 36; Plate 19
CRS #S-901

Description: The Beatrice Wiltbanks House is single story wood framed dwelling with a gabled roof and masonry foundation. Gable ends have been clipped on the side elevations. The street facade is arranged in three bays with a central door sheltered by a small porch. The porch roof also has a clipped gable end. Windows are regularly placed, each sheltered by a metal awning. Walls and roof are sheathed in composite siding.

Elsie Brittingham House c. 1930s
Route 285 (tax map #3-34-5-190)
Figure 36; Plate 20
CRS #S-8010

Description: The Elsie Brittingham House is a two story wood framed dwelling, two bays wide and three bays deep, with a gabled roof. Most windows are 6/1 sash. A single car garage and porch, sharing a shed roof, adjoin the street facade at its left side. An enclosed porch with a gabled roof adjoins the north elevation. A simple brick chimney rises outside the north wall of the dwelling.

Lucille I. Williams House late 19th c.
136 Route 9 (tax map #3-34-5-193)
Figure 36; Plate 21
CRS #S-888

Description: The Lucille I. Williams House is a wood framed dwelling composed of a two story gable roofed main block and a two story gable roofed rear ell, to which an enclosed one story shed roofed front porch and an enclosed one story shed roofed rear porch have been added. Above the concrete block foundation the walls are clad in metal siding. Composite shingles cover all the roof slopes, and a brick chimney is centered on the ridge of the main block roof. The northwestern elevation of the main block faces Route 9 and forms a three bay facade. Above



Plate 20. Elsie Brittingham House (3-34-5-190), From the Southeast.



Plate 21. Lucille I. Williams House (3-34-5-193), From the Northwest.

the enclosed front porch, three 2/2 sash windows are arranged symmetrically, trimmed with louvered metal shutters. On the facade of the enclosed porch an axial sash entrance door is flanked by three 2/2 sash windows on each side. Three 2/2 sash windows occupy both the northeastern and southwestern elevations of the enclosed porch. The northeastern elevation of the main block has one 1/1 sash window at the northern end of the first story. One 1/1 sash window can be seen on both the first and the second story of the rear ell. There are two 1/1 sash windows on the first story of the southwestern elevation of the main block, and one 3/6 sash window on the second story of the southwestern elevation of the rear ell. Two pairs of 2/2 sash windows and an entrance door occupy the southwestern elevation of the enclosed rear porch, which extends across the southwestern and the southeastern elevations of the rear ell. One outbuilding stands on this property, a rectangular one story, wood framed shed. The shed is located to the south of the house, at the end of a driveway which parallels the southwest elevation of the dwelling. The walls of the shed are covered with brick patterned sheathing paper, and the shed roof is covered with composite shingles.

Mauil Heirs House late 19th c.
Alley between Routes 9 and 285 (tax map #3-34-5-194)
Figure 36; Plate 22
CRS #S-890

Description: The Mauil Heirs House is a wood framed ell-plan dwelling composed of two gable roofed two story sections joined to form an ell, with a one story shed roofed addition filling in most of the space enclosed by the ell. No foundation is visible below the clapboard covering the exterior walls. On the southwestern elevation of the main block, which faces the alley and forms the facade, the entrance door is a modern paneled replacement with three lights. The door is located to the southeast of the center of the facade, with two 2/2 sash windows to the northwest and one 2/2 sash window to the southeast. Directly above the three first story windows are three square, two light sash windows on the second story. On the southeastern elevation, a gable end, one square two light sash window is centered in the gable above a 2/2 sash window on the first story. Extending the northwestern elevation of the main block to the northeast is the two story rear ell, containing 6/2 sash windows on the first story and 3/3 casement windows on the second story. The window and door openings are trimmed with plain surrounds, including the louvered windows in the one story shed roofed addition. Composite shingles cover all the slopes of the roof. Two corbeled brick chimneys rise from the ridges of the gabled roofs, one near the west end of the main block and one near the northwest end of the rear ell.



Plate 22. Maul Heirs House (3-34-5-194), From the Southeast.



Plate 23. Garland R. Briscoe House (3-34-5-196), From the Southeast.

Garland R. Briscoe House c. 1910
Route 285, Box 26 (tax map #3-34-5-196)
Figure 36; Plate 23
CRS #S-902

Description: The Garland R. Briscoe House is a two and a half story wood framed, hip roofed square dwelling set on a concrete block foundation. Covering the front or northwestern slope of the roof are wooden shingles; the other slopes are covered in composite shingles. A gable roofed dormer covered with clapboarding occupies the center of the northwestern slope of the roof, and a corbeled brick chimney rises from the southeastern slope near the peak. Vertical board paneling sheathes the walls both of the main block of the house and of the one story hip roofed enclosed front porch. Six 1/1 sash windows flank the front porch door. On the facade elevation of the house, the four light sash entrance door is flanked by two 5 vertical/1 sash windows, set below two 3/1 sash windows on the second story. This pattern is repeated on the southwestern elevation, where two 3/1 sash windows occupy the second story and one 5/1 sash occupies the first story. On the northeastern elevation, however, the second story windows are 1/1 and 2/2 sash while the first story window is 5/1 sash. All the windows have plain surrounds with a molding strip atop the lintels, forming a small hood mold. A second enclosed porch is located on the rear elevation and at the easternmost end of the northeastern elevation. One outbuilding stands on this property, a garage in deteriorated condition. Located to the northeast of the house and accessed by an alley which parallels the southwest elevation of the dwelling, the rectangular one story frame garage is set on concrete block piers and is covered with vertical board paneling. A gable roof is sheathed in corrugated metal.

Virginia Williams House mid 19th c.
Route 285 (tax map #3-34-5-197)
Figure 36; Plate 24
CRS #S-903

Description: The Virginia Williams House is a two and a half story wood framed dwelling with a steeply pitched gabled roof and an adjoining rear wing of similar form and materials. The street facade is three bays wide with a door in the lower left side. Windows are 2/2 sash. The exterior is sheathed in claboard siding. A simple brick chimney rises inside the north wall of the main block and another inside the west wall of the wing. The building is abandoned and in poor condition.



Plate 24. Virginia Williams House (3-34-5-197), From the Southeast.

William Holloman House c. 1920s
Route 285 (tax map #3-34-5-198)
Figure 36; Plate 25
CRS #S-8013

Description: The William Holloman House is a one and a half story wood framed dwelling, three bays wide and one bay deep, with a gabled roof. It also has a central dormer facing the street, a shed roofed enclosed porch, and several wings and additions to the rear. The exterior is sheathed in metal siding and the roof in composite shingles.

Irwin A. Coursey House c. 1920s
Route 9 (tax map #3-34-5-202)
Figure 36; Plate 26
CRS #S-887

Description: The Irwin A. Coursey House is a rectangular one and a half story wood framed house with a gabled roof. Concrete block makes up the foundation, and the overhanging roof with exposed rafter ends is covered with composite shingles. The northern gable end elevation faces Route 9 and forms the facade, with a shed roofed screened porch covering the three bays of the first story. Above the front porch roof the peak of the gable is covered in clapboarding around a paired 1/1 sash window. The remaining exterior wall surface is clad in metal siding. An axial screened door gives access to the front which features turned wooden posts and railings with turned wooden balusters. The axial sash entrance door to the main block is set between 1/1 sash windows. On the western elevation, two 1/1 sash windows are symmetrically placed, while four 1/1 sash windows are located on the eastern elevation. Window and door openings are set in molded surrounds. On the southern elevation, a gable roofed addition occupies the eastern half of the first story, adjoining a small screened porch on the west. A corbeled brick chimney rises from the ridge of the main block, to the north of the midpoint. One outbuilding stands on this property, a square wood frame privy. Located to the north of the dwelling, the privy walls are covered with vertical board siding and the shed roof in composite shingles.

Robert Cropper House c. 1920s
Route 9 (tax map #3-34-5-204)
Figure 36; Plate 27
CRS #S-8014

Description: The Robert Cropper House is a one and a half story wood framed dwelling with a gabled roof, the rectangular main block and one story rear addition forming an ell plan. Above a brick foundation the walls of the main block are covered in wood clapboarding, while unfinished plywood sheathes the walls of the addition. The overhanging gable roofs of the main block and the



Plate 25. William Holloman House (3-34-5-198), From the Southeast.



Plate 26. Irwin A. Coursey House (3-34-5-202), From the Northwest.



Plate 27. Robert Cropper House (3-34-5-204), From the Northwest.



Plate 28. Jeroy Carter House (3-34-5-208), From the Northwest.

addition have exposed rafter ends and are covered with composite shingles. A corbeled chimney rises from the midpoint of the ridge of the main block roof, and a second ridge chimney is centered on the roof on the rear addition. On the northern gable end elevation, which faces Route 9 and forms the facade, a shed roofed screened porch covers the three bays of the first story. Centered in the gable above the porch roof is a paired 1/1 sash window. An axial screen door set between turned wood posts is featured on the front porch, with an axial sash entrance door set between 1/1 sash windows in the main block facade within. The western elevation contains one three light louvered window and one 1/1 sash window in the main block. An entrance door occupies the northernmost end of the western elevation of the rear addition, near the juncture with the main block. In the eastern elevation are located three 1/1 sash windows and one single light casement window. All the window and door openings are set in plain surrounds with molding atop the lintels to form hood molds. Two outbuildings stand on this property, a shed and a privy. The one story rectangular wood framed shed has walls and shed roof covered with corrugated metal, a sash entrance door on the eastern elevation, and 1/1 sash windows on the eastern and northern elevations. The square frame privy has plywood sheathing on the walls and composite shingles on the shed roof. Both outbuildings are located to the southwest of the dwelling.

Jeroy Carter House c. 1920s
Route 9 (tax map #3-34-5-208)
Figure 36; Plate 28
CRS #S-885

Description: The Jeroy Carter House is a rectangular one story wood framed dwelling, sited with the northwestern gable and elevation facing Route 9. Corrugated metal covers the foundation below walls sheathed in both composite shingles and brick cladding. The gable roof, covered with composite roofing material, has a slight overhang. On the northwestern elevation or facade an axial sash entrance door is flanked by 1/1 sash windows below a boarded window in the peak of the gable. On the southwestern side elevation, the westernmost two-thirds of the wall is covered with composite shingle cladding and contains one 1/1 sash window. The southernmost one-third of the southwestern elevation is covered with composite brick sheathing, and contains one 1/1 sash window and an entrance door at the southernmost end. Three 1/1 sash windows are symmetrically placed in the northeastern elevation. All window and door openings are set in plain surrounds. An exterior concrete block chimney rises next to the southeastern elevation to the south of the roof ridge. Two outbuildings stand on this property, a shed covered with vertical board siding and a shed covered with clapboards. Both sheds are wood framed, rectangular and have gable roofs. The clapboard covered shed is located to the

southwest of the dwelling, and has garage doors on the northwestern elevation. The board siding covered shed is located to the southeast of the dwelling with a vertical board door at the northernmost corner of the western elevation.

Jeroy Carter House late 19th c.
Route 9 (tax map #3-34-5-208.1)
Figure 36; Plate 29
CRS #S-884

Description: The Jeroy Carter House is a three bay, two and a half story wood framed block with a gabled roof. An enclosed porch with a hipped roof adjoins the street facade, while a two story wing adjoins the rear of the block. Windows are 1/1 sash, some with shutters intact. The exterior is sheathed in composite siding and roofing.

John H. Maker House mid 19th c.
Route 285 (tax map #3-34-5-210)
Figure 36; Plate 30
CRS #S-904

Description: The John H. Maker House is a two story wood framed gable roofed dwelling, composed of a main block and a rear ell which together create an ell plan. Above the concrete block foundation the walls are covered with composite shingles. On the overhanging roof, sheathed with composite shingles, two corbeled brick chimneys rise from the ridge: one to the southwest of center on the main block, and one at the northwest end of the rear ell. On the southeastern elevation, which faces Route 285 and forms the facade, four window openings are symmetrically placed. Two square 2/2 sash windows occupy the second story and two 1/1 sash windows occupy the first story. The four light sash entrance door is located northeast of the center of the facade. On the gable ends of the main block, sash windows are set in the peak of the gable: on the southwestern elevation, a 4/4 sash window, and on the northeastern, a 2/2 sash window. The northeastern elevation of the ell has a 2/2 sash window on the first story with a 3/3 casement window on the second story. One outbuilding stands on this property, a one story square wood framed shed. Located to the north of the dwelling at the end of a driveway which parallels the northeast elevation of the house, the shed has a corrugated metal covered shed roof and walls that are sheathed in plywood.



Plate 29. Jeroy Carter House (3-34-5-208.1), From the Northwest.



Plate 30. John H. Maker House (3-34-5-210), From the South.

Hattie Burton House late 19th c.
Route 285 (tax map #3-34-5-211)
Figure 36; Plate 31
CRS #S-905

Description: The Hattie Burton House is a two story wood framed block, two bays wide and two bays deep, with a steeply pitched gabled roof. A two story wing adjoins the north wall. Windows are regularly placed 2/2 sash, flanked by shutters. The exterior is clad in clapboard siding and composite roofing.

George W. Tunnell House c. 1920s
NW corner Route 285 and Church Road (tax map #3-34-5-212)
Figure 36; Plate 32
CRS #S-906

Description: The George W. Tunnell House is a rectangular one story wood framed dwelling set on a concrete block foundation. An overhanging gable roof, sheathed in corrugated metal, shelters the exterior walls, which are covered with vertical board paneling. A one story shed roofed addition extends from the northern or rear elevation. The southern elevation is a gable end that faces the street and forms a two bay facade consisting of a paneled entrance door and a 6/6 sash window, both set in plain surrounds. On the western elevation are three 6/6 sash windows and an axial concrete block chimney, while one 6/6 window is centered on the eastern elevation. Two outbuildings stand on this property, a shed and a privy. The rectangular wood framed shed is located to the northwest of the dwelling, the exterior walls covered with horizontal flush boarding and the shed roof with corrugated metal. A paneled entrance door occupies the northern end of the eastern elevation of the shed. The walls of the rectangular wood framed privy are covered with plywood, the roof with corrugated metal. The privy is located to the northeast of the dwelling.

The Paynter B. Ward House late 19th c.
Route 9 (tax map #3-34-5-214)
Figure 36; Plate 33
CRS #S-883

Description: The Paynter B. Ward House is a rectangular two and a half story wood framed dwelling, three bays wide and two bays deep, with a one story shed roofed addition on the southeastern or rear elevation. Wooden clapboards cover the walls above a CMU foundation, and the overhanging gabled roof with exposed rafter ends is sheathed with composite shingles. On the northwestern elevation or facade the entrance door occupies the westernmost of the three bays, and contains one large light. Two 1/1 light sash windows are located in the two remaining bays of the first story, and three 1/1 light sash windows are arranged symmetrically on the second story. On the northeastern