

DRAFT  
NOT FOR BIDDING  
AUGUST 2015

**PLAN - SWM BMP NO. 720 STA. 712+50 TO STA 720+50, WET POND**  
SCALE: 1" = 30'

BMP NO. 720 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	63.00	15.44
1-YEAR	24.0	1.0	63.35	1.74
10-YEAR	58.3	8.5	63.69	3.46
100-YEAR	112.30	32.0	64.14	5.80

HAZARD CLASSIFICATION "A" AS PER POND CODE 378  
 DRAINAGE AREA TO FACILITY: 25.47 ACRES  
 MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.  
 SEE SHEET SW-04 FOR NOTES.

M:\31653\000\CONTRACT 1A\CADD\SW01-720\301\_1A.dgn 2/2/2015 12:23 PM



ADDENDUMS / REVISIONS




**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT PLAN  
BMP 720**

SW-01
SHEET NO. 622
TOTAL SHTS. 875



DRAFT  
NOT FOR BIDDING  
AUGUST 2015

**STAKEOUT PLAN - SWM BMP NO. 720 STA. 712+50 TO STA. 720+50, WET POND**  
SCALE: 1" = 30'

**P254 BASELINE  
STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
FES240	STA.60+58.40	552356.40	578797.57
FES241	STA.61+03.26	552398.54	578782.18

**EMBANKMENT BASELINE "A"  
STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
1	POB STA.10+00.00	551596.17	578652.16
2	PI STA.10+61.00	551594.41	578713.13
3	PI STA.11+00.13	551593.27	578752.24
4	PI STA.12+19.29	551573.92	578869.82
5	PI STA.12+44.54	551569.82	578894.74
6	PC STA.13+85.54	551546.92	579033.87
7	PT STA.15+05.01	551617.06	579110.40
8	PC STA.21+19.49	552229.76	579063.63
9	PT STA.21+63.47	552269.95	579047.51
10	PC STA.22+16.60	552311.03	579013.81
11	PT STA.22+54.85	552332.93	578983.00
12	PC STA.23+47.47	552364.91	578896.08
13	PT STA.24+01.18	552375.05	578843.56
14	PI STA.25+09.01	552378.16	578735.79
15	POE STA.25+70.01	552379.92	578674.81

**BASELINE "B" 30" RCP  
STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
16	POB STA.30+00.00	551625.75	578653.01
17	PI STA.30+61.00	551623.99	578713.99
18	PI STA.31+16.16	551622.40	578769.13
19	PI STA.31+67.95	551674.19	578769.20
20	PI STA.32+06.95	551685.01	578806.67
26	POE STA.32+43.13	551715.69	578825.83

**BASELINE "D" 18" RCP  
STAKEOUT INFORMATION**


POINT NO.	STATION	NORTHING	EASTING
33	POB STA.50+00.00	551622.51	578765.37
34	PI STA.50+73.98	551552.16	578742.47
35	POE STA.51+03.00	551523.15	578741.67

**BASELINE "C" 30" RCP  
STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
21	POB STA.40+00.00	551521.59	578892.18
22	PI STA.40+35.86	551555.15	578879.53
23	PI STA.40+92.65	551611.18	578888.75
24	PI STA.41+22.65	551635.25	578906.66
25	PI STA.41+48.34	551660.94	578906.87
26	PI STA.42+46.14	551715.69	578825.83
27	PI STA.43+68.33	551837.44	578815.43
28	PI STA.44+71.18	551934.25	578850.13
29	PI STA.47+03.71	552166.52	578839.11
30	PI STA.47+36.14	552198.93	578837.91
31	PI STA.47+94.14	552255.77	578826.41
32	POE STA.49+13.88	552375.38	578832.11



ADDENDUMS / REVISIONS




**US 301,  
SR 896 TO SR 1**

CONTRACT	BRIDGE NO.
T200911308	DESIGNED BY: DLH
COUNTY	CHECKED BY: JDC
NEW CASTLE	

**STORMWATER  
STAKEOUT PLAN  
BMP 720**


SW-02
SHEET NO.
623
TOTAL SHTS.
875



PROFILE - POND EMBANKMENT - BMP 720 BASELINE "A"

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'

MATCH LINE STA. 18+50  
SEE THIS SHEET




PROFILE - POND EMBANKMENT - BMP 720 BASELINE "A"

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'


MATCH LINE STA. 18+50  
SEE THIS SHEET

DRAFT  
NOT FOR BIDDING




PROFILE - BMP 720 BASELINE "B"

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'



PROFILE - BMP 720 BASELINE "D"

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'




POND MAINTENANCE ACCESS ROAD  
SCALE: NONE

- RIPRAP NOTES:**
- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
  - THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

p:\1653-000\scott\fact\1a\cadd\SW03-712030-1A.dgn 3/2/2014 10:25:15 PM

ADDENDUMS / REVISIONS




**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC


**STORMWATER  
MANAGEMENT PROFILES  
BMP 720**

SW-03
SHEET NO. 624
TOTAL SHTS. 875



**PROFILE - BMP 720 BASELINE "C"**

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'



**PROFILE - FES 241 TO FES 240**

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'

**POND CONSTRUCTION SEQUENCE AND NOTES:**

THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:  
SECTION 271 - STORMWATER MANAGEMENT POND  
SECTION 272 - POND OUTLET STRUCTURE, CONCRETE

1. INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
2. CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
3. INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
4. CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
5. CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICES, DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
6. EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
7. STABILIZE ALL BARE AREAS BELOW ELEV. 64.00, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 64.00 WITH DRY SEED MIX.

**MAINTENANCE OF POND AS A SEDIMENT BASIN**

1. SEE SHEET CS-26 FOR SB720 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 63.44. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICES SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 63.00. THE COST OF THE BAFFLE AND SKIMMER DEVICES AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
2. CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
3. CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 63.21, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.

**CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**

1. CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
2. REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
3. PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICES AND PLYWOOD.

**GENERAL NOTES:**

1. THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
2. STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.


**RIPRAP NOTES:**

1. RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
2. THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

D:\projects\2009\11308\11308.dwg 11/20/09 11:25:35 AM



ADDENDUMS / REVISIONS	





**US 301,  
SR 896 TO SR 1**


CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT PROFILES  
BMP 720**


<b>SW-04</b>
SHEET NO. 625
TOTAL SHTS. 875




PLAN - SWM BMP NO. 720 WEIR WALL  
SCALE: 1/2" = 1'




ELEVATION - SWM BMP NO. 720 WEIR WALL  
SCALE: 1/2" = 1'



SECTION A-A  
SCALE: 3/4" = 1'-0"



SECTION B-B  
SCALE: 3/4" = 1'-0"




SECTION C-C  
SCALE: 3/4" = 1'-0"


WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
720 WW-WP-1	551573.4267	578869.7436
720 WW-WP-2	551569.3256	578894.6583

NOTES:

1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
2. KEYS ARE NOMINAL SIZE.
3. CONCRETE SHALL BE CLASS A, 4500 PSI.
4. RIPRAP NOT SHOWN FOR CLARITY.
5. E. F. = EACH FACE, E. S. = EQUAL SPACING.
6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
7. 6" GRADED AGGREGATE BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.



REINFORCEMENT DETAIL AT WEIR OPENING  
SCALE: 3/4" = 1'-0"



CONSTRUCTION JOINT DETAIL  
SCALE: 3/4" = 1'-0"

p:\31653-000\cadd\sw05-720\01-1A.dgn 10/31/2014 10:25:58 PM



**PLAN - SWM BMP NO. 722 STA. 726+50 TO STA. 730+00, WET POND**


SCALE: 1" = 30'

BMP NO. 722 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	66.50	0.34
1-YEAR	3.8	0.4	67.07	0.19
10-YEAR	11.5	2.2	67.76	0.47
100-YEAR	20.1	5.9	68.42	0.78

HAZARD CLASSIFICATION "A" AS PER POND CODE 378

DRAINAGE AREA TO FACILITY: 6.12 ACRES

MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.



**POND MAINTENANCE ACCESS ROAD**

SCALE: NONE

**GENERAL NOTES:**

1. THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
2. STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

**POND CONSTRUCTION SEQUENCE AND NOTES:**

- THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:
- SECTION 271 - STORMWATER MANAGEMENT POND
  - SECTION 272 - POND OUTLET STRUCTURE, CONCRETE
1. INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  2. CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
  3. INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  4. CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
  5. CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICE. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
  6. EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVER EXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
  7. STABILIZE ALL BARE AREAS BELOW ELEV. 67.50, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 67.50 WITH DRY SEED MIX.


**MAINTENANCE OF POND AS A SEDIMENT BASIN**

1. SEE SHEET CS-29 FOR SB722 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 67.83. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICE SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 66.50. THE COST OF THE BAFFLE AND SKIMMER DEVICE AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
2. CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
3. CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 67.24, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.

**CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**

1. CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
2. REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
3. PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICE AND PLYWOOD.

M:\31653\000\CONTRACT\14\CADD\SW06-730U301\_1A.dgn 2/2/2015 12:42:55 AM



**STAKEOUT PLAN - SWM BMP NO. 722 STA. 726+50 TO STA. 730+00, WET POND**  
 SCALE: 1" = 30'

EMBANKMENT BASELINE "A" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
1	POB STA.10+00.00	552986.60	578719.27
2	PI STA.10+61.00	552975.94	578779.33
3	PC STA.10+94.16	552970.14	578811.98
4	PT STA.12+17.01	553011.20	578921.63
5	PI STA.12+19.63	553013.24	578923.27
6	PI STA.12+44.63	553032.71	578938.96
7	PC STA.12+47.25	553034.75	578940.60
8	PT STA.13+30.11	553112.23	578963.36
9	PC STA.14+45.46	553226.92	578951.03
10	PT STA.14+75.50	553250.56	578934.58
11	PC STA.14+97.32	553260.30	578915.06
12	PT STA.15+27.82	553286.10	578904.18
13	PI STA.15+31.20	553289.32	578905.21
14	PI STA.15+77.40	553303.61	578861.27
15	POE STA.16+38.40	553322.47	578803.26

ACCESS ROAD BASELINE "B" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
16	POE STA.20+00.00	553066.27	578734.76
17	PI STA.20+61.00	553053.66	578794.44
18	PC STA.21+14.10	553042.68	578846.39
19	PT STA.21+27.60	553035.80	578857.71
20	PC STA.21+50.81	553017.87	578872.44
21	PT STA.21+66.56	553004.33	578880.36
22	POE STA.21+89.23	552983.21	578888.61

ACCESS ROAD BASELINE "C" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
23	POB STA.30+00.00	553170.30	578759.07
24	PC STA.30+62.10	553154.88	578819.23
25	PT STA.31+02.50	553164.60	578856.69
26	PC STA.31+27.33	553181.69	578874.70
27	PT STA.31+53.41	553192.44	578897.96
28	POE STA.32+09.86	553198.48	578954.08

BASELINE "D" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
29	POB STA.40+00.00	553022.54	578725.92
30	PI STA.40+61.00	553010.99	578785.82
31	PI STA.41+10.15	553001.69	578834.08
32	PI STA.41+89.27	553051.89	578895.24
33	PI STA.42+51.38	553012.92	578943.59
34	POE STA.42+79.33	552988.33	578956.88

p:\31653-000\contract\1a\cadd\SW07-730U301-1A.dgn  
 07/27/2014 14:40:06 PM



ADDENDUMS / REVISIONS	







**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT  
STAKEOUT PLAN  
BMP 722**

<b>SW-07</b>
SHEET NO. 628
TOTAL SHTS. 875



**RIPRAP NOTES:**

- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
- THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

DRAFT


NOT FOR BIDDING

AUGUST 2015

p:\1653-000\stormfact\1a\cadd\SW08-730U301-1A.dgn  
 07/27/2014 14:41 PM



ADDENDUMS / REVISIONS	





US 301,  
SR 896 TO SR 1

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC


<b>STORMWATER MANAGEMENT PROFILES BMP 722</b>	SHEET NO. 629
	TOTAL SHTS. 875

SW-08







PLAN - SWM BMP NO. 722 WEIR WALL  
SCALE: 1/2" = 1'-0"



ELEVATION - SWM BMP NO. 722 WEIR WALL  
SCALE: 1/2" = 1'



SECTION A-A  
SCALE: 3/4" = 1'-0"




SECTION B-B  
SCALE: 3/4" = 1'-0"

DRAFT  
NOT FOR BIDDING  
AUGUST 2015

WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
722 WW-WP-1	553012.9282	578923.6624
722 WW-WP-2	553032.3937	578939.3499

- NOTES:**
1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
  2. KEYS ARE NOMINAL SIZE.
  3. CONCRETE SHALL BE CLASS A, 4500 PSI.
  4. RIPRAP NOT SHOWN FOR CLARITY.
  5. E.F. = EACH FACE, E.S.=EQUAL SPACING.
  6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
  7. 6" GRADED AGGREGATE BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.



ADDITIONAL REINFORCEMENT AT WEIR WALL OPENING  
SCALE: 3/4" = 1'

p:\31653-000\contract\to\cadd\sw09-7300301-1A.dgn 09/27/2014 10:45:15 PM




ADDENDUMS / REVISIONS	

US 301,  
SR 896 TO SR 1

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: HQ
	CHECKED BY: JAG

STORMWATER  
MANAGEMENT DETAILS  
BMP 722

SW-09
SHEET NO. 630
TOTAL SHTS. 875



**PLAN - SWM BMP NO. 723 STA. 735+50 TO STA. 740+00, WET POND**


SCALE: 1" = 30'

BMP NO. 723 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	71.00	0.38
1-YEAR	6.3	0.5	71.92	0.30
10-YEAR	19.9	3.4	73.05	0.82
100-YEAR	43.4	11.8	74.34	1.66

HAZARD CLASSIFICATION "A" AS PER POND CODE 378

DRAINAGE AREA TO FACILITY: 8.89 ACRES

MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.



**POND MAINTENANCE ACCESS ROAD**

SCALE: NONE

**GENERAL NOTES:**

- THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
- STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

**POND CONSTRUCTION SEQUENCE AND NOTES:**

THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:

- SECTION 271 - STORMWATER MANAGEMENT POND
  - SECTION 272 - POND OUTLET STRUCTURE, CONCRETE
- INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
  - INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
  - CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICE. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
  - EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
  - STABILIZE ALL BARE AREAS BELOW ELEV. 72.00, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 72.00 WITH DRY SEED MIX.


**MAINTENANCE OF POND AS A SEDIMENT BASIN**

- SEE SHEET CS-30 FOR SB723 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 72.92. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICE SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 71.00. THE COST OF THE BAFFLE AND SKIMMER DEVICE AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
- CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
- CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 72.09, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.

**CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**

- CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
- REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
- PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICE AND PLYWOOD.

M:\31653\000\CONTRACT\14\CADD\SW10-738U301-1A.dgn 2/2/2015 12:28:46 AM



**STAKEOUT PLAN - SWM BMP NO. 723 STA. 735+50 TO STA. 740+00, WET POND**

DRAFT

NOT FOR BIDDING

AUTOMATIC 2015

EMBANKMENT BASELINE "A" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
1	POB STA.10+00.00	553830.81	579034.09
2	PI STA.10+61.02	553798.29	579085.72
3	PC STA.11+18.00	553767.93	579133.94
4	PT STA.11+50.96	553770.90	579164.42
5	PC STA.12+03.22	553806.76	579202.42
6	PT STA.12+64.26	553844.14	579250.56
7	PI STA.12+68.19	553846.24	579253.89
8	PI STA.12+83.39	553853.51	579267.24
9	PI STA.12+98.59	553860.78	579280.59
10	PI STA.12+99.58	553861.26	579281.46
11	PC STA.13+13.48	553866.54	579294.31
12	PT STA.14+24.10	553955.38	579346.39
13	PC STA.14+80.29	554011.6	579339.63
14	PT STA.15+41.03	554069.17	579353.01
15	PI STA.15+66.91	554090.90	579367.05
16	PI STA.16+29.47	554143.62	579400.74
17	PI STA.16+78.96	554176.64	579363.88
18	POE STA.17+39.96	554217.33	579318.43


ACCESS ROAD BASELINE "B" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
19	POB STA.20+00.00	553812.41	579208.57
20	PI STA.20+27.53	553832.90	579190.18
21	PI STA.20+38.53	553839.48	579181.36
22	PI STA.20+43.53	553842.46	579177.35

ACCESS ROAD BASELINE "C" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
23	POB STA.30+00.00	554049.86	579181.05
24	PI STA.30+61.00	554013.71	579230.19
25	PC STA.31+09.36	553983.82	579268.19
26	PT STA.31+33.75	553977.41	579291.08
27	PI STA.31+42.53	553978.47	579299.79
28	POE STA.31+86.01	553983.69	579342.96

BASELINE "D" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
29	POB STA.40+00.00	553856.94	579049.90
30	PI STA.40+61.00	553825.06	579101.91
31	PI STA.41+61.30	553796.15	579149.06
32	PI STA.42+06.93	553868.80	579203.23
33	PI STA.43+29.75	553939.56	579303.63
34	PI STA.43+51.77	553961.50	579301.85
35	PI STA.43+93.02	554002.46	579296.89
36	POE STA.45+18.45	554103.28	579222.26

BASELINE "E" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
37	POB STA.50+00.00	553897.17	579243.49
38	POE STA.50+88.46	553819.47	579285.76

ADDENDUMS / REVISIONS






US 301,  
SR 896 TO SR 1

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC



**STORMWATER  
MANAGEMENT  
STAKEOUT PLAN  
BMP 723**

SW-11
SHEET NO. 632
TOTAL SHTS. 875



**PROFILE - ACCESS ROAD - BMP 723 BASELINE "B"**  
 SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'

**PROFILE - BMP 723 BASELINE "D"**  
 SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'



**PROFILE - ACCESS ROAD - BMP 723 BASELINE "C"**  
 SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'


**PROFILE - BMP 723 BASELINE "E"**  
 SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'

- RIPRAP NOTES:**
- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
  - THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

P:\653-000\contract\1a\cadd\SW12-738050-1A.dgn  
 2015/08/14 14:56 PM



ADDENDUMS / REVISIONS	




**US 301,  
 SR 896 TO SR 1**


CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC

**STORMWATER  
 MANAGEMENT  
 PROFILES  
 BMP 723**

SW-12
SHEET NO. 633
TOTAL SHTS. 875



PLAN - SWM BMP NO. 723 WEIR WALL  
SCALE: 1/2" = 1'




ELEVATION - SWM BMP NO. 723 WEIR WALL  
SCALE: 1/2" = 1'


WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
723 WW-WP-1	553845.8061	579254.1284
723 WW-WP-2	553860.3443	579280.8267

**NOTES:**


1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
2. KEYS ARE NOMINAL SIZE.
3. CONCRETE SHALL BE CLASS A, 4500 PSI.
4. RIPRAP NOT SHOWN FOR CLARITY.
5. E.F. = EACH FACE, E.S. = EQUAL SPACING.
6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
7. 6" GRADED AGGREGATE BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.




ADDITIONAL REINFORCEMENT AT WEIR WALL OPENING  
SCALE: 3/4" = 1'



SECTION A-A  
SCALE: 3/4" = 1'-0"




SECTION B-B  
SCALE: 3/4" = 1'-0"



CONSTRUCTION JOINT DETAIL  
SCALE: 3/4" = 1'-0"

p:\31653-000\contract\1a\cadd\SW13-738U301-1A.dgn 09/27/2014 14:52:58 PM



**PLAN - SWM BMP NO. 725 STA. 749+50 TO STA. 752+50, WET POND**


SCALE: 1" = 30'

BMP NO. 725 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	62.00	0.77
1-YEAR	5.1	0.5	62.53	0.20
10-YEAR	16.9	3.4	63.50	0.59
100-YEAR	37.6	13.4	64.73	1.16

HAZARD CLASSIFICATION "A" AS PER POND CODE 378

DRAINAGE AREA TO FACILITY: 7.23 ACRES

MANAGEMENT PROVIDED BY THE FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.



**POND MAINTENANCE ACCESS ROAD**

SCALE: NONE

**GENERAL NOTES:**

- THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
- STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

**POND CONSTRUCTION SEQUENCE AND NOTES:**

THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:

- SECTION 271 - STORMWATER MANAGEMENT POND
- SECTION 272 - POND OUTLET STRUCTURE, CONCRETE

- INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
- CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
- INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
- CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
- CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICE. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN THE FIELD.
- EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
- STABILIZE ALL BARE AREAS BELOW ELEV. 63.00, EXCLUDING POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 63.00 WITH DRY SEED MIX.


**MAINTENANCE OF POND AS A SEDIMENT BASIN**

- SEE SHEET CS-32 FOR SB725 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 63.60. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICE SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 62.00. THE COST OF THE BAFFLE AND SKIMMER DEVICE AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
- CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
- CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 62.80, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.

**CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**

- CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
- REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
- PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICE AND PLYWOOD.

M:\31653\000\CONTRACT\14\CADD\SWM\752U301\_1A.dgn 7/29/2015 12:29:25 AM



**PLAN - SWM BMP NO. 725 STA. 749+50 TO STA. 752+50, WET POND**  
SCALE: 1" = 30'

**ACCESS ROAD BASELINE "A" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
1	POB STA.10+00.00	554891.36	580305.80
2	PI STA.10+73.59	554958.62	580275.91
3	PC STA.10+99.09	554967.77	580252.12
4	PT STA.11+20.91	554970.98	580230.71
5	PI STA.11+36.63	554969.90	580215.02
6	PC STA.12+12.50	554964.66	580139.34
7	PT STA.12+42.50	554976.67	580113.20
8	PI STA.13+01.67	555024.13	580077.86
9	PI STA.13+16.09	555035.70	580069.26
10	PI STA.13+45.84	555058.16	580049.75
11	POE STA.13+75.94	555077.65	580026.82

**ACCESS ROAD BASELINE "B" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
5	POB STA.20+00.00	554969.90	580215.02
12	PC STA.20+81.95	555051.79	580218.12
13	PT STA.21+53.22	555110.52	580184.57
14	PI STA.21+58.47	555113.02	580179.94
15	PI STA.21+86.47	555126.32	580155.30
16	PC STA.21+89.65	555127.83	580152.51
17	PT STA.22+29.94	555129.67	580113.59
18	PC STA.22+97.39	555103.38	580051.48
19	PT STA.23+06.70	555097.92	580044.04
11	PI STA.23+33.30	555077.65	580026.82
20	POE STA.23+84.14	555038.91	579993.89

**BASELINE "C" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
21	POB STA.30+00.00	554880.32	580276.80
22	PI STA.31+59.86	555037.35	580246.83
23	PC STA.32+04.44	555081.13	580238.47
24	PT STA.32+19.87	555094.65	580231.02
25	PC STA.32+27.49	555101.02	580226.82
26	PT STA.32+49.55	555116.71	580211.52
27	PI STA.32+88.84	555139.14	580179.26
28	PI STA.33+05.19	555148.48	580165.83
29	PI STA.33+18.61	555156.31	580154.94
30	PI STA.33+38.51	555165.04	580137.06
31	POE STA.34+01.51	555164.05	580074.06

**BASELINE "D" STAKEOUT INFORMATION**





POINT NO.	STATION	NORTHING	EASTING
22	POB STA.40+00.00	555037.35	580246.83
32	PI STA.40+15.14	555041.26	580232.20
33	PI STA.40+85.16	555059.36	580164.56
34	POE STA.41+16.86	555074.42	580136.66

DRAFT

NOT FOR BIDDING

AUGUST 2015

p:\31653-000\contract\1a\card\SWIS-752U301-1A.dgn 2/2/2014 11:52:52 AM



- RIPRAP NOTES:**
- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
  - THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

p:\31653-000\scans\0510\1a\cadd\SWB-752U301\_1A.dgn  
 2017/05/14 14:20:03 PM



ADDENDUMS / REVISIONS	




**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC


**STORMWATER  
MANAGEMENT  
PROFILES  
BMP 725**

<b>SW-16</b>
SHEET NO. 637
TOTAL SHTS. 875






PLAN - SWM BMP NO. 725 WEIR WALL  
SCALE: 1/2" = 1'




ELEVATION - SWM BMP NO. 725 WEIR WALL  
SCALE: 1/2" = 1'

WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
725 WW-WP-1	555125.8816	580155.0648
725 WW-WP-2	555112.5809	580179.7041


- NOTES:**
1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
  2. KEYS ARE NOMINAL SIZE.
  3. CONCRETE SHALL BE CLASS A, 4500 PSI.
  4. RIPRAP NOT SHOWN FOR CLARITY.
  5. E.F. = EACH FACE, E.S. = EQUAL SPACING.
  6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
  7. THE CLAY CORE SHALL BE COMPACTED TO AT LEAST 95% OF THE LABORATORY MAXIMUM DENSITY AS DETERMINED BY AASHTO T99 METHOD C FOR A DISTANCE OF 5'-0" MINIMUM ON EITHER SIDE OF THE WEIR WALL FOOTING ALONG THE CENTERLINE OF EMBANKMENT/CLAY CORE.
  8. 6" GRADED AGGREGATE BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.




ADDITIONAL REINFORCEMENT AT WEIR WALL OPENING  
N. T. S.



CONSTRUCTION JOINT DETAIL  
SCALE: 3/4" = 1'-0"



SECTION A-A  
SCALE: 3/4" = 1'-0"




SECTION B-B  
SCALE: 3/4" = 1'-0"

P:\31653-000\contract\1a\cadd\SW17-720U30-1A.dgn  
 2023/08/14 14:25:10 PM

ADDENDUMS / REVISIONS	

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: HQ
	CHECKED BY: JAG

<b>SW-17</b>
SHEET NO. 638
TOTAL SHTS. 875



DRAFT

NOT FOR BIDDING

AUGUST 2015

**PLAN - SWM BMP NO. 731 STA. 783+50 TO STA. 790+00, WET POND**


SCALE: 1" = 40'

BMP NO. 731 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	50.00	7.40
1-YEAR	22.60	4.0	50.92	1.53
10-YEAR	79.90	30.3	52.13	3.93
100-YEAR	184.50	106.1	53.54	7.11

HAZARD CLASSIFICATION "A" AS PER POND CODE 378

DRAINAGE AREA TO FACILITY: 62.49 ACRES

MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.



**POND MAINTENANCE ACCESS ROAD**  
SCALE: NONE

**GENERAL NOTES:**


- THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
- STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

- POND CONSTRUCTION SEQUENCE AND NOTES:**  
THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:  
SECTION 271 - STORMWATER MANAGEMENT POND  
SECTION 272 - POND OUTLET STRUCTURE, CONCRETE
- INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
  - INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
  - CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICES. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
  - EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
  - STABILIZE ALL BARE AREAS BELOW ELEV. 51.00, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 51.00 WITH DRY SEED MIX.

- MAINTENANCE OF POND AS A SEDIMENT BASIN**
- SEE SHEET CS-18 FOR SB731 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 52.35. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICES SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 50.00. THE COST OF THE BAFFLE AND SKIMMER DEVICES AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
  - CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
  - CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 51.47, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.

- CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**
- CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
  - REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
  - PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICES AND PLYWOOD.

M:\31653\000\CONTRACT\14\CADD\SWB-787\U301-1A.dgn 15/08/2015 12:00:57 PM



**MAINTENANCE ROAD BASELINE "A" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
1	POB STA. 10+00.00	555499.72	583943.13
2	PI STA. 10+69.15	555430.60	583945.35
3	PC STA. 10+82.28	555417.48	583945.78
4	PT STA. 11+35.23	555372.16	583969.58
5	PC STA. 11+54.78	555352.62	583970.26
6	PRC STA. 11+74.83	555334.93	583978.49
7	PT STA. 12+57.93	555258.88	583995.94
8	PI STA. 12+70.72	555247.03	583991.14
9	PI STA. 12+88.71	555231.24	583982.51
10	PI STA. 13+27.90	555198.71	583960.65
11	PI STA. 14+08.46	555129.37	583919.65
12	PC STA. 15+05.60	555046.86	583868.36
13	PT STA. 15+33.44	555027.58	583848.66
14	PC STA. 15+79.25	555004.23	583809.24
15	PT STA. 16+80.98	555007.17	583712.89
16	PC STA. 18+59.53	555107.33	583565.08
17	PT STA. 19+12.77	555149.18	583533.77

**MAINTENANCE ROAD BASELINE "C" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
25	POB STA. 30+00.00	555327.20	583985.81
26	PI STA. 31+04.60	555318.12	583981.61
27	PC STA. 31+77.12	555311.82	583809.36
28	PT STA. 31+88.73	555311.55	583797.77
29	PI STA. 33+05.35	555316.29	583681.24
30	PC STA. 33+46.58	555275.44	583675.69
31	PT STA. 33+96.43	555242.84	583642.73
32	POE STA. 34+85.36	555231.86	583554.48

**MAINTENANCE ROAD BASELINE "B" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
18	POB STA. 20+00.00	555487.53	583720.10
19	PI STA. 20+71.85	555415.92	583725.83
20	PI STA. 21+03.04	555384.92	583729.29
21	PC STA. 21+54.16	555353.59	583769.68
22	PT STA. 21+65.96	555344.73	583777.36
23	PI STA. 21+92.27	555321.86	583790.38
24	POE STA. 22+02.28	555311.87	583789.98

**MAINTENANCE ROAD BASELINE "D" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
33	POB STA. 40+00.00	555495.49	583843.21
34	PI STA. 40+69.23	555426.33	583846.16
35	PI STA. 41+31.00	555364.61	583848.80
36	PI STA. 41+70.48	555340.03	583879.70
37	PI STA. 42+35.48	555275.28	583885.34
38	PI STA. 44+66.67	555061.18	583798.11
39	PC STA. 45+33.90	555003.33	583832.37
40	PT STA. 45+54.19	554983.91	583832.90
41	PI STA. 46+48.03	554900.66	583789.59
42	POE STA. 46+80.83	554877.41	583766.46

DRAFT

NOT FOR BIDDING


AUGUST 2015

**PLAN - SWM BMP NO. 731 STA. 783+50 TO STA. 790+00, WET POND**  
SCALE: 1" = 40'

D:\31653-000\swm\cadd\swm9-787\0301\_1A.dgn 11/23/14 11:23:50 AM



ADDENDUMS / REVISIONS	




**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: HMB
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT  
STAKEOUT PLAN  
BMP 731**


SW-19
SHEET NO. 640
TOTAL SHTS. 875

**RIPRAP NOTES:**  
 1. RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON/ITEMS 712020 AND 712021.  
 2. THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.



**PROFILE - BMP 731 BASELINE "A"**

SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'




**PROFILE - BMP 731 BASELINE "B"**

SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'

**PROFILE - BMP 731 BASELINE "C"**

SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'




**PROFILE - BMP 731 BASELINE "D"**

SCALE: HORIZONTAL: 1" = 30'  
 VERTICAL: 1" = 10'

P:\1653-000\stormwater\1a\cadd\SW20-787\U301\_1A.dgn  
 07/31/2014 14:23:37 PM



ADDENDUMS / REVISIONS	





**US 301,  
 SR 896 TO SR 1**


CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: C.R.H.
	CHECKED BY: JDC

**STORMWATER  
 PROFILES  
 BMP 731**

SW-20
SHEET NO. 641
TOTAL SHTS. 875




PLAN - SWM BMP NO. 787 WEIR WALL  
SCALE: 1/2" = 1'




ELEVATION - SWM BMP NO. 787 WEIR WALL  
SCALE: 1/2" = 1'

WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
731 WW-WP-1	555005.0486	583811.5986
731 WW-WP-2	555022.3718	583840.8498

- NOTES:**
1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
  2. KEYS ARE NOMINAL SIZE.
  3. CONCRETE SHALL BE CLASS A, 4500 PSI.
  4. RIPRAP NOT SHOWN FOR CLARITY.
  5. E. F. = EACH FACE, E. S. = EQUAL SPACING.
  6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
  7. 6" GRADED AGGREGATE BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.




ADDITIONAL REINFORCEMENT AT WEIR WALL OPENING  
SCALE: NOT TO SCALE



SECTION A-A  
SCALE: 3/4" = 1'

CONSTRUCTION JOINT DETAIL  
SCALE: 3/4" = 1'-0"




SECTION B-B  
SCALE: 3/4" = 1'

P:\31653-000\Drawings\SW\21-787\030-1A.dgn  
 2023/08/14 14:23:58 PM

ADDENDUMS / REVISIONS

CONTRACT	BRIDGE NO.
T200911308	DESIGNED BY: HQ
COUNTY	CHECKED BY: JAG
NEW CASTLE	



**PLAN - SWM BMP NO. 733, STA. 803+00 TO STA. 806+50, WET POND**


SCALE: 1" = 30'

BMP NO. 733 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	37.00	0.62
1-YEAR	5.6	0.6	37.79	0.30
10-YEAR	19.9	7.1	38.83	0.74
100-YEAR	45.7	18.3	40.40	1.55

HAZARD CLASSIFICATION "A" AS PER POND CODE 378

DRAINAGE AREA TO FACILITY: 11.22 ACRES

MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.



**POND MAINTENANCE ACCESS ROAD**  
SCALE: NONE

**GENERAL NOTES:**

- THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
- STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

**POND CONSTRUCTION SEQUENCE AND NOTES:**

- THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:
- SECTION 271 - STORMWATER MANAGEMENT POND
  - SECTION 272 - POND OUTLET STRUCTURE, CONCRETE
- INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
  - INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
  - CONSTRUCT POND OUTLET STRUCTURE, PRINCIPAL SPILLWAY AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF PRINCIPAL SPILLWAY. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICE. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
  - EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
  - STABILIZE ALL BARE AREAS BELOW ELEV. 38.00, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 38.00 WITH DRY SEED MIX.

**MAINTENANCE OF POND AS A SEDIMENT BASIN**

- SEE SHEET CS-21 FOR SB733 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENINGS IN ORDER TO FORM CREST AT ELEVATION 39.30. PLYWOOD SHALL BE AFFIXED TO RISER STRUCTURE USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICE SHALL BE ATTACHED TO THE PERMANENT 6" ORIFICE AT PERMANENT POOL ELEVATION 37.00. THE COST OF THE BAFFLES AND SKIMMER DEVICE AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
- CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
- CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 38.21, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.

**CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**


- CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
- REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
- PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, REMOVE SKIMMER DEWATERING DEVICE AND PLYWOOD, AND INSTALL CATCH BASIN TRAP.

M:\31653\000\CONTRACT\14\CADD\SW22-810\301-1A.dgn  
 5/2/2015 7:22:25 AM

DRAFT

NOT FOR BIDDING

AUGUST 2015



**STAKEOUT PLAN – SWM BMP NO. 733 STA. 802+50 TO STA. 806+50, WET POND**

SCALE: 1" = 30'

BASELINE "A" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
1	POB STA.10+00.00	555811.61	585411.01
2	PC STA.10+37.15	555776.52	585398.81
3	PT STA.10+72.06	555743.49	585404.28
4	PC STA.13+11.16	555555.01	585551.42
5	PT STA.13+71.98	555513.46	585595.50
6	POE STA.15+00.00	555440.76	585700.88

BASELINE "B" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
7	POB STA.20+00.00	555379.23	585494.73
8	PI STA.21+48.95	555527.28	585511.07
9	PI STA.21+68.79	555529.88	585491.40
10	PI STA.22+96.15	555630.27	585413.03
11	POE STA.24+16.41	555704.25	55507.84

BASELINE "C" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
12	POB STA.30+00.00	555585.07	585527.96
13	POE STA.30+85.00	555532.76	585460.96

ADDENDUMS / REVISIONS








**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT  
STAKEOUT PLAN  
BMP 733**


SW-23
SHEET NO. 644
TOTAL SHTS. 875



- RIPRAP NOTES:**
- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
  - THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.
  - THE ANTI-SEEP COLLAR AND MODIFIED CLASS A BEDDING SHALL BE MEASURED AND PAID AS ITEM 614738 "ANTI-SEEP COLLAR."

p:\1653-000\scen\figs\1a\cead\sw24-810U30\_1A.dgn  
 07/27/2014 14:20:05 PM

ADDENDUMS / REVISIONS




**US 301, SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC


**STORMWATER PROFILES BMP 733**

SW-24
SHEET NO. 645
TOTAL SHTS. 875







PLAN  
SCALE: 3/4" = 1' - 0"



VIEW A-A  
SCALE: 3/4" = 1' - 0"




VIEW B-B  
SCALE: 3/4" = 1' - 0"




SECTION E-E  
SCALE: 3/4" = 1' - 0"




TOP SLAB KEY DETAIL  
SCALE: 1" = 1' - 0"




CATCH BASIN TRAP  
N.T.S.




TRASH RACK 'D' - FRONT ELEVATION  
N.T.S.




TRASH RACK 'D' - SIDE ELEVATION  
N.T.S.




TOP SLAB - REINFORCEMENT PLAN  
SCALE: 3/4" = 1' - 0"



SECTION D-D  
SCALE: 3/4" = 1' - 0"



SECTION F-F  
SCALE: 3/4" = 1' - 0"




SECTION C-C  
SCALE: 3/4" = 1' - 0"

NOTES:

- E.F. = EACH FACE  
F.F. = FRONT FACE  
R.F. = REAR FACE
- MANHOLE STEPS NOT SHOWN IN SECTION VIEWS FOR CLARITY, SEE STANDARD CONSTRUCTION DETAILS FOR MANHOLE STEP DETAILS.
- TOP SLAB NOT SHOWN IN SECTIONS C-C THROUGH F-F FOR CLARITY.
- TOP SLAB SHALL BE PRECAST. A WATERSTOP SHALL BE PLACED BETWEEN THE PRECAST TOP SLAB AND THE CAST-IN-PLACE RISER STRUCTURE.
- PAYMENT FOR EXCAVATION, CONCRETE, REINFORCING STEEL, HOOD, WATERSTOP, TRASH RACK, AND ALL WORK ASSOCIATED WITH CONSTRUCTION OF STORMWATER MANAGEMENT RISER STRUCTURE WILL BE MADE UNDER ITEM 910007, POND OUTLET STRUCTURE, CONCRETE NO. 6.
- SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
- 6" GRADED AGGREGATED BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.

14-CADD-SW25-810U301-1A.dgn  
M:\31653\000\CONTRACT 7/2015  
7/2015 AM



**PLAN - SWM BMP NO. 734 STA. 824+00 TO STA. 829+00, WET POND**


SCALE: 1" = 30'

BMP NO. 734 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	30.00	2.94
1-YEAR	9.1	0.6	30.58	0.58
10-YEAR	27.7	3.3	31.47	1.52
100-YEAR	59.3	12.8	32.68	2.96

HAZARD CLASSIFICATION "A" AS PER POND CODE 378

DRAINAGE AREA TO FACILITY: 13.64 ACRES

MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUALITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.



**GENERAL NOTES:**

- THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
- STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

**POND CONSTRUCTION SEQUENCE AND NOTES:**

THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:

- SECTION 271 - STORMWATER MANAGEMENT POND
- SECTION 272 - POND OUTLET STRUCTURE, CONCRETE

- INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
- CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
- INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
- CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
- CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICES. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
- EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
- STABILIZE ALL BARE AREAS BELOW ELEV. 31.00, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 31.00 WITH DRY SEED MIX.

**MAINTENANCE OF POND AS A SEDIMENT BASIN**

- SEE SHEET CS-40 FOR SB734 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 31.35. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICES SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 30.00. THE COST OF THE BAFFLE AND SKIMMER DEVICES AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
- CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
- CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 30.69, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.


**CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**

- CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
- REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
- PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICES AND PLYWOOD.

M:\31653\000\CONTRACT\14\CADD\SW26-8300301\_1A.dgn  
 2/2/2015 7:54:47 AM

DRAFT

NOT FOR BIDDING



**STAKEOUT PLAN - SWM BMP NO. 734 STA. 802+50 TO STA. 806+50, WET POND**

SCALE: 1" = 30'

**EMBANKMENT BASELINE "A" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
1	POB STA. 10+00.00	55553.43	587781.50
2	PI STA. 10+61.00	555608.81	587755.94
3	PI STA. 10+86.00	555631.51	587745.47
4	PC STA. 11+32.95	555664.28	587711.85
5	PT STA. 11+83.49	555682.73	587666.15
6	PC STA. 12+28.88	555682.51	587620.77
7	PT STA. 12+57.68	555689.74	587593.22
8	PC STA. 13+98.32	555759.46	587471.08
9	PT STA. 14+81.05	555762.90	587391.51
10	PC STA. 15+58.29	555730.54	587321.38
11	PT STA. 16+77.67	555629.69	587284.21
12	PC STA. 17+44.72	555568.81	587312.30
13	PI STA. 18+64.83	555527.53	587413.34
14	PI STA. 19+21.20	555474.83	587433.35
15	POE STA. 19+82.20	555417.13	587453.13


**ACCESS ROAD BASELINE "B" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
16	POB STA. 20+00.00	555692.04	587589.19
17	POE STA. 20+77.49	555623.00	587554.00

**BASELINE "C" STAKEOUT INFORMATION**

POINT NO.	STATION	NORTHING	EASTING
18	POB STA. 30+00.00	555514.33	587696.74
19	PI STA. 30+61.00	555569.81	587671.38
20	PI STA. 31+27.46	555630.25	587643.75
21	PI STA. 31+93.28	555637.23	587578.30
22	PI STA. 32+37.63	555657.05	587538.62
23	PI STA. 32+71.39	555656.61	587504.87
24	PI STA. 33+99.94	555621.87	587381.10
25	PI STA. 34+27.94	555642.84	587362.55
26	PI STA. 34+64.45	555676.95	587375.56
27	PI STA. 35+07.74	555707.86	587405.88
28	PI STA. 35+80.05	555698.20	587477.54
29	PI STA. 36+11.90	555711.66	587506.40
30	POE STA. 36+80.20	555771.04	587540.29

ADDENDUMS / REVISIONS





**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: CRH
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT  
STAKEOUT PLAN  
BMP 734**

SW-27

SHEET NO.	648
TOTAL SHTS.	875




- RIPRAP NOTES:**
- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
  - THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

DRAFT  
NOT FOR BIDDING  
AUGUST 2015

p:\1653-000\swm\fact\1a\cadd\SW28-830U301-1A.dgn 10/3/2014 10:54:14 PM



ADDENDUMS / REVISIONS	




**US 301,  
SR 896 TO SR 1**


CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: CRH
	CHECKED BY: JDC

**STORMWATER  
MANAGEMENT PROFILES  
BMP 734**


<b>SW-28</b>
SHEET NO. 649
TOTAL SHTS. 875




**PLAN - SWM BMP NO. 734 WEIR WALL**  
SCALE: 1/2" = 1'



**ELEVATION - SWM BMP NO. 734 WEIR WALL**  
SCALE: 1/2" = 1'




**SECTION A-A**  
SCALE: 3/4" = 1'-0"




**SECTION B-B**  
SCALE: 3/4" = 1'-0"

WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
734 WW-WP-1	555740.5014	587503.2854
734 WW-WP-2	555723.6463	587532.8134



**ADDITIONAL REINFORCEMENT AT WEIR WALL OPENING**  
N. T. S.



**CONSTRUCTION JOINT DETAIL**  
SCALE: 3/4" = 1'-0"

**NOTES:**

1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
2. KEYS ARE NOMINAL SIZE.
3. CONCRETE SHALL BE CLASS A, 4500 PSI.
4. RIPRAP NOT SHOWN FOR CLARITY.
5. E. F. = EACH FACE, E. S. = EQUAL SPACING.
6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
7. 6" GRADED AGGREGATE BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.

**DELAWARE**  
DEPARTMENT OF TRANSPORTATION

ADDENDUMS / REVISIONS


**US 301,**  
**SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: HQ
	CHECKED BY: JAG

**STORMWATER**  
**MANAGEMENT DETAILS**  
**BMP 734**

<b>SW-29</b>
SHEET NO. 650
TOTAL SHTS. 875


D:\31653-000\Drawings\SW29-830U301-1A.dgn 3/25/14 10:24:14 AM



**PLAN - SWM BMP NO. 737 STA. 833+50 TO 837+50, WET POND**  
SCALE: 1" = 30'

BMP NO. 737 - DESIGN SUMMARY				
DESIGN STORM	FACILITY INFLOW (CFS)	FACILITY DISCHARGE (CFS)	WATER SURFACE ELEVATION	STORAGE VOLUME (AC-FT)
PERM. POOL	N. A.	N. A.	28.00	0.78
1-YEAR	6.3	0.6	28.53	0.24
10-YEAR	21.0	3.6	29.53	0.75
100-YEAR	47.2	14.5	30.84	1.52

HAZARD CLASSIFICATION "A" AS PER POND CODE 378  
DRAINAGE AREA TO FACILITY: 8.94 ACRES  
MANAGEMENT PROVIDED BY FACILITY: WATER QUALITY CONTROL VIA EXTENDED DETENTION FOR 1-YEAR RESOURCE PROTECTION STORM AND QUANTITY CONTROL FOR THE 10 AND 100-YEAR EVENTS.




**GENERAL NOTES:**

- THE CONTRACTOR SHALL PROVIDE "AS-BUILT" DRAWINGS OF ALL STORMWATER MANAGEMENT FACILITIES, SUCH AS PONDS, BIOFILTRATION SWALES, BIO-RETENTION AREAS, ETC. THE "AS-BUILT" DRAWINGS SHALL SHOW THE ACTUAL FINISHED GROUND CONTOURS, OUTLET STRUCTURE DIMENSIONS AND ELEVATIONS, ETC., AS THEY EXIST AT THE COMPLETION OF THE PROJECT. THESE DRAWINGS SHALL BE SIGNED AND SEALED BY A PROFESSIONAL ENGINEER OR LAND SURVEYOR REGISTERED IN THE STATE OF DELAWARE. ALL "AS-BUILT" DRAWINGS SHALL BE SENT TO THE DELDOT STORMWATER ENGINEER. ALL COSTS FOR THIS WORK SHALL BE INCLUDED UNDER ITEM 763501 - CONSTRUCTION ENGINEERING.
- STORMWATER MANAGEMENT PONDS SERVING AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION SHALL HAVE SEDIMENT REMOVED AT TIMES DETERMINED BY THE ENGINEER AND AT THE CONCLUSION OF THE PROJECT AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN VEGETATIVELY STABILIZED. COST FOR SEDIMENT REMOVAL SHALL BE PAID FOR UNDER ITEM 250000 - SEDIMENT REMOVAL. ACCESS SHALL BE MAINTAINED TO ALL SEDIMENT REMOVAL CONTROL DEVICES REQUIRING MAINTENANCE UNTIL CONSTRUCTION PHASING AND VEGETATIVE STABILIZATION ALLOW THE REMOVAL OF THOSE CONTROLS, WHICH ARE NO LONGER REQUIRED.

- POND CONSTRUCTION SEQUENCE AND NOTES:**  
THE STORMWATER MANAGEMENT POND SHALL FUNCTION AS A SEDIMENT BASIN DURING ROADWAY CONSTRUCTION AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING SECTIONS OF THE STANDARD SPECIFICATIONS:  
SECTION 271 - STORMWATER MANAGEMENT POND  
SECTION 272 - POND OUTLET STRUCTURE, CONCRETE
- INSTALL STABILIZED CONSTRUCTION ENTRANCE PER CONSTRUCTION PHASING, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB FOR INSTALLATION OF PERIMETER EROSION AND SEDIMENT CONTROLS.
  - INSTALL PERIMETER SEDIMENT CONTROLS AS SHOWN ON THE CONSTRUCTION PHASING PLANS, MOT AND EROSION AND SEDIMENT CONTROL PLANS.
  - CLEAR AND GRUB REMAINING AREA FOR POND CONSTRUCTION.
  - CONSTRUCT POND OUTLET STRUCTURE AND RIPRAP ENERGY DISSIPATOR AT DOWNSTREAM END OF WEIR WALL. EXCAVATE AS NEEDED TO INSTALL POND OUTLET STRUCTURE. INSTALL SKIMMER DEWATERING DEVICE. DE-WATER FOUNDATION AS NEEDED IN ACCORDANCE WITH SECTION 111 AND USE SUMP PIT FOR PUMPING. LOCATION OF SUMP PIT TO BE DETERMINED IN FIELD.
  - EXCAVATE THE POND AND COMPLETE THE BASIN TO LINES, GRADES, AND DETAILS SHOWN IN THE CONSTRUCTION PLANS. OVEREXCAVATE THE BOTTOM OF THE POOL 2 FEET FOR SEDIMENT STORAGE. DURING EXCAVATION, THE CONTRACTOR SHALL SALVAGE AND STOCKPILE ANY SOILS CLASSIFIED AS CH, CL, CH, AND GM PER THE UNIFIED SOIL CLASSIFICATION SYSTEM TO BE USED TO CONSTRUCT EMBANKMENT. THE ABOVE CLASSIFIED SOILS MAY BE OBTAINED FROM ELSEWHERE WITHIN THE PROJECT LIMITS.
  - STABILIZE ALL BARE AREAS BELOW ELEV. 29.00, EXCLUDING THE POND BOTTOM, WITH WET SEED MIX AND ABOVE ELEV. 29.00 WITH DRY SEED MIX.

- MAINTENANCE OF POND AS A SEDIMENT BASIN**
- SEE SHEET CS-41 FOR SB737 BASIN DETAILS. PLACE EXTERIOR GRADE PLYWOOD ACROSS WEIR OPENING IN ORDER TO FORM CREST AT ELEVATION 29.56. PLYWOOD SHALL BE AFFIXED TO WEIR WALL USING CONSTRUCTION ADHESIVE OR OTHER APPROVED MEANS. SKIMMER DEVICE SHALL BE ATTACHED TO PLYWOOD BAFFLE AT PERMANENT POOL ELEVATION 28.00. THE COST OF THE BAFFLE AND SKIMMER DEVICE AND MAINTENANCE AND/OR REPLACEMENT OF BOTH THROUGHOUT CONSTRUCTION SHALL BE INCIDENTAL TO ITEM 272500.
  - CONTRACTOR SHALL INSPECT THE BASIN IMMEDIATELY AFTER EVERY RAIN AND MAKE REPAIRS AS NEEDED.
  - CONTRACTOR SHALL CLEARLY MARK THE CLEANOUT ELEVATION, 28.81, ON A STAKE DRIVEN INTO THE GROUND AT A LOCATION CLEARLY VISIBLE FROM THE EMBANKMENT. SEDIMENT SHALL BE REMOVED WHEN CLEANOUT ELEVATION IS REACHED AND DISPOSED OF AT A LOCATION APPROVED BY THE ENGINEER.
- CONVERSION TO PERMANENT STORMWATER MANAGEMENT POND**
- CONVERT THE BASIN INTO THE PERMANENT STORMWATER MANAGEMENT POND AFTER ALL AREAS DRAINING TO THE POND HAVE BEEN PERMANENTLY STABILIZED AND THE ENGINEER HAS APPROVED THE CONVERSION.
  - REMOVE EXCESS ACCUMULATED SEDIMENT ON THE POND BOTTOM AND BENCHES, IF ANY, TO THE SPECIFIED FINISHED LINES AND GRADES SHOWN IN THE PLAN AND DISPOSE SEDIMENT AT A LOCATION APPROVED BY THE ENGINEER. IF ELEVATION OF ACCUMULATED SEDIMENT IN POOL BOTTOMS IS BELOW THE PROPOSED FINISHED ELEVATION, ADDITIONAL FILL MATERIAL SHALL NOT BE PLACED IN POND.
  - PUMP DOWN STANDING WATER IN THE POND AS NECESSARY AND COMPLETE STABILIZATION OF ALL BARE AREAS, REMOVE EROSION AND SEDIMENT CONTROL MEASURES, AND REMOVE SKIMMER DEWATERING DEVICE AND PLYWOOD.

DELDOT CONTRACT 1A-CADD-SW30-833U301-1A.dgn  
 2/20/2015 7:58:20 AM



NOT FOR BIDDING

**STAKEOUT PLAN - SWM BMP NO. 737 STA. 833+50 TO STA. 837+50, WET POND**

SCALE: 1" = 30'


EMBANKMENT BASELINE "A" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
1	POB STA.10+00.00	555806.40	588329.79
2	PI STA.10+61.00	555861.79	588304.23
3	PI STA.11+03.62	555894.22	588276.58
4	PI STA.11+06.13	555896.13	588274.95
5	PI STA.11+81.92	555941.62	588214.33
6	PI STA.12+09.92	555958.43	588191.94
7	PC STA.12+12.24	555959.82	588190.08
8	PRC STA.12+46.47	555989.84	588177.09
9	PT STA.12+64.37	556007.30	588174.25
10	PC STA.12+72.41	556014.60	588170.88
11	PT STA.13+08.53	556045.11	588182.12
12	PC STA.14+67.51	556111.79	588326.45
13	PT STA.15+05.23	556113.83	588363.23
14	PI STA.15+23.72	556107.99	588380.76
15	PI STA.15+54.95	556085.90	588402.85
16	PI STA.15+71.62	556072.04	588412.11
17	PC STA.15+81.49	556064.23	588418.13
18	PCC STA.15+95.44	556053.84	588427.42
19	PT STA.16+13.32	556043.56	588441.97
20	PI STA.16+38.39	556032.43	588464.43
21	PC STA.16+46.88	556032.71	588472.91
22	PT STA.16+67.44	556036.50	588493.04
23	PI STA.17+25.93	556056.00	588548.18
24	POE STA.18+61.08	555933.29	588604.80

ACCESS ROAD BASELINE "B" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
3	POB STA.20+00.00	555894.22	588276.58
25	PC STA.20+14.63	555903.71	588287.71
26	PRC STA.20+50.46	555934.37	588304.72
27	PT STA.21+09.19	555989.32	588324.40
28	PI STA.21+14.24	555993.65	588326.99
29	PC STA.21+27.10	556003.44	588335.33
30	PT STA.21+60.00	556011.25	588365.23
31	PI STA.22+09.65	555994.06	588411.80
32	PI STA.22+43.87	556012.24	588440.80
33	POE STA.22+72.45	556037.85	588453.50

BASELINE "C" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
34	POB STA.30+00.00	555917.01	588174.62
35	PI STA.30+19.49	555930.61	588188.57
36	PI STA.30+86.21	555983.98	588228.62
37	PI STA.31+68.23	556002.79	588308.45
38	PI STA.32+37.61	555972.01	588370.63
39	PI STA.32+59.85	555981.60	588390.70
40	PI STA.32+97.41	555987.03	588427.86
41	POE STA.34+35.66	556040.04	588555.55

BASELINE "D" STAKEOUT INFORMATION			
POINT NO.	STATION	NORTHING	EASTING
42	POB STA.40+00.00	555835.46	588392.77
43	PI STA.41+37.07	555959.19	588333.79
44	POE STA.41+64.91	555984.14	588346.13

ADDENDUMS / REVISIONS




**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: CRH
	CHECKED BY: DLH


**STORMWATER  
STAKEOUT PLAN  
BMP 737**

SW-31
SHEET NO. 652
TOTAL SHTS. 875



**PROFILE - POND EMBANKMENT - BMP 737 BASELINE 'A'**

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'




**PROFILE - ACCESS ROAD - BMP 737 BASELINE "B"**

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'

**PROFILE - BMP 737 BASELINE "C"**

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'



**PROFILE - BMP 737 BASELINE "D"**

SCALE: HORIZONTAL: 1" = 30'  
VERTICAL: 1" = 10'

- RIPRAP NOTES:**
- RIPRAP CUTOFF AND TOE WALLS SHALL BE MEASURED BELOW THE NORMAL RIPRAP PAD DEPTH AND PAID PER TON (ITEMS 712020 AND 712021).
  - THE 26" DEPTH FOR R-5 RIPRAP SHALL CONSIST OF 20" R-5 RIPRAP AND 6" OF DE NO. 57 STONE.

P:\03\653-000\control\1a\cadd\SW32-833U301-1A.dgn  
 10/31/2014 10:40:41 AM



ADDENDUMS / REVISIONS	




**US 301,  
SR 896 TO SR 1**

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: CRH
	CHECKED BY: JDC


<b>STORMWATER MANAGEMENT PROFILES BMP 737</b>	
SHEET NO.	653
TOTAL SHTS.	875

<b>SW-32</b>
--------------







PLAN - SWM BMP NO. 737 WEIR WALL  
SCALE: 1/2" = 1'



SECTION A-A  
SCALE: 3/4" = 1'-0"



ELEVATION - SWM BMP NO. 737 WEIR WALL  
SCALE: 1/2" = 1'




SECTION B-B  
SCALE: 3/4" = 1'-0"


WORKING POINT COORDINATES		
WORKING POINT	NORTHING	EASTING
737 WW-WP-1	555958.0256	588191.6354
737 WW-WP-2	555941.2191	588214.0305

NOTES:

1. MAXIMUM FACTORED BEARING RESISTANCE FOR WEIR WALL IS 2 KSF.
2. KEYS ARE NOMINAL SIZE.
3. CONCRETE SHALL BE CLASS A, 4500 PSI.
4. RIPRAP NOT SHOWN FOR CLARITY.
5. E.F. = EACH FACE, E.S.=EQUAL SPACING.
6. SEE REINFORCING BAR LIST ON DRAWINGS SW-34 AND SW-35.
7. 6" GRADED AGGREGATED BASE BEDDING SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR THE WEIR WALL.



CONSTRUCTION JOINT DETAIL  
SCALE: 3/4" = 1'-0"



ADDITIONAL REINFORCEMENT AT WEIR WALL OPENING  
SCALE: NOT TO SCALE


P:\31653-000\contingest\to\cadd\SW35-833U301\_1A.dgn  
 09/27/2014 12:40:07 PM

ADDENDUMS / REVISIONS	


CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: HQ
	CHECKED BY: JAG







**INFILTRATION TRENCH DETAIL**



**OBSERVATION PORT DETAIL**

ID	LENGTH FT.	WIDTH FT.	DEPTH FT.	TOP ELEVATION FT.	BOTTOM ELEVATION FT.	GROUND WATER EL. FT.	MEASURED RATE IN/HR	DESIGN RATE IN/HR
BMP 726	50.0'	4.0'	3.0'	73.95'	70.95'	<68.0	3.5	1.75
BMP 712	150.0'	6.0'	3.0'	65.00'	62.00'	<57.9	6.0	3.0
BMP 713	100.0'	6.0'	4.0'	65.00'	61.00'	<59.0	10.0	5.0
BMP 744	150.0'	6.0'	5.0'	72.85'	67.85'	<65.7	3.0	1.5
BMP 745	60.0'	4.0'	3.0'	71.90'	68.90'	<67.3	2.5	1.25

- NOTES:**
- FOOTPRINT OF PROPOSED INFILTRATION TRENCH PLUS 10 FEET IN ALL DIRECTIONS SHALL BE MARKED IN THE FIELD WITH CONSTRUCTION SAFETY FENCE (ITEM 727520) AT THE BEGINNING OF CONSTRUCTION. THIS AREA SHALL BE OFF LIMITS TO CONSTRUCTION EQUIPMENT UNTIL WORK ON INFILTRATION TRENCHES BEGIN. COST OF BARRIER FENCE SHALL BE INCIDENTAL TO THE CONTRACT UNIT COST FOR INFILTRATION TRENCH (ITEM 718513).
  - DURING CONSTRUCTION, THE CONTRACTOR SHALL EXERCISE CAUTION NOT TO DISTURB AND COMPACT ANY IN SITU SOIL LAYER BELOW THE PROPOSED GRADE AND WITHIN THE FOOTPRINT OF THE INFILTRATION TRENCH. THE SIDES AND BOTTOM OF THE TRENCH SHALL BE SCARIFIED PRIOR TO PLACEMENT OF THE GEOTEXTILE MATERIAL AND BACKFILLING WITH STONE.
  - FILTER FABRIC SHALL BE PLACED ALONG THE SIDE OF THE INFILTRATION TRENCH AND EXTEND OVER THE ENTIRE TOP OF THE INFILTRATION TRENCH DURING CONSTRUCTION. ONCE THE ENTIRE DRAINAGE AREA HAS BEEN STABILIZED WITH A GOOD STAND OF GRASS, THE CONTRACTOR SHALL CUT THE FILTER FABRIC AT GROUND LEVEL AND EXPOSE THE TOP SURFACE OF THE TRENCH. ANY BARE AREAS SHALL BE IMMEDIATELY SEEDED AND MULCHED WITH SRBM, TYPE 5. FILTER FABRIC MATERIAL SHALL CONFORM TO SECTION 827.04 OF THE STANDARD SPECIFICATIONS.
  - STONE BACKFILL FOR THE INFILTRATION TRENCH SHALL BE DE NO. 3 STONE. THE DE NO. 3 STONE SHALL BE CLEAN, DOUBLE WASHED CRUSHED AGGREGATE FREE OF ROCK DUST, FINES, AND SOIL PARTICLES. STONES SHALL NOT BE CRUSHED LIMESTONE AGGREGATES. STONE BACKFILL MATERIALS DETERMINED TO BE CONTAMINATED SHALL BE REPLACED AT THE CONTRACTORS EXPENSE.
  - AN OBSERVATION PORT SHALL BE INSTALLED IN THE CENTER OF EACH INFILTRATION TRENCH. SEE DETAIL.

DRAFT

NOT FOR BIDDING

AUGUST 2015

p:\1653-000\contract\1a\cadd\SW36-U301\_1A.dgn 8/2/2014 12:42:18 PM

ADDENDUMS / REVISIONS	

--

<b>US 301, SR 896 TO SR 1</b>
-----------------------------------

CONTRACT T200911308	BRIDGE NO.
COUNTY NEW CASTLE	DESIGNED BY: DLH
	CHECKED BY: JDC

<b>STORMWATER MANAGEMENT DETAILS</b>
--

SW-36
SHEET NO. 657
TOTAL SHTS. 875