

B. AN ENVIRONMENTAL MONITOR WILL BE RESPONSIBLE FOR REVIEWING ENVIRONMENTAL COMPLIANCE, CONTACT INFORMATION FOR THE PROJECT'S ENVIRONMENTAL MONITOR WILL BE PROVIDED AT THE PRE-CONSTRUCTION MEETINGS AND MAY ALSO BE OBTAINED BY CALLING THE DELDOT ENVIRONMENTAL STUDIES SECTION AT (302) 760-2264. THE PRESENCE OF THE DEPARTMENT'S ENVIRONMENTAL MONITOR DOES NOT ALLEVIATE OR NULLIFY ANY OF THE CONTRACTOR'S OBLIGATIONS TO FULLY COMPLY WITH ALL ENVIRONMENTAL PERMITS AND/OR REGULATIONS.

C. IF A DEPARTURE FROM THE APPROVED PLANS IS NECESSARY, THE CONTRACTOR SHALL CONTACT THE ENGINEER AND ENVIRONMENTAL MONITOR IMMEDIATELY. THE ENVIRONMENTAL MONITOR SHALL COORDINATE WITH THE APPROPRIATE RESOURCE AGENCIES INCLUDING BUT NOT LIMITED TO THE ARMY CORPS OF ENGINEERS (USACE), DELAWARE DEPARTMENT OF NATURAL RESOURCES AND ENVIRONMENTAL CONTROL (DNREC), STATE HISTORIC PRESERVATION OFFICE (SHPO), AND MARYLAND DEPARTMENT OF THE ENVIRONMENT (MDE). WORK SHALL NOT PROCEED UNTIL ALL THE NECESSARY APPROVALS, PERMITS OR MODIFICATIONS ARE OBTAINED. THIS RESOURCE AGENCY APPROVAL IS IN ADDITION TO ANY APPROVAL THAT NEEDS TO BE DERIVED FROM THE ENGINEER. THE ENVIRONMENTAL MONITOR CANNOT APPROVE ANY CHANGE INDEPENDENT FROM THE ENGINEER. APPROVAL MAY TAKE A SIGNIFICANT AMOUNT OF TIME TO COMPLETE AND ALL CHANGES MAY NOT BE APPROVED. THE CONTRACTOR SHALL HAVE NO CLAIM AGAINST THE DEPARTMENT FOR COSTS OR DELAYS ASSOCIATED WITH RESOURCE AGENCY APPROVAL OR REJECTION OF CHANGES OR DEVIATIONS FROM THESE PLANS.

D. USE OF THESE SHEETS DOES NOT ALLEVIATE THE CONTRACTOR'S RESPONSIBILITY TO COMPLY WITH ALL CONDITIONS SET FORTH IN THE ENVIRONMENTAL STATEMENT AND PERMITS.

E. THE IDENTIFIED PERMANENT AND TEMPORARY IMPACTS TO JURISDICTIONAL RESOURCES SHOWN ON THE ENVIRONMENTAL COMPLIANCE SHEETS ARE THE ONLY AUTHORIZED IMPACTS.

2. NATURAL AND CULTURAL RESOURCE ISSUES:

A. PERMIT REQUIREMENTS / APPROVALS\*:

USACE - INDIVIDUAL PERMIT - CENAP-OP-R-2006-6071-1 (PROVISIONAL PENDING WQ CERTIFICATION); PROVISIONAL APPROVAL AUGUST 18. 2009; EXPIRES

DECEMBER 31, 2019\*\*

DNREC SUBAQUEOUS LANDS PERMIT - PENDING\*\* DNREC WATER QUALITY CERTIFICATION - PENDING\*\*

DELAWARE COASTAL ZONE MANAGEMENT FEDERAL CONSISTENCY CERTIFICATION -

SEPTEMBER 14, 2007; NO EXPIRATION\*\*

NEW CASTLE COUNTY FLOODPLAIN APPROVAL - PENDING\*\*

FOR UNDER ITEM 727552 - RESOURCE PROTECTION FENCE.

\* THE PERMITS/APPROVALS LISTED ARE THOSE REQUIRED FOR THIS PROJECT. THE ENVIRONMENTAL STUD<mark>IES SECTION IS RESP</mark>ONSIBLE FOR COORDINATING/OBTAINING THESE PERMITS/APPROVALS.

\*\* THE CONTRACTOR MUST ENSURE THAT THESE PERMITS/APPROVALS ARE IN THEIR POSSESSION PRIOR TO THE BEGINNING OF CONSTRUCTION AND ENSURE THESE PERMITS/APPROVALS ARE DISPLAYED ON-SITE DURING THE ENTIRE CONSTRUCTION PERIOD.

B. CONSTRUCTION RESTRICTIONS: ENDANGERED SPECIES NONE

FISHERIES: NONE

MIGRATORY BIRDS: NONE

C. PROTECTION OF RESOURCES: I. ITEM 727552 - RESOURCE PROTECTION FENCE (WITH ASSOCIATED SIGNAGE) SHALL BE USED ALONG THE LIMIT OF CONSTRUCTION (LOC) AND OTHER AREAS SHOWN ON THE PLANS WHERE WETLANDS, WATERS OR CULTURAL RESOURCES EXIST. RESOURCE PROTECTION FENCE SHALL BE INSTALLED IMMEDIATELY AFTER STAKEOUT OF LOC AND PRIOR TO INSTALLATION OF EROSION AND SEDIMENT CONTROLS. THE CONTRACTOR SHALL STAKEOUT THE LOCATION OF THE RESOURCE PROTECTION FENCE AND THE ENVIRONMENTAL MONITOR WILL BE RESP<mark>ONSIBLE FOR CONFIRMIN</mark>G OR ADJUSTING THE FENCING LOCATIONS PRIOR TO CONSTRUCTION. IMPROPERLY PLACED FENCE SHALL BE RE-INSTALLED AT CONTRACTOR EXPENSE. ANY ADDITIONAL RESOURCE PROTECTION FENCE AS REQUESTED BY THE ENVIRONMENTAL MONITOR AND CONFIRMED BY THE ENGINEER SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE. RESOURCE PROTECTION FENCE SIGNAGE SHALL BE PROVIDED BY DELDOT AND INSTALLED BY THE CONTRACTOR ALONG THE FENCE NO GREATER THAN 100 FEET APART AND WITH A MINIMUM OF 2 SIGNS PER CONTINUOUS FENCE RUN AS INDICATED IN THE SPECIAL PROVISIONS. RESOURCE PROTECTION FENCE SHALL BE PAID

II. THE PURPOSE OF ITEM 727552 - RESOURCE PROTECTION FENCE IS TO PREVENT IMPACTS TO SENSITIVE RESOURCES DURING CONSTRUCTION. ACCESS INTO THESE AREAS IS STRICTLY PROHIBITED. THE CONTRACTOR IS RESPONSIBLE FOR ENSURING THAT ALL EMPLOYEES UNDERSTAND AND COMPLY WITH THE PURPOSE OF THE RESOURCE PROTECTION FENCE.

III. THE INSTALLATION OF THE RIGHT-OF-WAY FENCE AND RESOURCE PROTECTION FENCE ARE THE ONLY CONSTRUCTION ACTIVITIES THAT ARE AUTHORIZED TO OCCUR OUTSIDE OF THE LOC.

IV. RESOURCE PROTECTION FENCE SHALL BE INSTALLED BY HAND AS PER THE DETAILS AND SPECIFICATIONS OF ITEM 727552 - RESOURCE PROTECTION FENCE. THERE SHALL BE NO GRUBBING FOR THE INSTALLATION OF RESOURCE PROTECTION FENCE. RIGHT-OF-WAY FENCE SHALL BE INSTALLED BY HAND IN SENSITIVE AREAS, INCLUDING WETLANDS, FORESTS, AND CULTURAL RESOURCE AREAS PROTECTED BY RESOURCE PROTECTION FENCE. THERE SHALL BE NO GRUBBING FOR THE INSTALLATION OF RIGHT-OF-WAY FENCE IN SENSITIVE AREAS. WHERE CLEARING IS NECESSARY FOR FENCE INSTALLATION, VEGETATION SHALL BE CUT FLUSH WITH THE GROUND (I.E. NO DISTURBANCE OF THE ROOT MAT). ENVIRONMENTAL IMPACTS SHALL BE MINIMIZED DURING THE INSTALLATION OF THE RESOURCE PROTECTION FENCE AND RIGHT-OF-WAY FENCE AND THE REMOVAL OF THE RESOURCE PROTECTION FENCE. ACCESS AND INSTALLATION/REMOVAL OF RESOURCE PROTECTION FENCE AND INSTALLATION OF RIGHT-OF-WAY FENCE SHALL BE COORDINATED WITH THE ENVIRONMENTAL MONITOR.

D. STREAM RESTORATION AND SLOPE RIPRAP TREATMENT:

I. THE CONTRACTOR SHALL FOLLOW THE SPECIAL PROVISIONS OF ITEM 712531 - CHANNEL BED FILL, IN REGARDS TO THE SALVAGING OF ON-SITE NATURAL STREAM BOTTOM MATERIAL OR THE FURNISHING OF OFF-SITE MATERIAL. IF A SEPARATE SPECIAL PROVISION OR MATERIAL GRADATION HAS BEEN DETAILED ON THE PLANS FOR A SPECIFIC CHANNEL LOCATION. THAT SPECIFICATION OR GRADATION SHALL BE UTILIZED FOR CHANNEL BED FILL AT THE INDICATED LOCATION(S). PIPES WITH DIAMETERS >/= 60" SHALL BE RECESSED A MINIMUM OF 12" BELOW THE STREAMBED ELEVATION. PIPES < 60" SHALL BE RECESSED A MINIMUM OF 4" OR 20% OF THE DIAMETER OF THE PIPE, WHICHEVER IS GREATER. BOX CULVERTS SHALL BE RECESSED 12" BELOW THE STREAMBED ELEVATION, ALL RIPRAP SHALL BE PLACED SUCH THAT THE TOP OF THE RIPRAP IS PLACED TO MATCH THE INVERT ELEVATION OF THE PIPE OR CULVERT AND CHOKED WITH BORROW TYPE 'B' SO THAT ALL OF THE VOIDS IN THE RIPRAP ARE FILLED WITH MATERIAL. PAYMENT UNDER ITEM 209002 - BORROW TYPE 'B'. THE RIPRAP SHALL THEN BE COVERED WITH CHANNEL BED FILL TO MATCH EXISTING UPSTREAM/DOWNSTREAM CHANNEL BED ELEVATIONS. PAYMENT UNDER ITEM 712531 - CHANNEL BED FILL.

PIPES AND RIPRAP SHALL BE RECESSED IN STREAMS LOCATED AT THE FOLLOWING CROSSINGS: UNNAMED TRIBUTARY TO SPRING MILL BRANCH - STA 605+00 UNNAMED TRIBUTARY TO DRAWYER CREEK - STA 659+00

II. OTHER AREAS OF THE CHANNEL BOTTOM AFFECTED BY CONSTRUCTION (INCLUDING, BUT NOT LIMITED TO, THE LOCATION OF SUMP PITS, STABILIZED OUTFALLS, TEMPORARY PIPES AND/OR SANDBAG DIKES AND DIVERSIONS) SHALL BE RESTORED TO PREDISTURBANCE CONDITIONS, ANY CAVITIES OR SCOUR HOLES RESULTING FROM CONSTRUCTION ACTIVITIES SHALL BE FILLED WITH CHANNEL BED FILL. PAYMENT UNDER ITEM 712531 - CHANNEL BED FILL.

III. W<mark>HEN</mark> ALL EROSION AND SEDIMENT CONTROL MEASURES ARE REMOVED AND THE STREAM RETURNS TO ITS NATURAL FLOW CONDITIONS, THE FLOW MUST REMAIN ABOVE GROUND AND ABOVE THE RIPRAP (I.E. THE FLOW CANNOT BE 'LOST' IN THE RIPRAP OR BENEATH THE STRUCTURE). IF THIS IS NOT ACHIEVED, THE CONTRACTOR WILL BE REQUIRED TO TAKE CORRECTIVE ACTION AT THE CONTRACTOR'S EXPENSE.

IV. ALL RIPRAP ON THE STREAM BANK, ABOVE THE ORDINARY HIGH WATER MARK, SHALL BE PLACED AS DESCRIBED BELOW:

CHOKE THE RIPRAP WITH ENOUGH ITEM 302012 - DELAWARE #57 STONE TO PREVENT THE LOSS OF TOPSOIL THROUGH THE RIPRAP AS APPROVED BY THE ENGINEER. FILL THE REMAINING VOIDS WITH TOPSOIL SO THAT THE RIPRAP IS BARELY VISIBLE. REGARDLESS OF DEPTH, THIS SHALL BE PAID FOR UNDER ITEM 733001 - TOPSOILING, 4" DEPTH. APPLY AN ADDITIONAL 4 INCH LAYER OF TOPSOIL (ITEM 733001 - TOPSOILING, 4" DEPTH), SEED WITH ITEM 734531 - STREAMBANK SEED MIX FROM ABOVE THE ORDINARY HIGH WATER MARK TO THE TOP OF THE SLOPE. IMMEDIATELY FOLLOWING THE SEEDING, INSTALL ITEM 735535 -SOIL RETENTION BLANKET MULCH, TYPE 5. ALL WORK, STARTING WITH TOPSOIL PLACEMENT THROUGH SEEDING AND MULCHING, SHALL BE COMPLETED PRIOR TO ANY RAIN EVENT. RIPRAP AND ALL OTHER ITEMS SHALL BE PAID FOR UNDER THEIR RESPECTIVE ITEMS.

STREAMBANK RIPRAP SHALL BE TREATED AS DESCRIBED ABOVE IN STREAMS LOCATED AT THE FOLLOWING CROSSINGS:

UNNAMED TRIBUTARY TO SPRING MILL BRANCH - STA 605+00 UNNAMED TRIB<mark>UTA</mark>RY TO DRAWYER CREEK - STA 659+00

BY DELDOT.

V. THE CHANNEL AND STREAM BANK SEGMENTS ENTERING AND EXITING THE BRIDGES, PIPES AND CULVERTS SHALL NOT BE WIDENED BEYOND THE DIMENSIONS SHOWN ON THE PLANS. THE CHANNEL WIDTHS, CHANNEL BANKS AND SIDE-SLOPES SHALL NOT BE WIDENED OR RE-CONTOURED TO ACCOMMODATE EASIER CONSTRUCTION OR ACCESS.

E. STAGING, STOCKPILING AND DISPOSAL: I. NO STOCKPILING OR STORAGE OF EQUIPMENT, MATERIALS. OR STRUCTURAL STEEL; NO STAGING AREA; AND NO INSTALLATION OF ANCILLARY FACILITIES SUCH AS CONCRETE OR ASPHALT PLANTS OR CONSTRUCTION TRAILERS SHALL BE PERMITTED ON ANY CULTURAL RESOURCE SITE OR WITHIN WETLANDS OR STREAMS OUTSIDE OF IDENTIFIED STORAGE AREAS APPROVED BY THE SHPO OR THE USACE. NO CONSTRUCTION MATERIALS, AGGREGATES, OR EARTH SHALL BE STOCKPILED OR STORED IN A MANNER THAT WOULD AFFECT WETLANDS OR STREAMS. STOCKPILES SHALL HAVE EROSION AND SEDIMENT CONTROLS APPROVED

II. ALL EXCESS EXCAVATED MATERIALS NOT USED IN HIGHWAY OR COMPENSATORY MITIGATION SITE CONSTRUCTION SHALL BE DISPOSED OF IN UPLAND, NON-WETLAND, NON-CULTURAL RESOURCE SITE(S). THE EXCAVATED MATERIAL SHALL BE PROPERLY CONTAINED AND STABILIZED TO PREVENT ITS ENTRY INTO ANY ADJACENT WETLANDS OR WATERWAYS. OUTSIDE OF ANY LOCATION DESIGNATED ON PLANS FOR DISPOSAL, NO DISPOSAL/WASTING OPERATION SHALL COMMENCE UNTIL WRITTEN APPROVAL OF THE DISPOSAL SITE(S) IS OBTAINED BY THE ENGINEER FROM THE USACE AND THE SHPO, THE CONTRACTOR SHALL SUBMIT THE PROPOSED DISPOSAL SITE LOCATION(S) TO THE ENGINEER. THE ENGINEER WILL SUBMIT THE PROPOSED DISPOSAL SITE INFORMATION TO THE SHPO AND USACE FOR APPROVAL. THE DEPARTMENT WILL NOT CONSIDER ANY DELAYS OR MONETARY CLAIMS OF ANY NATURE RESULTING FROM DELAYS IN APPROVAL OR REJECTION OF DISPOSAL SITES OR FROM THE CONTRACTOR'S FAILURE OR DIFFICULTY IN FINDING ACCEPTABLE DISPOSAL SITES TO MEET THE TIME FRAMES AND CAPACITIES REQUIRED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL PLANS, EROSION AND SEDIMENTATION CONTROL MEASURES, ETC. REQUIRED BY THE APPROPRIATE REGULATORY AGENCY FOR UTILIZING OFF-SITE SPOILS AREAS.

F. MINIMIZATION AND RESTORATION OF TEMPORARY IMPACTS: ALL TEMPORARY IMPACTS SHOWN ON THESE SHEETS SHALL BE RESTORED AS SPECIFIED IN THE MISCELLANEOUS PROJECT NOTES TO PREDISTURBANCE GRADE AND CONDITION AND STABILIZED. THE AREA SHALL BE PLANTED AS SHOWN IN THE MOT SHEETS AND NOTED ON THESE EC SHEETS. STREAMS SHALL BE RESTORED TO PREDISTURBANCE PATTERN AND PROFILE.

WETLANDS DELINEATED BY RUMMEL KLEPPER & KAHL. LLP, IN JUNE 2005 THROUGH DECEMBER 2010 IN ACCORDANCE WITH THE 1987 USACE WETLAND DELINEATION MANUAL AND APPLICABLE REGIONAL SUPPLEMENTS.

PRELIMINARY JURISDICTIONAL DETERMINATION AUGUST 18. 2009. WETLAND IDENTIFIERS CORRESPOND TO THE US 301 WETLAND DELINEATION REPORT.

SHEET PREPARED BY: MCCORMICK TAYLOR, INC. DATE: MARCH 10. 2010

SHEETS LAST UPDATED: APRIL 13. 2012

ALL IDENTIFIED WATER/WETLANDS ON THESE ENVIRONMENTAL COMPLIANCE SHEETS ARE USACE JURISDICTIONAL AND/OR DNREC JURISDICTIONAL.

G. CULTURAL RESOURCES:

IF ANY UNANTICIPATED DISCOVERIES OF ARCHAEOLOGICAL OR HUMAN REMAINS OCCUR DURING CONSTRUCTION, ALL WORK SHALL BE IMMEDIATELY SUSPENDED IN THE AREA OF THE DISCOVERY AND THE ENVIRONMENTAL MONITOR SHALL BE CONTACTED. THE ENVIRONMENTAL MONITOR WILL CONTACT DELDOT CULTURAL RESOURCES, SHPO AND USACE TO COMMENCE THE NECESSARY FEDERAL AND STATE COORDINATION. WORK SHALL NOT RESUME UNTIL APPROPRIATE RESOURCE AGENCY COORDINATION, INVESTIGATION AND/OR RECOVERY IS COMPLETE.

H. SOIL AND EARTH DISTURBANCE:

I. ITEM 251001 - REINFORCED SILT FENCE SHALL BE USED DUE TO THE HIGH PROBABILITY OF OVERBANK FLOODING, IN THE FOLLOWING LOCATIONS:

DRAWYER CREEK- STA 635+00 TO 640+00

II. THERE SHALL BE NO GRUBBING UNDER BRIDGES EXCEPT WHERE NECESSARY TO CONSTRUCT PROJECT COMPONENTS SUCH AS FOUNDATIONS, SLOPE PROTECTION AND UTILITIES. BRIDGE LOCATIONS ARE AS FOLLOWS:

DRAWYER CREEK - STA 638+00

I. FLOODPLAIN: NEW RIPRAP PLACED IN THE FLOODPLAIN BENEATH BRIDGES SHALL BE BURIED.

RIPRAP FLOODPLAIN LOCATIONS ARE AS FOLLOWS:

DRAWYER CREEK - STA 638+00

**DELAWARE** DEPARTMENT OF TRANSPORTATION ADDENDUMS / REVISIONS

NOT TO SCALE

US 301, NORFOLK SOUTHERN RR TO SR 896

CONTRAC BRIDGE NO. T200911301 REL DESIGNED BY: COUNTY LMM CHECKED BY: NEW CASTLE

**ENVIRONMENTAL** COMPLIANCE **NOTES** 

SHEET NO 168 DTAL SHTS 240

**EC-02** 

	TEMPORARY OPEN	WATER IM	PACT AREA	<b>SCHEDULE</b>	
I D	IMPACT DESCRIPTION	AREA (SF)	AREA (AC)	VOLUME (CY)	JURISDICTION
4-0T1	E&S AREA	<i>578. 81</i>	<i>0. 0133</i>	21.44	USACE/DNREC
4-0T2	E&S AREA	<i>395. 69</i>	0.0091	14.66	USACE/DNREC
7-0T1	TEMPORARY ACCESS	<i>603. 44</i>	0.0139	<i>22. 35</i>	USACE/DNREC
7-0T2	TEMPORARY ACCESS	745. 94	0.0171	<i>27. 63</i>	USACE
7-0T3	TEMPORARY ACCESS	<i>658.02</i>	0.0151	<i>24. 37</i>	USACE/DNREC
7-0T4	TEMPORARY ACCESS	740. 29	0.0170	27. 42	USACE
7-0T5	TEMPORARY ACCESS	<i>166. 36</i>	0.0038	6. 16	USACE/DNREC
7-0T6	TEMPORARY ACCESS	82.64	0.0019	<i>3.</i> 06	USACE/DNREC
8-0T1	E&S AREA	<i>534. 27</i>	<i>0. 0123</i>	19. 79	USACE/DNREC
8-0T2	E&S AREA	<i>788. 75</i>	0.0181	29. 21	USACE/DNREC
TOTAL USACE FOR THIS SHEET		5, 294. 21	0.1216	196.09	USACE
TOTAL DNREC FOR THIS SHEET		<i>3,</i> 807. 98	<i>0.0875</i>	141.04	DNREC


	PERMANENT WE	•		•	
I D	IMPACT DESCRIPTION	AREA (SF)	AREA (AC)	VOLUME (CY)	JURISDICTION
4-W1	FILL	9, 421. 28	<i>0.</i> 2163	N/A	USACE
4-W2	FILL	13, 942. 62	<i>0. 3201</i>	N/A	USACE
4-W3	EXCAVATION	1, 565. 07	<i>0.</i> 0359	N/A	USACE
4-W4	RIPRAP	260.05	0.0060	N/A	USACE
5-W1	FILL	<i>4, 355. 00</i>	0.1000	N/A	USACE
5-W2	EXCAVATION	324. 41	0.0074	N/A	USACE
7-W1	SHADING	<i>4, 575. 89</i>	0.1050	N/A	USACE
7-W2	SHADING	4, 382. 01	0.1006	N/A	USACE
7-W3	FILL	300.51	0.0069	N/A	USACE
8-W1	EXCAVATION	<i>223. 28</i>	0.0051	N/A	USACE
14-W1	EXCAVATION	19, 700. 65	<i>0.</i> 4523	N/A	USACE
14-W2	EXCAVATION	<i>4, 500. 76</i>	<i>0.</i> 1033	N/A	USACE
OTAL F	ERMANENT WETLAND IMPACTS	<i>63, 551. 53</i>	1. 4589	N/A	


TEMPORARY WETLAND IMPACT AREA SCHEDULE							
ID	IMPACT DESCRIPTION	AREA (SF)	AREA (AC)	VOLUME (CY)	JURISDICTION		
7-WT1	TEMPORARY ACCESS	<i>5, 763. 90</i>	<i>0.</i> 1 <i>323</i>	N/A	USACE		
7-WT2	TEMPORARY ACCESS	3, 616. 13	0.0830	N/A	USACE		
7-WT3	TEMPORARY ACCESS	1, 217. 13	0.0279	N/A	USACE		
TOTAL TO	EMPORA <mark>RY</mark> WETLAND IMPACTS	10, 597. 16	<i>0.</i> 2433	N/A			


## NOT FOR BIDDING AUGUST 2015


-EA\$


EC-03 ADDENDUMS / REVISIONS BRIDGE NO. **DELAWARE** US 301, T200911301 ENVIRONMENTAL COMPLIANCE PLAN 169 NOT TO SCALE REL DESIGNED BY: **DEPARTMENT OF TRANSPORTATION** NORFOLK SOUTHERN RR TO SR 896 DTAL SHTS COUNTY LMM NEW CASTLE CHECKED BY: 240














175 OTAL SHTS 240

ENVIRONMENTAL COMPLIANCE PLAN

DELAWARE DEPARTMENT OF TRANSPORTATION

ADDENDUMS / REVISIONS


US 301, NORFOLK SOUTHERN RR TO SR 896 T200911301 NEW CASTLE

CONTRACT

COUNTY


BRIDGE NO.

DESIGNED BY: LMM CHECKED BY:




NOTE: NO IMPACTS ON THIS SHEET

EC-10 ADDENDUMS / REVISIONS BRIDGE NO. **DELAWARE** SCALE US 301, T200911301 **ENVIRONMENTAL** DEPARTMENT OF TRANSPORTATION DESIGNED BY: NORFOLK SOUTHERN RR TO SR 896 **COMPLIANCE PLAN** OTAL SHTS NEW CASTLE LMM 240 CHECKED BY:



EC-11 ADDENDUMS / REVISIONS CONTRACT BRIDGE NO. **DELAWARE** US 301, NORFOLK SOUTHERN RR TO SR 896 T200911301 177 ENVIRONMENTAL COMPLIANCE PLANS DESIGNED BY: DEPARTMENT OF TRANSPORTATION OTAL SHTS COUNTY NEW CASTLE 240 CHECKED BY: LMM





NEW CASTLE


LMM


CHECKED BY:


240











NORFOLK SOUTHERN RR TO SR 896

CHECKED BY: JTR

NEW CASTLE

TOTAL SHTS

240