

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -1

TABULATION OF BIDS
FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

STATE/FEDERAL AID NO: NH-2015 (20)

CONTRACT TIME : 850 CALENDAR DAYS

CONTRACT DESCRIPTION :

RURAL(UNDER 5,000 POPULATION)

PROJECT(S) : NH-2015 (20)

THE IMPROVEMENTS CONSIST OF FURNISHING ALL MATERIALS AND LABOR FOR CONSTRUCTION OF A DIVIDED HIGHWAY INCLUDING: CLEARING AND GRUBBING; EXCAVATION, HAULING AND PLACING EMBANKMENT FOR ROADWAY CONSTRUCTION P.C.C. ROADWAY PAVEMENT AND SHOULDERS; P.C.C./ASPHALT RAMPS; ASPHALT SIDE ROADS; TOLL FACILITIES; INTELLIGENT TRANSPORTATION SYSTEMS INCLUDING CVISN AND WIM; DRAINAGE IMPROVEMENTS; STORMWATER MANAGEMENT FACILITIES; GUARDRAIL; FENCING; ARCHEOLOGY RESOURCE PROTECTION AREAS; EROSION AND SEDIMENT CONTROLS; SIGNING; LIGHTING; PAVEMENT MARKINGS; TRAFFIC SIGNAL WORK; LANDSCAPING; MECHANICALLY STABILIZED EARTH RETAINING WALLS; REINFORCED CONCRETE BRIDGES WITH PRESTRESSED REINFORCED CONCRETE GIRDERS; FURNISHING AND INSTALLING PILES; MAINTENANCE OF TRAFFIC; UTILITY RELOCATIONS; AND OTHER INCIDENTAL CONSTRUCTION IN ACCORDANCE WITH THE LOCATION, NOTES AND DETAILS SHOWN ON THE PLANS AND AS DIRECTED BY THE ENGINEER. THIS CONTRACT INCLUDES WORK WITHIN THE STATE OF MARYLAND.

SET-ASIDE :

VENDOR RANKING : Contract was awarded on 01/21/16 to vendor GREGGO & FERRARA, INC.

RANK	VENDOR NAME	TOTAL BID	% OVER LOW BID	% OVER EST
0	ENGINEER'S ESTIMATE	\$ 44,699,288.81	97.0569%	100.0000%
1	GREGGO & FERRARA, INC., 4048 NEW CASTLE AVENUE, NEW CASTLE, DE, 19720	\$ 46,054,715.79	100.0000%	103.0323%
2	TUTOR PERINI CORPORATION, 1000 MAIN STREET, NEW ROCHELLE, NY, 10801	\$ 46,462,808.00	100.8861%	103.9453%
3	RICHARD E PIERSON CONSTRUCTION COMPANY, INC., P O BOX 430, WOODSTOWN, NJ, 08098	\$ 49,266,835.27	106.9746%	110.2184%
4	GEORGE & LYNCH, INC., 150 LAFFERTY LANE, DOVER, DE, 19901	\$ 51,660,683.11	112.1724%	115.5738%
5	ALLAN MYERS MD INC, PO BOX 278, FALLSTON, MD, 21047	\$ 52,273,277.00	113.5026%	116.9443%

LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY DE ONLY								
0020 202000	EXCAVATION AND EMBANKMENT	1049186.000 CY	6.50000	6819709.00	5.90000	6190197.40	6.00000	6295116.00
0030 202515	COMPACTING INSITU MATERIAL	720.000 SY	9.00000	6480.00	0.50000	360.00	10.00000	7200.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -2

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0040 202572	LUMP BORROW AREA EROSION & SEDIMENT CONTROL & DEWATERING		165000.00000	165000.00	125000.00000	125000.00	150000.00000	150000.00
0050 203000	110.000 CY CHANNEL EXCAVATION		45.00000	4950.00	21.00000	2310.00	35.00000	3850.00
0060 207000	22.000 CY EXCAVATION AND BACKFILL FOR STRUCTURES		40.00000	880.00	280.00000	6160.00	100.00000	2200.00
0070 208000	10228.000 CY EXCAVATION AND BACKFILLING FOR PIPE TRENCHES		10.00000	102280.00	6.00000	61368.00	5.00000	51140.00
0080 208001	17.000 CY FLOWABLE FILL		200.00000	3400.00	380.00000	6460.00	275.00000	4675.00
0090 209002	80814.000 CY BORROW, TYPE B		15.00000	1212210.00	20.00000	1616280.00	10.00000	808140.00
0100 211000	LUMP REMOVAL OF STRUCTURES AND OBSTRUCTIONS		30000.00000	30000.00	35000.00000	35000.00	50000.00000	50000.00
0110 211521	6.000 EACH ABANDONMENT OF WELLS		1000.00000	6000.00	1500.00000	9000.00	2500.00000	15000.00
0120 212000	1892.000 CY UNDERCUT EXCAVATION		11.70000	22136.40	8.20000	15514.40	9.00000	17028.00
0130 302007	22803.000 CY GRADED AGGREGATE BASE COURSE, TYPE B		34.25000	781002.75	58.00000	1322574.00	50.00000	1140150.00
0140 302011	1380.000 TON DELAWARE NO. 3 STONE		44.00000	60720.00	32.00000	44160.00	50.00000	69000.00
0150 304501	129994.000 SY PERMEABLE TREATED BASE, 4"		13.50000	1754919.00	14.00000	1819916.00	14.00000	1819916.00
0160 304502	126083.000 SY SOIL CEMENT BASE COURSE, 6"		6.25000	788018.75	7.00000	882581.00	5.00000	630415.00
0170 304506	2741.000 TON PORTLAND CEMENT		140.00000	383740.00	120.00000	328920.00	200.00000	548200.00
0180 401801	4257.000 TON BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS PG 64-22 (CARBONATE STONE)		85.00000	361845.00	71.00000	302247.00	86.00000	366102.00
0190 401810	15969.000 TON BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22		75.00000	1197675.00	64.00000	1022016.00	68.00000	1085892.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -3

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
0200 401819	19086.000 TON		75.00000	1431450.00	64.00000	1221504.00	68.00000
	BITUMINOUS CONCRETE, SUPERPAVE,						
	BITUMINOUS CONCRETE BASE COURSE, 160						
	GYRATIONS, PG 64-22						
							1297848.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -4

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT							
ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0210 401825	3.000 TON	150.00000	450.00	180.00000	540.00	700.00000	2100.00
BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22, WEDGE							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -5

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE		(1) GREGGO & FERRARA INC		(2) TUTOR PERINI CORPORATION	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0220 401827 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (NON-CARBONATE STONE)	7916.000 TON	90.00000	712440.00	71.00000	562036.00	73.00000	577868.00
0230 501006 PORTLAND CEMENT CONCRETE PAVEMENT, 12"	129978.000 SY	55.00000	7148790.00	59.00000	7668702.00	54.50000	7083801.00
0240 605755 OVERHEAD SIGN SUPPORTS AND FOUNDATIONS	LUMP	260000.00000	260000.00	334000.00000	334000.00	327000.00000	327000.00
0250 612020 REINFORCED CONCRETE PIPE, 12", CLASS IV	696.000 LF	40.00000	27840.00	67.00000	46632.00	40.00000	27840.00
0260 612022 REINFORCED CONCRETE PIPE, 18", CLASS IV	5973.000 LF	48.00000	286704.00	73.00000	436029.00	42.00000	250866.00
0270 612023 REINFORCED CONCRETE PIPE, 24", CLASS IV	2800.000 LF	62.00000	173600.00	85.00000	238000.00	51.00000	142800.00
0280 612025 REINFORCED CONCRETE PIPE, 30", CLASS IV	2426.000 LF	78.00000	189228.00	99.00000	240174.00	78.00000	189228.00
0290 612026 REINFORCED CONCRETE PIPE, 30", CLASS V	176.000 LF	85.00000	14960.00	110.00000	19360.00	150.00000	26400.00
0300 612027 REINFORCED CONCRETE PIPE, 42", CLASS IV	945.000 LF	120.00000	113400.00	130.00000	122850.00	175.00000	165375.00
0310 612028 REINFORCED CONCRETE PIPE, 48", CLASS IV	206.000 LF	160.00000	32960.00	160.00000	32960.00	200.00000	41200.00
0320 612030 REINFORCED CONCRETE PIPE, 18", CLASS V	304.000 LF	65.00000	19760.00	78.00000	23712.00	66.00000	20064.00
0330 612031 REINFORCED CONCRETE PIPE, 24", CLASS V	528.000 LF	70.00000	36960.00	96.00000	50688.00	72.00000	38016.00
0340 612034 REINFORCED CONCRETE PIPE, 36", CLASS IV	777.000 LF	120.00000	93240.00	120.00000	93240.00	140.00000	108780.00
0350 612038 REINFORCED CONCRETE PIPE, 60", CLASS IV	1065.000 LF	200.00000	213000.00	290.00000	308850.00	300.00000	319500.00
0360 612049 REINFORCED CONCRETE PIPE, 12", CLASS V	140.000 LF	65.00000	9100.00	67.00000	9380.00	50.00000	7000.00
0370 612205 REINFORCED CONCRETE ELLIPTICAL PIPE, 19"X30", CLASS IV	679.000 LF	90.00000	61110.00	120.00000	81480.00	150.00000	101850.00
0380 612216 REINFORCED CONCRETE ELLIPTICAL PIPE, 14"X23", CLASS IV	816.000 LF	120.00000	97920.00	100.00000	81600.00	65.00000	53040.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -6

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE		(1) GREGGO & FERRARA INC		(2) TUTOR PERINI CORPORATION	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0390 612219 REINFORCED CONCRETE ELLIPTICAL PIPE, 24"X38", CLASS IV	394.000 LF	120.00000	47280.00	140.00000	55160.00	200.00000	78800.00
0400 612535 CLEANING DRAINAGE PIPE, 15"-24" DIA	858.000 LF	4.00000	3432.00	7.00000	6006.00	10.00000	8580.00
0410 612536 CLEANING DRAINAGE PIPE, GREATER THAN 24" DIA	296.000 LF	6.00000	1776.00	9.00000	2664.00	15.00000	4440.00
0420 617001 REINFORCED CONCRETE FLARED END SECTION, 12"	15.000 EACH	750.00000	11250.00	1500.00000	22500.00	600.00000	9000.00
0430 617003 REINFORCED CONCRETE FLARED END SECTION, 18"	51.000 EACH	1000.00000	51000.00	1700.00000	86700.00	800.00000	40800.00
0440 617005 REINFORCED CONCRETE FLARED END SECTION, 24"	19.000 EACH	1100.00000	20900.00	1900.00000	36100.00	900.00000	17100.00
0450 617007 REINFORCED CONCRETE FLARED END SECTION, 30"	12.000 EACH	1450.00000	17400.00	2000.00000	24000.00	1000.00000	12000.00
0460 617164 REINFORCED CONCRETE FLARED END SECTION, 19" X 30"	4.000 EACH	1600.00000	6400.00	2100.00000	8400.00	1400.00000	5600.00
0470 617165 REINFORCED CONCRETE FLARED END SECTION, 14" X 23"	4.000 EACH	1500.00000	6000.00	1900.00000	7600.00	1200.00000	4800.00
0480 617174 REINFORCED CONCRETE FLARED END SECTION, 24" X 38"	2.000 EACH	2500.00000	5000.00	2700.00000	5400.00	2500.00000	5000.00
0490 617518 DRAINAGE HEADWALLS, MODIFIED	LUMP	96144.00000	96144.00	160000.00000	160000.00	200000.00000	200000.00
0500 701011 PORTLAND CEMENT CONCRETE CURB, TYPE 2	6204.000 LF	24.00000	148896.00	20.00000	124080.00	20.00000	124080.00
0510 701012 PORTLAND CEMENT CONCRETE CURB, TYPE 1-4	1877.000 LF	22.00000	41294.00	23.00000	43171.00	23.00000	43171.00
0520 701016 INTEGRAL PORTLAND CEMENT CONCRETE CURB & GUTTER, TYPE 1-4	1408.000 LF	28.00000	39424.00	27.00000	38016.00	26.00000	36608.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -7

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE		(1) GREGGO & FERRARA INC		(2) TUTOR PERINI CORPORATION	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0530 701022 INTEGRAL PORTLAND CEMENT & GUTTER, TYPE 3-8	3084.000	LF	25.00000	77100.00	19.00000	58596.00	18.00000	55512.00
0540 705001 P.C.C. SIDEWALK, 4"	6738.000	SF	9.00000	60642.00	7.00000	47166.00	7.00000	47166.00
0550 705002 P.C.C. SIDEWALK, 6"	29291.000	SF	12.00000	351492.00	8.00000	234328.00	8.00000	234328.00
0560 705007 SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	100.000	SF	30.90000	3090.00	37.00000	3700.00	50.00000	5000.00
0570 707005 UNDERDRAIN OUTLET	134.000	EACH	300.00000	40200.00	390.00000	52260.00	460.00000	61640.00
0580 708050 DRAINAGE INLET, 34" X 18"	17.000	EACH	2500.00000	42500.00	2000.00000	34000.00	3700.00000	62900.00
0590 708051 DRAINAGE INLET, 34" X 24"	14.000	EACH	2600.00000	36400.00	2500.00000	35000.00	4300.00000	60200.00
0600 708052 DRAINAGE INLET, 48" X 30"	14.000	EACH	2700.00000	37800.00	3100.00000	43400.00	4800.00000	67200.00
0610 708053 DRAINAGE INLET, 48" X 48"	12.000	EACH	2800.00000	33600.00	3100.00000	37200.00	4800.00000	57600.00
0620 708055 DRAINAGE INLET, 66" X 48"	3.000	EACH	5300.00000	15900.00	4900.00000	14700.00	7100.00000	21300.00
0630 708057 DRAINAGE INLET, 72" X 24"	4.000	EACH	3500.00000	14000.00	4800.00000	19200.00	7000.00000	28000.00
0640 708058 DRAINAGE INLET, 72" X 48"	3.000	EACH	5000.00000	15000.00	5400.00000	16200.00	7600.00000	22800.00
0650 708105 MANHOLE (SANITARY)	4.000	EACH	4500.00000	18000.00	3700.00000	14800.00	5700.00000	22800.00
0660 708111 MANHOLE, 48" X 30"	18.000	EACH	2500.00000	45000.00	3200.00000	57600.00	4100.00000	73800.00
0670 708112 MANHOLE, 48" X 48"	1.000	EACH	3000.00000	3000.00	3300.00000	3300.00	5000.00000	5000.00
0680 708114 MANHOLE, 66" X 48"	3.000	EACH	3000.00000	9000.00	5700.00000	17100.00	7200.00000	21600.00
0690 708583 PERSONNEL GRATE FOR PIPE INLET	6.000	EACH	700.00000	4200.00	2800.00000	16800.00	700.00000	4200.00
0700 708585 JUNCTION BOX, 48" X 30"	1.000	EACH	1450.00000	1450.00	1700.00000	1700.00	5400.00000	5400.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -8

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0710 708658	DRAINAGE INLETS, MODIFIED	LUMP	137154.00000	137154.00	113000.00000	113000.00	140000.00000	140000.00
0720 708659	DRAINAGE MANHOLES, MODIFIED	LUMP	62868.00000	62868.00	62000.00000	62000.00	70000.00000	70000.00
0730 712005	RIPRAP, R-4	2154.000 SY	26.00000	56004.00	32.00000	68928.00	50.00000	107700.00
0740 712006	RIPRAP, R-5	373.000 SY	52.00000	19396.00	70.00000	26110.00	70.00000	26110.00
0750 712007	RIPRAP, R-6	31.000 SY	65.00000	2015.00	73.00000	2263.00	125.00000	3875.00
0760 712531	CHANNEL BED FILL	15.000 CY	62.90000	943.50	25.00000	375.00	100.00000	1500.00
0770 713002	GEOTEXTILES, SEPARATION	7306.000 SY	1.50000	10959.00	1.10000	8036.60	2.00000	14612.00
0780 713003	GEOTEXTILES, RIPRAP	3776.000 SY	1.50000	5664.00	1.10000	4153.60	2.00000	7552.00
0790 715001	PERFORATED PIPE UNDERDRAINS, 6"	59887.000 LF	8.00000	479096.00	17.00000	1018079.00	12.00000	718644.00
0800 715500	UNDERDRAIN OUTLET PIPE, 6"	3642.000 LF	20.00000	72840.00	27.00000	98334.00	12.00000	43704.00
0810 716000	CONVERTING EXISTING DRAINAGE INLET TO JUNCTION BOX	1.000 EACH	1860.00000	1860.00	3100.00000	3100.00	4000.00000	4000.00
0820 720050	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-31	6563.000 LF	14.35000	94179.05	24.00000	157512.00	23.00000	150949.00
0830 720052	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 3-31	2275.000 LF	25.51000	58035.25	28.00000	63700.00	29.00000	65975.00
0840 720055	CURVED GUARDRAIL SECTION	282.000 LF	31.00000	8742.00	30.00000	8460.00	33.00000	9306.00
0850 720585	GUARDRAIL END TREATMENT ATTENUATOR, TYPE 1-31	5.000 EACH	2400.00000	12000.00	2800.00000	14000.00	2700.00000	13500.00
0860 720586	GUARDRAIL END TREATMENT ATTENUATOR, TYPE 2-31	11.000 EACH	2300.00000	25300.00	2500.00000	27500.00	2700.00000	29700.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -9

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0870 720588	10.000 EACH	3500.00000	35000.00	5100.00000	51000.00	6200.00000	62000.00
GUARDRAIL END TREATMENT ATTENUATOR, TYPE							
3-31							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -10

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0880 720611	FLEXIBLE DELINEATOR, PERMANENT	183.000 EACH	32.00000	5856.00	58.00000	10614.00	41.00000	7503.00
0890 720626	CONCRETE SINGLE FACE BARRIER, TYPE I	630.000 LF	150.00000	94500.00	140.00000	88200.00	88.00000	55440.00
0900 725001	GUARDRAIL TO BARRIER CONNECTION (EXIT TYPE 31)	5.000 EACH	585.00000	2925.00	590.00000	2950.00	700.00000	3500.00
0910 725002	GUARDRAIL TO BARRIER CONNECTION, APPROACH TYPE 1-31	7.000 EACH	1815.00000	12705.00	2100.00000	14700.00	2400.00000	16800.00
0920 726001	END ANCHORAGE 31	21.000 EACH	700.00000	14700.00	800.00000	16800.00	900.00000	18900.00
0930 727000	RIGHT-OF-WAY FENCE	27099.000 LF	4.00000	108396.00	19.00000	514881.00	11.00000	298089.00
0940 727001	RIGHT-OF-WAY FENCE GATE	3.000 EACH	1200.00000	3600.00	1300.00000	3900.00	800.00000	2400.00
0950 727014	CONSTRUCTION SAFETY FENCE	621.000 LF	2.15000	1335.15	1.60000	993.60	2.00000	1242.00
0960 727552	RESOURCE PROTECTION FENCE	5636.000 LF	2.30000	12962.80	2.00000	11272.00	2.00000	11272.00
0970 735501	HERBICIDE APPLICATION, NOXIOUS WEEDS	50.000 ACRE	275.00000	13750.00	130.00000	6500.00	130.00000	6500.00
0980 737523	PLANTINGS	LUMP	107970.00000	107970.00	120000.00000	120000.00	90000.00000	90000.00
0990 743000	MAINTENANCE OF TRAFFIC	LUMP	370267.00000	370267.00	180000.00000	180000.00	400000.00000	400000.00
1000 743003	ARROWPANELS, TYPE C	189.000 EADY	17.50000	3307.50	49.00000	9261.00	75.00000	14175.00
1010 743004	FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	317.000 EADY	40.00000	12680.00	57.00000	18069.00	75.00000	23775.00
1020 743005	FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	91.000 EADY	35.00000	3185.00	60.00000	5460.00	75.00000	6825.00
1030 743006	PLASTIC DRUMS	290542.000 EADY	0.30000	87162.60	1.10000	319596.20	0.05000	14527.10
1040 743007	TRAFFIC OFFICERS	924.000 HOUR	75.00000	69300.00	75.00000	69300.00	75.00000	69300.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -11

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1050 743010	534.000	EADY	150.00000	80100.00	280.00000	149520.00	450.00000	240300.00
FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II								
1060 743015	1745.000	LF	13.50000	23557.50	36.00000	62820.00	30.00000	52350.00
FURNISH AND MAINTAIN PORTABLE PCC SAFETY BARRIER								
1070 743016	1960.000	LF	4.53000	8878.80	4.00000	7840.00	20.00000	39200.00
RELOCATION PORATBLE SAFETY BARRIER								
1080 743023	271614.000	LF DY	1.50000	407421.00	0.68000	184697.52	0.17000	46174.38
TEMPORARY BARRICADES, TYPE III								
1090 743024	65228.000	EADY	1.50000	97842.00	2.60000	169592.80	1.60000	104364.80
TEMPORARY WARNING SIGNS AND PLAQUES								
1100 743025	11.000	EACH	750.00000	8250.00	1700.00000	18700.00	1100.00000	12100.00
INSTALL TEMPORARY IMPACT ATTENUATOR								
1110 743029	9.000	EACH	4490.00000	40410.00	14000.00000	126000.00	14300.00000	128700.00
FURNISH TEMPORARY IMPACT ATTENUATOR - NON-GATING, REDIRECTIVE, TEST LEVEL 3								
1120 743030	3.000	EACH	1365.00000	4095.00	2000.00000	6000.00	1500.00000	4500.00
RELOCATE TEMPORARY IMPACT ATTENUATOR								
1130 743031	1574.000	HOOR	80.00000	125920.00	50.00000	78700.00	95.00000	149530.00
ATSSA CERTIFIED TRAFFIC CONTROL SUPERVISOR								
1140 743056	5730.000	HOOR	52.90000	303117.00	51.00000	292230.00	50.00000	286500.00
FLAGGER, NEW CASTLE COUNTY, FEDERAL								
1150 743065	1146.000	HOOR	76.71000	87909.66	73.00000	83658.00	80.00000	91680.00
FLAGGER, NEW CASTLE COUNTY, FEDERAL, OVERTIME								
1160 744506	17.000	EACH	2000.00000	34000.00	2200.00000	37400.00	2087.36000	35485.12
CONDUIT JUNCTION WELL, TYPE 7, PRECAST POLYMER CONCRETE								
1170 744519	8.000	EACH	500.00000	4000.00	750.00000	6000.00	730.58000	5844.64
RELOCATION OF EXISTING JUNCTION WELL								
1180 744520	4.000	EACH	1100.00000	4400.00	900.00000	3600.00	887.13000	3548.52
CONDUIT JUNCTION WELL, TYPE 1, PRECAST CONCRETE								
1190 744523	1.000	EACH	1300.00000	1300.00	1500.00000	1500.00	1408.97000	1408.97
CONDUIT JUNCTION WELL, TYPE 4, PRECAST CONCRETE								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -12

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1200 744530	CONDUIT JUNCTION WELL, TYPE 11, PRECAST CONCRETE/ POLYMER LID-FRAME	125.000 EACH	1100.00000	137500.00	980.00000	122500.00	965.40000	120675.00
1210 744531	CONDUIT JUNCTION WELL, TYPE 14, PRECAST CONCRETE/ POLYMER LID-FRAME	56.000 EACH	1350.00000	75600.00	1500.00000	84000.00	1382.87000	77440.72
1220 744541	FURNISH & INSTALL FRAME AND LID FOR JUNCTION WELL, TYPE 11	3.000 EACH	420.00000	1260.00	400.00000	1200.00	391.38000	1174.14
1230 744542	FURNISH & INSTALL FRAME AND LID FOR JUNCTION WELL, TYPE 14	1.000 EACH	550.00000	550.00	780.00000	780.00	767.10000	767.10
1240 744544	ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	6.000 EACH	300.00000	1800.00	370.00000	2220.00	365.29000	2191.74
1250 745602	FURNISH & INSTALL UP TO 4" SCHEDULE 80 HDPE CONDUIT (BORE)	651.000 LF	34.00000	22134.00	32.00000	20832.00	31.31000	20382.81
1260 745604	FURNISH & INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	45263.000 LF	13.50000	611050.50	7.40000	334946.20	7.25000	328156.75
1270 745606	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (TRENCH)	2087.000 LF	30.00000	62610.00	26.00000	54262.00	24.79000	51736.73
1280 745609	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (ON STRUCTURE)	20.000 LF	41.00000	820.00	34.00000	680.00	33.03000	660.60
1290 746509	RELOCATING LIGHT POLE	13.000 EACH	2500.00000	32500.00	480.00000	6240.00	469.66000	6105.58
1300 746511	CABLES, 1/#4 AWG	3986.000 LF	2.40000	9566.40	0.69000	2750.34	0.68000	2710.48
1310 746512	CABLES, 1/#6 AWG	33809.000 LF	1.40000	47332.60	0.49000	16566.41	0.48000	16228.32
1320 746513	CABLES, 1/#8 AWG	318.000 LF	1.25000	397.50	0.43000	136.74	0.42000	133.56
1330 746515	INSULATED GROUND CABLES, 1/#6	9603.000 LF	1.65000	15844.95	0.49000	4705.47	0.48000	4609.44

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -13

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1340 746517	19.000 EACH	3000.00000	57000.00	2800.00000	53200.00	2724.00000	51756.00
ALUMINUM LIGHTING STANDARD WITH SINGLE							
DAVIT ARM, 30' POLE							

DATE : 01/21/16

PAGE : 001 -14

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1350 746519	16.000	EACH	3300.00000	52800.00	3000.00000	48000.00	2917.08000	46673.28
ALUMINUM LIGHTING STANDARD WITH SINGLE DAVIT ARM, 40' POLE								
1360 746527	12711.000	LF	2.25000	28599.75	1.20000	15253.20	1.15000	14617.65
CABLES, 1/#2 AWG								
1370 746541	93945.000	LF	0.50000	46972.50	1.80000	169101.00	1.71000	160645.95
INSTALLATION OF ELECTRICAL WIRE OR CABLE IN EMPTY CONDUITS								
1380 746564	625.000	LF	1.35000	843.75	0.69000	431.25	0.68000	425.00
INSULATED GROUND CABLES, 1/#4								
1390 746577	165.000	LF	1.35000	222.75	0.43000	70.95	0.42000	69.30
INSULATED GROUND CABLE, 1/#8								
1400 746586	140.000	SF	13.50000	1890.00	22.00000	3080.00	20.40000	2856.00
RELOCATE SIGN								
1410 746590	8.000	EACH	81.00000	648.00	120.00000	960.00	114.81000	918.48
FURNISH & INSTALL GROUND ROD								
1420 746594	45.000	EACH	350.00000	15750.00	360.00000	16200.00	354.85000	15968.25
LUMINAIRE (HPS), 250 WATT								
1430 746595	48.000	EACH	1500.00000	72000.00	2800.00000	134400.00	2687.47000	128998.56
ALUMINUM LIGHTING STANDARD, 40' POLE								
1440 746598	3234.000	LF	3.35000	10833.90	1.20000	3880.80	1.15000	3719.10
INSULATED GROUND CABLE , 1/#2								
1450 746615	80.000	LF	22.00000	1760.00	50.00000	4000.00	12.24000	979.20
PVC SCHEDULE 40 DUCT, 6"								
1460 746622	6868.000	LF	9.10000	62498.80	3.40000	23351.20	3.34000	22939.12
CABLES, 1/#4/0 AWG								
1470 746653		LUMP	9300.00000	9300.00	5300.00000	5300.00	5218.39000	5218.39
ELECTRICAL TESTING								
1480 746669	19.000	EACH	325.00000	6175.00	360.00000	6840.00	354.85000	6742.15
LUMINAIRE (HPS), 150 WATTS								
1490 746717	3.000	EACH	915.00000	2745.00	1800.00000	5400.00	1722.07000	5166.21
ELECTRIC SERVICE ON RACK WITH SERVICE RISER								
1500 746817	9953.000	LF	5.00000	49765.00	2.40000	23887.20	2.35000	23389.55
CABLES, 1/#2/0 AWG								
1510 746847	4.000	EACH	2600.00000	10400.00	2500.00000	10000.00	2400.46000	9601.84
POLE BASE, TYPE 3								
1520 746850	4.000	EACH	1000.00000	4000.00	700.00000	2800.00	694.05000	2776.20
POLE BASE, TYPE 4A								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -15

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1530 746852	POLE BASE, TYPE 6	82.000 EACH	950.00000	77900.00	1000.00000	82000.00	991.50000	81303.00
1540 746861	INSULATED GROUND CABLES, 1/350 KCMIL	6621.000 LF	12.50000	82762.50	5.20000	34429.20	5.11000	33833.31
1550 746872	LIGHTING CONTROL AND DISTRIBUTION ENCLOSURE	2.000 EACH	16000.00000	32000.00	12000.00000	24000.00	11376.10000	22752.20
1560 746903	INSULATED GROUND CABLES, 1/#2/0	4033.000 LF	6.50000	26214.50	2.40000	9679.20	2.35000	9477.55
1570 746904	INSULATED GROUND CABLES, 1/#4/0	1871.000 LF	8.75000	16371.25	3.40000	6361.40	3.34000	6249.14
1580 746924	FURNISH & INSTALL LOOP WIRE 1-CONDUCTOR #14 AWG ENCASED IN 1/4" FLEXIBLE TUBING IN A LOOP SAWCUT	3504.000 LF	13.00000	45552.00	15.00000	52560.00	14.35000	50282.40
1590 746951	RELOCATING POLE & MAST ARM	1.000 EACH	11000.00000	11000.00	640.00000	640.00	626.21000	626.21
1600 747515	CABINET BASE, TYPE M	4.000 EACH	1200.00000	4800.00	1700.00000	6800.00	1617.70000	6470.80
1610 747516	CABINET BASE, TYPE P	3.000 EACH	1200.00000	3600.00	1600.00000	4800.00	1617.70000	4853.10
1620 748015	PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	4301.000 SF	3.25000	13978.25	4.40000	18924.40	4.25000	18279.25
1630 748019	TEMPORARY MARKINGS, PAINT, 4"	9351.000 LF	0.21000	1963.71	0.30000	2805.30	1.00000	9351.00
1640 748026	TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	276.000 SF	3.25000	897.00	3.20000	883.20	5.00000	1380.00
1650 748032	TEMPORARY MARKINGS, PAINT, 5"	258.000 LF	0.23000	59.34	0.32000	82.56	3.00000	774.00
1660 748033	PERMANENT PAVEMENT STRIPING, ALKYD-THERMOPLASTIC, 5"	62.000 LF	3.00000	186.00	1.10000	68.20	5.00000	310.00
1670 748502	RAISED/RECESSED PAVEMENT MARKER	533.000 EACH	24.50000	13058.50	53.00000	28249.00	51.00000	27183.00
1680 748525	TEMPORARY MARKINGS, TAPE, 4"	37313.000 LF	1.53000	57088.89	1.40000	52238.20	2.00000	74626.00
1690 748527	TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS	520.000 SF	17.52000	9110.40	5.30000	2756.00	8.00000	4160.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -16

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1700 748530	10624.000 SF REMOVAL OF PAVEMENT STRIPING		1.50000	15936.00	2.50000	26560.00	2.50000	26560.00
1710 748548	146717.000 LF PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"		0.50000	73358.50	0.50000	73358.50	0.50000	73358.50
1720 748549	3812.000 LF PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 10"		1.75000	6671.00	1.00000	3812.00	1.00000	3812.00
1730 748553	49.000 EACH PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, BIKE SYMBOL		80.00000	3920.00	400.00000	19600.00	400.00000	19600.00
1740 748557	23558.000 LF PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 3"		0.60000	14134.80	0.62000	14605.96	0.60000	14134.80
1750 748566	5475.000 LF RETROREFLECTIVE PREFORMED PATTERNED MARKINGS, 8"		6.40000	35040.00	8.00000	43800.00	7.70000	42157.50
1760 748567	395.000 LF RETROREFLECTIVE PREFORMED PATTERNED MARKINGS, 13"		10.40000	4108.00	13.00000	5135.00	14.00000	5530.00
1770 749500	2553.000 SF SIGN PANEL		18.00000	45954.00	23.00000	58719.00	21.42000	54685.26
1840 749532	20.000 SF SUPPLY OF FLAT SHEET ALUMINUM SIGN PANEL, TYPE IX RETROREFLECTIVE SHEETING		10.00000	200.00	27.00000	540.00	25.50000	510.00
1880 749687	196.000 EACH INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST		72.00000	14112.00	110.00000	21560.00	127.50000	24990.00
1890 749688	10.000 EACH INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" DEPTH		20.00000	200.00	110.00000	1100.00	102.00000	1020.00
1900 749689	4.000 EACH INSTALLATION OF 4" DIAMETER HOLE, GREATER THAN 6" DEPTH		25.00000	100.00	110.00000	440.00	102.00000	408.00
1910 749690	1069.000 SF INSTALLATION OR REMOVAL OF TRAFFIC SIGNS ON MULTIPLE SIGN POSTS		15.00000	16035.00	16.00000	17104.00	12.24000	13084.56
1920 753503	262.000 LF INSTALLING SANITARY SEWER, PVC, 12"		85.00000	22270.00	45.00000	11790.00	100.00000	26200.00

DATE : 01/21/16

PAGE : 001 -17

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1930 758000	REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	19253.000 SY	10.00000	192530.00	8.00000	154024.00	4.00000	77012.00
1940 759506	FIELD OFFICE, TYPE II.22 SPECIAL COMPLE	30.000 EAMO	7500.00000	225000.00	4200.00000	126000.00	11000.00000	330000.00
1950 760012	RUMBLE STRIPS, BIKE-FRIENDLY, HOT-MIX	22362.000 LF	0.29000	6484.98	0.30000	6708.60	0.20000	4472.40
1960 760017	RUMBLE STRIPS, CONCRETE	59567.000 LF	0.75000	44675.25	0.61000	36335.87	0.50000	29783.50
1970 760507	PROFILE MILLING, BITUMINOUS CONCRETE	6786.000 SYIN	0.65000	4410.90	1.70000	11536.20	5.00000	33930.00
1980 762001	SAW CUTTING, BITUMINOUS CONCRETE	4764.000 LF	1.33000	6336.12	1.60000	7622.40	5.00000	23820.00
1990 762002	SAW CUTTING, CONCRETE, FULL DEPTH	697.000 LF	9.94000	6928.18	4.30000	2997.10	10.00000	6970.00
2000 763000	INITIAL EXPENSE	LUMP	1851373.00000	1851373.00	490000.00000	490000.00	2100000.00000	2100000.00
2010 763501	CONSTRUCTION ENGINEERING	LUMP	740550.00000	740550.00	300000.00000	300000.00	700000.00000	700000.00
2020 763503	TRAINEE	2000.000 HOUR	0.80000	1600.00	0.80000	1600.00	0.80000	1600.00
2030 763508	PROJECT CONTROL SYSTEM DEVELOPMENT PLAN	LUMP	75000.00000	75000.00	50000.00000	50000.00	50000.00000	50000.00
2040 763509	CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	30.000 EAMO	400.00000	12000.00	430.00000	12900.00	500.00000	15000.00
2050 763597	UTILITY CONSTRUCTION ENGINEERING	100.000 HOUR	100.00000	10000.00	150.00000	15000.00	150.00000	15000.00
2060 763619	WEIGH IN MOTION SYSTEM (WIM)	LUMP	240000.00000	240000.00	360000.00000	360000.00	241000.00000	241000.00
2070 763689	STRUCTURAL WORK, GANTRY	LUMP	100800.00000	100800.00	110000.00000	110000.00	50000.00000	50000.00
2080 900500	ENVIRONMENTAL PERFORMANCE INCENTIVE (DISINCENTIVE)	LUMP	488000.00000	488000.00	488000.00000	488000.00	488000.00000	488000.00
2090 905001	SILT FENCE	12571.000 LF	2.40000	30170.40	1.40000	17599.40	3.00000	37713.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -18

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
ITEM DESCRIPTION								
2100 905002	45734.000	LF	2.55000	116621.70	3.70000	169215.80	4.00000	182936.00
REINFORCED SILT FENCE								
2110 905003	1303.000	CY	7.40000	9642.20	17.00000	22151.00	25.00000	32575.00
SEDIMENT TRAP								
2120 905004	16.000	EACH	160.00000	2560.00	320.00000	5120.00	300.00000	4800.00
INLET SEDIMENT CONTROL, DRAINAGE INLET								
2130 905005	11.000	EACH	160.00000	1760.00	320.00000	3520.00	300.00000	3300.00
INLET SEDIMENT CONTROL, CURB INLET								
2140 906001	1.000	EACH	290.00000	290.00	1200.00000	1200.00	4000.00000	4000.00
PORTABLE SEDIMENT TANK								
2150 906002	9.000	EACH	2000.00000	18000.00	500.00000	4500.00	500.00000	4500.00
DEWATERING BAG								
2160 906003	1.000	EACH	1500.00000	1500.00	1900.00000	1900.00	7000.00000	7000.00
SUMP PIT								
2170 906004	11.000	EACH	545.00000	5995.00	2100.00000	23100.00	1900.00000	20900.00
SKIMMER DEWATERING DEVICE								
2180 907011	47.000	TON	45.00000	2115.00	58.00000	2726.00	100.00000	4700.00
STONE CHECK DAM								
2190 908010	500754.000	SY	1.00000	500754.00	2.20000	1101658.80	0.95000	475716.30
TOPSOILING, 6" DEPTH								
2200 908014	519169.000	SY	0.35000	181709.15	0.63000	327076.47	0.52000	269967.88
PERMANENT GRASS SEEDING, DRY GROUND								
2210 908015	450305.000	SY	0.45000	202637.25	0.53000	238661.65	0.50000	225152.50
PERMANENT GRASS SEEDING, WET GROUND								
2220 908017	468154.000	SY	0.25000	117038.50	0.40000	187261.60	0.40000	187261.60
TEMPORARY GRASS SEEDING								
2230 908019	50.000	SY	1.00000	50.00	11.00000	550.00	20.00000	1000.00
STREAMBANK SEED MIX, SEEDING								
2240 908020	123047.000	SY	1.50000	184570.50	2.10000	258398.70	1.90000	233789.30
EROSION CONTROL BLANKET MULCH								
2250 908021	1824.000	SY	8.00000	14592.00	7.70000	14044.80	6.00000	10944.00
TURF REINFORCEMENT MATTING, TYPE 1								
2260 908023	1259.000	TON	32.00000	40288.00	30.00000	37770.00	50.00000	62950.00
STABILIZED CONSTRUCTION ENTRANCE								
2270 908503	25854.000	SY	0.50000	12927.00	0.58000	14995.32	0.70000	18097.80
WETLAND MITIGATION GRASS SEEDING								
2300 910004	2981.000	CY	30.00000	89430.00	65.00000	193765.00	10.00000	29810.00
CLAY BORROW, CUT-OFF TRENCH								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -19

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2310 910007	OUTLET STRUCTURE	LUMP	277138.00000	277138.00	440000.00000	440000.00	750000.00000	750000.00
2320 910009	INFILTRATION TRENCH	200.000 LF	30.00000	6000.00	61.00000	12200.00	90.00000	18000.00
4040 605501	GROUND MOUNT BREAKAWAY TYPE SIGN SUPPORTS AND FOUNDATION	LUMP	72531.00000	72531.00	115000.00000	115000.00	109000.00000	109000.00
4060 201000	CLEARING AND GRUBBING	LUMP	530000.00000	530000.00	250000.00000	250000.00	796589.89000	796589.89
4080 907507	EARTH DIKE, TYPE A-2	1880.000 LF	15.00000	28200.00	18.00000	33840.00	14.00000	26320.00
4090 909005	STREAM DIVERSION	LUMP	15000.00000	15000.00	48000.00000	48000.00	60000.00000	60000.00
SECTION TOTALS			\$ 37,735,266.88		\$ 38,536,308.71		\$ 38,540,092.48	
SECTION 0002 BRIDGE 1-486 STANDARD ITEMS								
2330 202505	SETTLEMENT PLATFORM	4.000 EACH	5250.00000	21000.00	1300.00000	5200.00	2000.00000	8000.00
2340 207000	EXCAVATION AND BACKFILL FOR STRUCTURES	216.000 CY	40.00000	8640.00	61.00000	13176.00	50.00000	10800.00
2350 602006	PORTLAND CEMENT CONCRETE MASONRY, PIER FOOTING, CLASS B	94.000 CY	350.00000	32900.00	340.00000	31960.00	500.00000	47000.00
2360 602007	PORTLAND CEMENT CONCRETE MASONRY, PIER ABOVE FOOTING, CLASS A	70.000 CY	750.00000	52500.00	1100.00000	77000.00	1000.00000	70000.00
2370 602013	PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D	195.000 CY	800.00000	156000.00	880.00000	171600.00	850.00000	165750.00
2380 602014	PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D	110.000 CY	500.00000	55000.00	440.00000	48400.00	550.00000	60500.00
2390 602015	PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A	70.000 CY	750.00000	52500.00	1300.00000	91000.00	1200.00000	84000.00
2400 602017	PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A	50.000 CY	900.00000	45000.00	780.00000	39000.00	1300.00000	65000.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -20

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)			(1)			(2)		
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION				
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	
2410 602772	LUMP		364000.00000	364000.00	237000.00000	237000.00	500000.00000	500000.00			
	MECHANICALLY STABILIZED EARTH WALLS										
2420 604000	135000.000	LB	1.40000	189000.00	1.20000	162000.00	1.30000	175500.00			
	BAR REINFORCEMENT, EPOXY COATED										
2430 608000	20.000	TON	35.00000	700.00	35.00000	700.00	100.00000	2000.00			
	COARSE AGGREGATE FOR FOUNDATION										
	STABILIZATION AND SUBFOUNDATION BACKFILL										
2440 623003	LUMP		160000.00000	160000.00	250000.00000	250000.00	245000.00000	245000.00			
	PRESTRESSED REINFORCED CONCRETE MEMBERS										
	BULB T BEAM										
2450 727507	290.000	LF	40.00000	11600.00	170.00000	49300.00	200.00000	58000.00			
	BRIDGE SAFETY FENCE										
	SECTION TOTALS		\$	1,148,840.00	\$	1,176,336.00	\$	1,491,550.00			
SECTION 0003 BRIDGE 1-486 PILE ALTERNATE 1											
2460 618062	854.000	LF	35.00000	29890.00	39.00000	33306.00	95.00000	81130.00			
	STEEL H PILES, HP 14 X 73										
2470 618065	142.000	LF	50.00000	7100.00	42.00000	5964.00	95.00000	13490.00			
	STEEL H TEST PILES, HP 14 X 73										
2480 619042	854.000	LF	25.00000	21350.00	22.00000	18788.00	65.00000	55510.00			
	INSTALL STEEL H PILES, HP 14 X 73										
2490 619045	142.000	LF	60.00000	8520.00	53.00000	7526.00	50.00000	7100.00			
	INSTALL STEEL H TEST PILES, HP 14 X 73										
2500 619501	1.000	EACH	500.00000	500.00	500.00000	500.00	500.00000	500.00			
	PRODUCTION PILE RESTRIKE										
2510 619502	1.000	EADY	1000.00000	1000.00	1000.00000	1000.00	1000.00000	1000.00			
	TEST PILE RESTRIKE										
2520 619519	4.000	EACH	2500.00000	10000.00	2000.00000	8000.00	2500.00000	10000.00			
	DYNAMIC PILE TESTING BY CONTRACTOR										
2530 619539	4.000	EACH	400.00000	1600.00	1000.00000	4000.00	600.00000	2400.00			
	SIGNAL MATCHING ANALYSIS BY CONTRACTOR										
	SECTION TOTALS		\$	79,960.00	\$	79,084.00	\$	171,130.00			
SECTION 0004 BRIDGE 1-486 PILE ALTERNATE 2											
2540 618552	924.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00			
	FURNISH PIPE PILE, SCHEDULE 40, OPEN										
	END, 14"										

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -21

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2550 618557	152.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH TEST PIPE PILE, SCHEDULE 40, OPEN END, 14"								
2560 619501	1.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
PRODUCTION PILE RESTRIKE								
2570 619502	1.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
TEST PILE RESTRIKE								
2580 619519	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
DYNAMIC PILE TESTING BY CONTRACTOR								
2590 619539	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
SIGNAL MATCHING ANALYSIS BY CONTRACTOR								
2600 619540	924.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL PIPE PILE, SCHEDULE 40, OPEN END, 14"								
2610 619558	152.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL TEST PIPE PILE, SCHEDULE 40, OPEN END, 14"								
SECTION TOTALS			\$	0.00	\$	0.00	\$	0.00
SECTION 0005 BRIDGE 1-482 STANDARD ITEMS								
2620 202505	4.000	EACH	5250.00000	21000.00	1300.00000	5200.00	2000.00000	8000.00
SETTLEMENT PLATFORM								
2630 207000	313.000	CY	40.00000	12520.00	61.00000	19093.00	50.00000	15650.00
EXCAVATION AND BACKFILL FOR STRUCTURES								
2640 602006	178.000	CY	350.00000	62300.00	340.00000	60520.00	300.00000	53400.00
PORTLAND CEMENT CONCRETE MASONRY, PIER FOOTING, CLASS B								
2650 602007	111.000	CY	750.00000	83250.00	940.00000	104340.00	900.00000	99900.00
PORTLAND CEMENT CONCRETE MASONRY, PIER ABOVE FOOTING, CLASS A								
2660 602013	443.000	CY	800.00000	354400.00	980.00000	434140.00	750.00000	332250.00
PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D								
2670 602014	237.000	CY	500.00000	118500.00	440.00000	104280.00	400.00000	94800.00
PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -22

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2680 602015	PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A	120.000 CY	750.00000	90000.00	1300.00000	156000.00	1000.00000	120000.00

DATE : 01/21/16

PAGE : 001 -23

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2690 602017	51.000	CY	900.000000	45900.00	780.000000	39780.00	1300.000000	66300.00
PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A								
2700 602772		LUMP	439950.000000	439950.00	293000.000000	293000.00	600000.000000	600000.00
MECHANICALLY STABILIZED EARTH WALLS								
2710 604000	258953.000	LB	1.400000	362534.20	1.200000	310743.60	1.300000	336638.90
BAR REINFORCEMENT, EPOXY COATED								
2720 608000	18.000	TON	35.000000	630.00	29.000000	522.00	100.000000	1800.00
COARSE AGGREGATE FOR FOUNDATION STABILIZATION AND SUBFOUNDATION BACKFILL								
2730 623003		LUMP	279928.000000	279928.00	410000.000000	410000.00	338000.000000	338000.00
PRESTRESSED REINFORCED CONCRETE MEMBERS BULB T BEAM								
2740 727507	354.000	LF	40.000000	14160.00	170.000000	60180.00	200.000000	70800.00
BRIDGE SAFETY FENCE								
SECTION TOTALS			\$	1,885,072.20	\$	1,997,798.60	\$	2,137,538.90
SECTION 0006 BRIDGE 1-482 PILE ALTERNATE 1								
2750 618062	1836.000	LF	35.000000	64260.00	39.000000	71604.00	95.000000	174420.00
STEEL H PILES, HP 14 X 73								
2760 618065	135.000	LF	50.000000	6750.00	42.000000	5670.00	95.000000	12825.00
STEEL H TEST PILES, HP 14 X 73								
2770 619042	1836.000	LF	25.000000	45900.00	22.000000	40392.00	50.000000	91800.00
INSTALL STEEL H PILES, HP 14 X 73								
2780 619045	135.000	LF	60.000000	8100.00	53.000000	7155.00	50.000000	6750.00
INSTALL STEEL H TEST PILES, HP 14 X 73								
2790 619501	1.000	EACH	500.000000	500.00	500.000000	500.00	500.000000	500.00
PRODUCTION PILE RESTRIKE								
2800 619502	1.000	EADY	1000.000000	1000.00	1000.000000	1000.00	1000.000000	1000.00
TEST PILE RESTRIKE								
2810 619519	4.000	EACH	2500.000000	10000.00	2000.000000	8000.00	2500.000000	10000.00
DYNAMIC PILE TESTING BY CONTRACTOR								
2820 619539	4.000	EACH	400.000000	1600.00	1000.000000	4000.00	600.000000	2400.00
SIGNAL MATCHING ANALYSIS BY CONTRACTOR								
SECTION TOTALS			\$	138,110.00	\$	138,321.00	\$	299,695.00
SECTION 0007 BRIDGE 1-482 PILE ALTERNATE 2								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -24

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2830 618552	2156.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH PIPE PILE, SCHEDULE 40, OPEN								
END, 14"								
2840 618557	155.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH TEST PIPE PILE, SCHEDULE 40,								
OPEN END, 14"								
2850 619501	1.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
PRODUCTION PILE RESTRIKE								
2860 619502	1.000	EADY	0.00000	0.00	0.00000	0.00	0.00000	0.00
TEST PILE RESTRIKE								
2870 619519	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
DYNAMIC PILE TESTING BY CONTRACTOR								
2880 619539	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
SIGNAL MATCHING ANALYSIS BY CONTRACTOR								
2890 619540	2156.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL PIPE PILE, SCHEDULE 40, OPEN								
END, 14"								
2900 619558	155.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL TEST PIPE PILE, SCHEDULE 40,								
OPEN END, 14"								
SECTION TOTALS			\$	0.00	\$	0.00	\$	0.00
SECTION 0008 BRIDGE 1-482 PILE ALTERNATE 3								
2910 618050	1612.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH STEEL SHELL PILES, 14"								
2920 618051	121.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH TEST STEEL SHELL PILES, 14"								
2930 619055	1612.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL STEEL SHELL PILES, 14"								
2940 619056	121.000	LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL TEST STEEL SHELL PILES, 14"								
2950 619501	1.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
PRODUCTION PILE RESTRIKE								
2960 619502	1.000	EADY	0.00000	0.00	0.00000	0.00	0.00000	0.00
TEST PILE RESTRIKE								
2970 619519	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
DYNAMIC PILE TESTING BY CONTRACTOR								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -25

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
ITEM DESCRIPTION								
2980 619539	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
SIGNAL MATCHING ANALYSIS BY CONTRACTOR								
SECTION TOTALS			\$	0.00	\$	0.00	\$	0.00
SECTION 0009 MARYLAND QUANTITIES								
2990 202000	56440.000	CY	6.50000	366860.00	6.50000	366860.00	2.00000	112880.00
EXCAVATION AND EMBANKMENT								
3000 202569	2602.000	SY	20.00000	52040.00	71.00000	184742.00	30.00000	78060.00
POND ACCESS ROAD, MARYLAND								
3010 208000	333.000	CY	10.00000	3330.00	6.00000	1998.00	9.00000	2997.00
EXCAVATION AND BACKFILLING FOR PIPE								
TRENCHES								
3020 208001	6.000	CY	200.00000	1200.00	380.00000	2280.00	300.00000	1800.00
FLOWABLE FILL								
3030 209002	2837.000	CY	15.00000	42555.00	20.00000	56740.00	10.00000	28370.00
BORROW, TYPE B								
3040 211002	63.000	LF	3.00000	189.00	5.30000	333.90	20.00000	1260.00
REMOVAL OF STRUCTURES AND OBSTRUCTIONS								
(GUARDRAIL)								
3050 255502	3.000	TON	44.00000	132.00	200.00000	600.00	600.00000	1800.00
GABION OUTLET STRUCTURE, MARYLAND								
3060 272511		LUMP	75254.00000	75254.00	140000.00000	140000.00	200000.00000	200000.00
POND OUTLET STRUCTURE, CONCRETE,								
MARYLAND								
3070 302007	966.000	CY	34.25000	33085.50	58.00000	56028.00	60.00000	57960.00
GRADED AGGREGATE BASE COURSE, TYPE B								
3080 302012	2923.000	TON	30.00000	87690.00	32.00000	93536.00	30.00000	87690.00
DELAWARE NO. 57 STONE								
3090 304501	14264.000	SY	13.50000	192564.00	14.00000	199696.00	14.00000	199696.00
PERMEABLE TREATED BASE, 4"								
3100 304502	13852.000	SY	6.25000	86575.00	7.00000	96964.00	5.00000	69260.00
SOIL CEMENT BASE COURSE, 6"								
3110 304506	247.000	TON	140.00000	34580.00	120.00000	29640.00	200.00000	49400.00
PORTLAND CEMENT								
3120 401801	547.000	TON	85.00000	46495.00	71.00000	38837.00	81.00000	44307.00
BITUMINOUS CONCRETE, SUPERPAVE, TYPE C,								
160 GYRATIONS PG 64-22 (CARBONATE STONE)								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -26

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE		(1) GREGGO & FERRARA INC		(2) TUTOR PERINI CORPORATION	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3130 401810 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22	63.000 TON	75.00000	4725.00	64.00000	4032.00	158.00000	9954.00
3140 401819 BITUMINOUS CONCRETE, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22	2232.000 TON	75.00000	167400.00	64.00000	142848.00	78.00000	174096.00
3150 401825 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22, WEDGE	33.000 TON	150.00000	4950.00	180.00000	5940.00	158.00000	5214.00
3160 401827 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (NON-CARBONATE STONE)	2772.000 TON	90.00000	249480.00	71.00000	196812.00	78.00000	216216.00
3170 501006 PORTLAND CEMENT CONCRETE PAVEMENT, 12"	14264.000 SY	55.00000	784520.00	58.00000	827312.00	54.00000	770256.00
3180 612022 REINFORCED CONCRETE PIPE, 18", CLASS IV	70.000 LF	42.00000	2940.00	73.00000	5110.00	50.00000	3500.00
3190 612023 REINFORCED CONCRETE PIPE, 24", CLASS IV	362.000 LF	50.00000	18100.00	85.00000	30770.00	100.00000	36200.00
3200 612205 REINFORCED CONCRETE ELLIPTICAL PIPE, 19"X30", CLASS IV	88.000 LF	80.00000	7040.00	120.00000	10560.00	100.00000	8800.00
3210 612210 REINFORCED CONCRETE ELLIPTICAL PIPE, 22"X34", CLASS IV	66.000 LF	85.00000	5610.00	140.00000	9240.00	120.00000	7920.00
3220 612505 PVC PIPE, 12"	291.000 LF	30.00000	8730.00	40.00000	11640.00	80.00000	23280.00
3230 612526 CORRUGATED POLYETHYLENE PIPE, TYPE S, 36"	100.000 LF	65.00000	6500.00	55.00000	5500.00	90.00000	9000.00
3240 612535 CLEANING DRAINAGE PIPE, 15"-24" DIA	70.000 LF	4.00000	280.00	7.00000	490.00	15.00000	1050.00
3250 612536 CLEANING DRAINAGE PIPE, GREATER THAN 24" DIA	255.000 LF	6.00000	1530.00	9.00000	2295.00	15.00000	3825.00
3260 617519 CONCRETE END SECTION, 24", MARYLAND	4.000 EACH	1300.00000	5200.00	1900.00000	7600.00	1000.00000	4000.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -27

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE		(1) GREGGO & FERRARA INC		(2) TUTOR PERINI CORPORATION	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3270 617520 CONCRETE END SECTION, 19"X 30", MARYLAN	1.000 EACH	2000.00000	2000.00	2100.00000	2100.00	1200.00000	1200.00
3280 617521 CONCRETE END SECTION, 22"X34", MARYLAND	1.000 EACH	2200.00000	2200.00	2700.00000	2700.00	1500.00000	1500.00
3290 708660 DRAINAGE INLET, TYPE K, SINGLE, MARYLAN	6.000 EACH	3000.00000	18000.00	3600.00000	21600.00	6000.00000	36000.00
3300 712005 RIPRAP, R-4	783.000 SY	26.00000	20358.00	32.00000	25056.00	70.00000	54810.00
3310 712552 RIPRAP SLOPE PROTECTION, MARYLAND	476.000 SY	54.00000	25704.00	65.00000	30940.00	70.00000	33320.00
3320 713003 GEOTEXTILES, RIPRAP	3713.000 SY	1.50000	5569.50	1.10000	4084.30	2.00000	7426.00
3330 715001 PERFORATED PIPE UNDERDRAINS, 6"	3238.000 LF	8.00000	25904.00	17.00000	55046.00	12.00000	38856.00
3340 715004 PERFORATED PIPE UNDERDRAINS, 12"	520.000 LF	20.00000	10400.00	46.00000	23920.00	41.00000	21320.00
3350 715500 UNDERDRAIN OUTLET PIPE, 6"	273.000 LF	20.00000	5460.00	27.00000	7371.00	12.00000	3276.00
3360 720043 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-27	653.000 LF	14.35000	9370.55	25.00000	16325.00	23.00000	15019.00
3370 720044 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 2-27	63.000 LF	28.70000	1808.10	30.00000	1890.00	31.00000	1953.00
3380 720050 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-31	300.000 LF	14.35000	4305.00	25.00000	7500.00	23.00000	6900.00
3390 720051 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 2-31	50.000 LF	28.70000	1435.00	32.00000	1600.00	31.00000	1550.00
3400 720585 GUARDRAIL END TREATMENT ATTENUATOR, TYPE 1-31	1.000 EACH	2400.00000	2400.00	2800.00000	2800.00	2700.00000	2700.00
3410 720611 FLEXIBLE DELINEATOR, PERMANENT	17.000 EACH	32.00000	544.00	58.00000	986.00	41.00000	697.00
3420 727552 RESOURCE PROTECTION FENCE	1785.000 LF	2.30000	4105.50	2.00000	3570.00	2.00000	3570.00
3430 727553 DIVERSION FENCE, MARYLAND	335.000 LF	3.00000	1005.00	13.00000	4355.00	10.00000	3350.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -28

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3440 734555	91022.000 SY TEMPORARY VEGETATIVE STABILIZATION, MARYLAND		1.25000	113777.50	0.48000	43690.56	0.40000	36408.80
3450 734556	82149.000 SY PERMANENT VEGETATIVE STABILIZATION, MARYLAND		1.25000	102686.25	0.70000	57504.30	0.60000	49289.40
3460 737531	LUMP PLANTINGS, MARYLAND		103635.00000	103635.00	60000.00000	60000.00	73000.00000	73000.00
3470 743003	4.000 EADY ARROWPANELS, TYPE C		17.50000	70.00	49.00000	196.00	200.00000	800.00
3480 743004	72.000 EADY FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN		40.00000	2880.00	57.00000	4104.00	95.00000	6840.00
3490 743006	57020.000 EADY PLASTIC DRUMS		0.30000	17106.00	1.10000	62722.00	1.00000	57020.00
3500 743010	223.000 EADY FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II		150.00000	33450.00	280.00000	62440.00	440.00000	98120.00
3510 743015	2205.000 LF FURNISH AND MAINTAIN PORTABLE PCC SAFETY BARRIER		13.50000	29767.50	36.00000	79380.00	30.00000	66150.00
3520 743016	1190.000 LF RELOCATION PORTABLE SAFETY BARRIER		4.53000	5390.70	4.00000	4760.00	20.00000	23800.00
3530 743023	10650.000 LFDY TEMPORARY BARRICADES, TYPE III		1.50000	15975.00	0.68000	7242.00	0.16000	1704.00
3540 743024	32564.000 EADY TEMPORARY WARNING SIGNS AND PLAQUES		1.50000	48846.00	2.60000	84666.40	1.60000	52102.40
3550 743025	5.000 EACH INSTALL TEMPORARY IMPACT ATTENUATOR		750.00000	3750.00	1700.00000	8500.00	1100.00000	5500.00
3560 743029	2.000 EACH FURNISH TEMPORARY IMPACT ATTENUATOR - NON-GATING, REDIRECTIVE, TEST LEVEL 3		4490.00000	8980.00	14000.00000	28000.00	15000.00000	30000.00
3570 743030	2.000 EACH RELOCATE TEMPORARY IMPACT ATTENUATOR		1365.00000	2730.00	2000.00000	4000.00	1500.00000	3000.00
3580 744506	2.000 EACH CONDUIT JUNCTION WELL, TYPE 7, PRECAST POLYMER CONCRETE		2000.00000	4000.00	2200.00000	4400.00	2087.36000	4174.72

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -29

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
							AMOUNT
3590 744530	CONDUIT JUNCTION WELL, TYPE 11, PRECAST CONCRETE/ POLYMER LID-FRAME	9.000 EACH	1100.00000	9900.00	990.00000	8910.00	975.84000
							8782.56

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -30

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)	(1)		(2)		
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3600 744531	CONDUIT JUNCTION WELL, TYPE 14, PRECAST CONCRETE/ POLYMER LID-FRAME	4.000 EACH	1350.00000	5400.00	1400.00000	5600.00	1382.88000	5531.52
3610 745602	FURNISH & INSTALL UP TO 4" SCHEDULE 80 HDPE CONDUIT (BORE)	295.000 LF	34.00000	10030.00	32.00000	9440.00	31.31000	9236.45
3620 745604	FURNISH & INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	2880.000 LF	13.50000	38880.00	7.50000	21600.00	7.31000	21052.80
3630 745606	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (TRENCH)	5.000 LF	30.00000	150.00	25.00000	125.00	24.79000	123.95
3640 746586	RELOCATE SIGN	52.000 SF	13.50000	702.00	11.00000	572.00	10.20000	530.40
3650 746852	POLE BASE, TYPE 6	2.000 EACH	950.00000	1900.00	1100.00000	2200.00	991.50000	1983.00
3660 748032	TEMPORARY MARKINGS, PAINT, 5"	9079.000 LF	0.23000	2088.17	0.30000	2723.70	1.00000	9079.00
3670 748034	TEMPORARY MARKINGS, PAINT, 10"	810.000 LF	0.48000	388.80	0.60000	486.00	1.00000	810.00
3680 748525	TEMPORARY MARKINGS, TAPE, 4"	10915.000 LF	1.53000	16699.95	1.40000	15281.00	2.00000	21830.00
3690 748527	TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS	120.000 SF	17.52000	2102.40	5.30000	636.00	8.00000	960.00
3700 748530	REMOVAL OF PAVEMENT STRIPING	3551.000 SF	1.50000	5326.50	2.50000	8877.50	3.00000	10653.00
3710 748560	5" WHITE PERMANENT PATTERNED REFLECTIVE PAVEMENT MARKING TAPE, MARYLAND	20532.000 LF	4.00000	82128.00	4.20000	86234.40	4.00000	82128.00
3720 748563	SNOWPLOWABLE RAISED PAVEMENT MARKERS, MARYLAND	115.000 EACH	24.50000	2817.50	34.00000	3910.00	33.00000	3795.00
3730 749500	SIGN PANEL	320.000 SF	18.00000	5760.00	26.00000	8320.00	25.00000	8000.00
3790 749687	INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	26.000 EACH	72.00000	1872.00	110.00000	2860.00	130.00000	3380.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -31

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3800 749690	477.000 SF	15.00000	7155.00	16.00000	7632.00	13.00000	6201.00
INSTALLATION OR REMOVAL OF TRAFFIC							
SIGNS ON MULTIPLE SIGN POSTS							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -32

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3810 756000	SAND	143.000 TON	35.00000	5005.00	19.00000	2717.00	50.00000	7150.00
3820 760006	PAVEMENT - MILLING, HOT-MIX, 2" DEPTH	21343.000 SY	1.65000	35215.95	1.20000	25611.60	3.50000	74700.50
3830 760016	RUMBLE STRIPS, HOT-MIX	11700.000 LF	0.29000	3393.00	0.30000	3510.00	0.20000	2340.00
3840 760017	RUMBLE STRIPS, CONCRETE	5800.000 LF	0.75000	4350.00	0.61000	3538.00	0.50000	2900.00
3850 760507	PROFILE MILLING, BITUMINOUS CONCRETE	2887.000 SYIN	0.65000	1876.55	0.60000	1732.20	6.00000	17322.00
3860 762001	SAW CUTTING, BITUMINOUS CONCRETE	2763.000 LF	1.33000	3674.79	1.60000	4420.80	5.00000	13815.00
3870 763573	SIGN, MARYLAND	1.000 EACH	375.00000	375.00	1100.00000	1100.00	2000.00000	2000.00
3880 763656	ASBUILT CERTIFICATION, MARYLAND	LUMP	16000.00000	16000.00	12000.00000	12000.00	30000.00000	30000.00
3890 763686	TRAFFIC OFFICER, MARYLAND	432.000 HOUR	98.16000	42405.12	98.16000	42405.12	98.16000	42405.12
3900 763691	FLAGGER, MARYLAND, STATE	500.000 HOUR	41.67000	20835.00	37.00000	18500.00	50.00000	25000.00
3910 763692	FLAGGER, MARYLAND, STATE, OVERTIME	100.000 HOUR	60.42000	6042.00	55.00000	5500.00	80.00000	8000.00
3920 905001	SILT FENCE	216.000 LF	2.40000	518.40	1.40000	302.40	2.00000	432.00
3930 905003	SEDIMENT TRAP	2818.000 CY	7.40000	20853.20	13.00000	36634.00	10.00000	28180.00
3940 905004	INLET SEDIMENT CONTROL, DRAINAGE INLET	7.000 EACH	160.00000	1120.00	320.00000	2240.00	300.00000	2100.00
3950 905500	SUPER SILT FENCE	5311.000 LF	8.30000	44081.30	6.70000	35583.70	9.00000	47799.00
3960 906002	DEWATERING BAG	1.000 EACH	2000.00000	2000.00	500.00000	500.00	2000.00000	2000.00
3970 907011	STONE CHECK DAM	9.000 TON	45.00000	405.00	95.00000	855.00	150.00000	1350.00
3980 908010	TOPSOILING, 6" DEPTH	53274.000 SY	1.00000	53274.00	2.20000	117202.80	1.40000	74583.60
3990 908020	EROSION CONTROL BLANKET MULCH	7828.000 SY	1.50000	11742.00	2.10000	16438.80	1.80000	14090.40

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -33

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		GREGGO & FERRARA INC		TUTOR PERINI CORPORATION	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
4000 908023	529.000	TON	32.00000	16928.00	30.00000	15870.00	50.00000	26450.00
STABILIZED CONSTRUCTION ENTRANCE								
4010 910002	844.000	TON	45.00000	37980.00	44.00000	37136.00	50.00000	42200.00
INFILTRATION STONE, NO. 8								
4020 910004	4926.000	CY	30.00000	147780.00	45.00000	221670.00	10.00000	49260.00
CLAY BORROW, CUT-OFF TRENCH								
4030 910500	290.000	CY	35.00000	10150.00	66.00000	19140.00	150.00000	43500.00
BIORETENTION SOIL MIX								
4050 605501		LUMP	14568.00000	14568.00	22000.00000	22000.00	21000.00000	21000.00
GROUND MOUNT BREAKAWAY TYPE SIGN								
SUPPORTS AND FOUNDATION								
4070 201000		LUMP	95000.00000	95000.00	43000.00000	43000.00	100000.00000	100000.00
CLEARING AND GRUBBING								
SECTION TOTALS			\$	3,712,039.73	\$	4,126,867.48	\$	3,822,801.62
CONTRACT TOTALS			\$	44,699,288.81	\$	46,054,715.79	\$	46,462,808.00
DBE GOALS			8	%	8	%	8	%

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -34

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 ROADWAY DE ONLY								
0020 202000	EXCAVATION AND EMBANKMENT	1049186.000 CY	7.65000	8026272.90	6.98000	7323318.28	6.00000	6295116.00
0030 202515	COMPACTING INSITU MATERIAL	720.000 SY	1.00000	720.00	10.00000	7200.00	15.00000	10800.00
0040 202572	BORROW AREA EROSION & SEDIMENT CONTROL & DEWATERING	LUMP	500000.00000	500000.00	1000000.00000	1000000.00	500000.00000	500000.00
0050 203000	CHANNEL EXCAVATION	110.000 CY	17.75000	1952.50	26.03000	2863.30	100.00000	11000.00
0060 207000	EXCAVATION AND BACKFILL FOR STRUCTURES	22.000 CY	48.45000	1065.90	36.29000	798.38	100.00000	2200.00
0070 208000	EXCAVATION AND BACKFILLING FOR PIPE TRENCHES	10228.000 CY	1.00000	10228.00	8.55000	87449.40	6.00000	61368.00
0080 208001	FLOWABLE FILL	17.000 CY	162.00000	2754.00	250.00000	4250.00	400.00000	6800.00
0090 209002	BORROW, TYPE B	80814.000 CY	10.40000	840465.60	22.95000	1854681.30	6.00000	484884.00
0100 211000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP	25000.00000	25000.00	136000.00000	136000.00	362581.83000	362581.83
0110 211521	ABANDONMENT OF WELLS	6.000 EACH	1000.00000	6000.00	1294.00000	7764.00	2200.00000	13200.00
0120 212000	UNDERCUT EXCAVATION	1892.000 CY	9.35000	17690.20	10.47000	19809.24	9.00000	17028.00
0130 302007	GRADED AGGREGATE BASE COURSE, TYPE B	22803.000 CY	40.75000	929222.25	49.11000	1119855.33	65.00000	1482195.00
0140 302011	DELAWARE NO. 3 STONE	1380.000 TON	38.95000	53751.00	48.94000	67537.20	40.00000	55200.00
0150 304501	PERMEABLE TREATED BASE, 4"	129994.000 SY	9.25000	1202444.50	10.50000	1364937.00	9.65000	1254442.10
0160 304502	SOIL CEMENT BASE COURSE, 6"	126083.000 SY	8.00000	1008664.00	9.71000	1224265.93	8.15000	1027576.45
0170 304506	PORTLAND CEMENT	2741.000 TON	131.00000	359071.00	147.00000	402927.00	133.00000	364553.00
0180 401801	BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS PG 64-22 (CARBONATE STONE)	4257.000 TON	83.90000	357162.30	80.00000	340560.00	90.00000	383130.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -35

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(3) RICHARD E PIERSON CONST CO I		(4) GEORGE & LYNCH INC		(5) ALLAN MYERS MD INC	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0190 401810 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22	15969.000 TON	70.80000	1130605.20	63.50000	1014031.50	74.00000	1181706.00
0200 401819 BITUMINOUS CONCRETE, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22	19086.000 TON	70.80000	1351288.80	64.00000	1221504.00	75.00000	1431450.00
0210 401825 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22, WEDGE	3.000 TON	219.00000	657.00	500.00000	1500.00	500.00000	1500.00
0220 401827 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (NON-CARBONATE STONE)	7916.000 TON	74.00000	585784.00	68.00000	538288.00	79.00000	625364.00
0230 501006 PORTLAND CEMENT CONCRETE PAVEMENT, 12"	129978.000 SY	56.00000	7278768.00	61.95000	8052137.10	55.00000	7148790.00
0240 605755 OVERHEAD SIGN SUPPORTS AND FOUNDATIONS	LUMP	314000.00000	314000.00	331000.00000	331000.00	330000.00000	330000.00
0250 612020 REINFORCED CONCRETE PIPE, 12", CLASS IV	696.000 LF	47.90000	33338.40	51.54000	35871.84	57.00000	39672.00
0260 612022 REINFORCED CONCRETE PIPE, 18", CLASS IV	5973.000 LF	54.00000	322542.00	59.10000	353004.30	52.00000	310596.00
0270 612023 REINFORCED CONCRETE PIPE, 24", CLASS IV	2800.000 LF	56.00000	156800.00	66.70000	186760.00	68.00000	190400.00
0280 612025 REINFORCED CONCRETE PIPE, 30", CLASS IV	2426.000 LF	81.00000	196506.00	103.90000	252061.40	90.00000	218340.00
0290 612026 REINFORCED CONCRETE PIPE, 30", CLASS V	176.000 LF	92.90000	16350.40	115.00000	20240.00	110.00000	19360.00
0300 612027 REINFORCED CONCRETE PIPE, 42", CLASS IV	945.000 LF	118.00000	111510.00	126.76000	119788.20	180.00000	170100.00
0310 612028 REINFORCED CONCRETE PIPE, 48", CLASS IV	206.000 LF	136.00000	28016.00	197.08000	40598.48	210.00000	43260.00
0320 612030 REINFORCED CONCRETE PIPE, 18", CLASS V	304.000 LF	51.00000	15504.00	70.00000	21280.00	75.00000	22800.00
0330 612031 REINFORCED CONCRETE PIPE, 24", CLASS V	528.000 LF	78.10000	41236.80	81.02000	42778.56	82.00000	43296.00
0340 612034 REINFORCED CONCRETE PIPE, 36", CLASS IV	777.000 LF	106.00000	82362.00	127.57000	99121.89	140.00000	108780.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -36

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)		
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC		
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0350 612038	1065.000 LF REINFORCED CONCRETE PIPE, 60", CLASS IV		268.00000	285420.00	306.40000	326316.00	300.00000	319500.00
0360 612049	140.000 LF REINFORCED CONCRETE PIPE, 12", CLASS V		55.20000	7728.00	60.00000	8400.00	50.00000	7000.00
0370 612205	679.000 LF REINFORCED CONCRETE ELLIPTICAL PIPE, 19"X30", CLASS IV		93.20000	63282.80	124.58000	84589.82	110.00000	74690.00
0380 612216	816.000 LF REINFORCED CONCRETE ELLIPTICAL PIPE, 14"X23", CLASS IV		72.90000	59486.40	78.03000	63672.48	80.00000	65280.00
0390 612219	394.000 LF REINFORCED CONCRETE ELLIPTICAL PIPE, 24"X38", CLASS IV		120.00000	47280.00	138.50000	54569.00	150.00000	59100.00
0400 612535	858.000 LF CLEANING DRAINAGE PIPE, 15"-24" DIA		6.30000	5405.40	17.40000	14929.20	5.00000	4290.00
0410 612536	296.000 LF CLEANING DRAINAGE PIPE, GREATER THAN 24" DIA		9.35000	2767.60	26.13000	7734.48	5.00000	1480.00
0420 617001	15.000 EACH REINFORCED CONCRETE FLARED END SECTION, 12"		770.00000	11550.00	462.08000	6931.20	900.00000	13500.00
0430 617003	51.000 EACH REINFORCED CONCRETE FLARED END SECTION, 18"		960.00000	48960.00	675.54000	34452.54	1100.00000	56100.00
0440 617005	19.000 EACH REINFORCED CONCRETE FLARED END SECTION, 24"		1100.00000	20900.00	780.19000	14823.61	1200.00000	22800.00
0450 617007	12.000 EACH REINFORCED CONCRETE FLARED END SECTION, 30"		1710.00000	20520.00	1359.94000	16319.28	2400.00000	28800.00
0460 617164	4.000 EACH REINFORCED CONCRETE FLARED END SECTION, 19" X 30"		1860.00000	7440.00	1309.70000	5238.80	2500.00000	10000.00
0470 617165	4.000 EACH REINFORCED CONCRETE FLARED END SECTION, 14" X 23"		1510.00000	6040.00	1126.07000	4504.28	1500.00000	6000.00
0480 617174	2.000 EACH REINFORCED CONCRETE FLARED END SECTION, 24" X 38"		2100.00000	4200.00	1500.00000	3000.00	2700.00000	5400.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -37

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0490 617518	LUMP		235000.00000	235000.00	198000.00000	198000.00	300000.00000	300000.00
	DRAINAGE HEADWALLS, MODIFIED							
0500 701011	6204.000 LF		23.00000	142692.00	24.01000	148958.04	25.00000	155100.00
0510 701012	1877.000 LF		26.00000	48802.00	11.76000	22073.52	23.00000	43171.00
0520 701016	1408.000 LF		30.00000	42240.00	31.75000	44704.00	26.00000	36608.00
	INTEGRAL PORTLAND CEMENT CONCRETE CURB & GUTTER, TYPE 1-4							
0530 701022	3084.000 LF		22.00000	67848.00	22.77000	70222.68	18.00000	55512.00
	INTEGRAL PORTLAND CEMENT CONCRETE CURB & GUTTER, TYPE 3-8							
0540 705001	6738.000 SF		7.00000	47166.00	7.74000	52152.12	8.00000	53904.00
	P.C.C. SIDEWALK, 4"							
0550 705002	29291.000 SF		8.05000	235792.55	8.67000	253952.97	8.00000	234328.00
	P.C.C. SIDEWALK, 6"							
0560 705007	100.000 SF		36.80000	3680.00	36.75000	3675.00	36.00000	3600.00
	SIDEWALK SURFACE DETECTABLE WARNING SYSTEM							
0570 707005	134.000 EACH		424.00000	56816.00	340.29000	45598.86	360.00000	48240.00
	UNDERDRAIN OUTLET							
0580 708050	17.000 EACH		2590.00000	44030.00	2435.08000	41396.36	2500.00000	42500.00
	DRAINAGE INLET, 34" X 18"							
0590 708051	14.000 EACH		3140.00000	43960.00	3076.29000	43068.06	3000.00000	42000.00
	DRAINAGE INLET, 34" X 24"							
0600 708052	14.000 EACH		3490.00000	48860.00	3303.31000	46246.34	3300.00000	46200.00
	DRAINAGE INLET, 48" X 30"							
0610 708053	12.000 EACH		3580.00000	42960.00	4238.32000	50859.84	3300.00000	39600.00
	DRAINAGE INLET, 48" X 48"							
0620 708055	3.000 EACH		4990.00000	14970.00	6437.49000	19312.47	4500.00000	13500.00
	DRAINAGE INLET, 66" X 48"							
0630 708057	4.000 EACH		6200.00000	24800.00	5637.52000	22550.08	4300.00000	17200.00
	DRAINAGE INLET, 72" X 24"							
0640 708058	3.000 EACH		5900.00000	17700.00	7527.24000	22581.72	5400.00000	16200.00
	DRAINAGE INLET, 72" X 48"							
0650 708105	4.000 EACH		4680.00000	18720.00	7352.39000	29409.56	8000.00000	32000.00
	MANHOLE (SANITARY)							
0660 708111	18.000 EACH		3260.00000	58680.00	3333.29000	59999.22	3300.00000	59400.00
	MANHOLE, 48" X 30"							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -38

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0670 708112	MANHOLE, 48" X 48"	1.000 EACH	3120.00000	3120.00	2650.00000	2650.00	3500.00000	3500.00
0680 708114	MANHOLE, 66" X 48"	3.000 EACH	5700.00000	17100.00	6718.51000	20155.53	5200.00000	15600.00
0690 708583	PERSONNEL GRATE FOR PIPE INLET	6.000 EACH	464.00000	2784.00	850.49000	5102.94	600.00000	3600.00
0700 708585	JUNCTION BOX, 48" X 30"	1.000 EACH	3490.00000	3490.00	1550.00000	1550.00	2700.00000	2700.00
0710 708658	DRAINAGE INLETS, MODIFIED	LUMP	150000.00000	150000.00	173254.97000	173254.97	200000.00000	200000.00
0720 708659	DRAINAGE MANHOLES, MODIFIED	LUMP	110000.00000	110000.00	103216.36000	103216.36	100000.00000	100000.00
0730 712005	RIPRAP, R-4	2154.000 SY	33.35000	71835.90	56.79000	122325.66	70.00000	150780.00
0740 712006	RIPRAP, R-5	373.000 SY	51.00000	19023.00	71.79000	26777.67	85.00000	31705.00
0750 712007	RIPRAP, R-6	31.000 SY	82.30000	2551.30	108.39000	3360.09	115.00000	3565.00
0760 712531	CHANNEL BED FILL	15.000 CY	130.00000	1950.00	106.30000	1594.50	100.00000	1500.00
0770 713002	GEOTEXTILES, SEPARATION	7306.000 SY	1.80000	13150.80	1.26000	9205.56	2.00000	14612.00
0780 713003	GEOTEXTILES, RIPRAP	3776.000 SY	1.05000	3964.80	2.25000	8496.00	2.00000	7552.00
0790 715001	PERFORATED PIPE UNDERDRAINS, 6"	59887.000 LF	15.00000	898305.00	12.84000	768949.08	12.00000	718644.00
0800 715500	UNDERDRAIN OUTLET PIPE, 6"	3642.000 LF	21.85000	79577.70	14.59000	53136.78	11.00000	40062.00
0810 716000	CONVERTING EXISTING DRAINAGE INLET TO JUNCTION BOX	1.000 EACH	1420.00000	1420.00	2500.00000	2500.00	4000.00000	4000.00
0820 720050	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-31	6563.000 LF	23.10000	151605.30	23.10000	151605.30	22.50000	147667.50
0830 720052	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 3-31	2275.000 LF	27.30000	62107.50	29.40000	66885.00	29.00000	65975.00
0840 720055	CURVED GUARDRAIL SECTION	282.000 LF	29.45000	8304.90	33.60000	9475.20	33.00000	9306.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -39

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0850 720585	GUARDRAIL END TREATMENT ATTENUATOR, TYPE 1-31	5.000 EACH	2730.00000	13650.00	2730.00000	13650.00	2700.00000	13500.00
0860 720586	GUARDRAIL END TREATMENT ATTENUATOR, TYPE 2-31	11.000 EACH	2410.00000	26510.00	2730.00000	30030.00	2700.00000	29700.00
0870 720588	GUARDRAIL END TREATMENT ATTENUATOR, TYPE 3-31	10.000 EACH	4990.00000	49900.00	6300.00000	63000.00	6200.00000	62000.00
0880 720611	FLEXIBLE DELINEATOR, PERMANENT	183.000 EACH	56.80000	10394.40	42.00000	7686.00	41.00000	7503.00
0890 720626	CONCRETE SINGLE FACE BARRIER, TYPE I	630.000 LF	114.00000	71820.00	315.44000	198727.20	179.00000	112770.00
0900 725001	GUARDRAIL TO BARRIER CONNECTION (EXIT TYPE 31)	5.000 EACH	580.00000	2900.00	630.00000	3150.00	615.00000	3075.00
0910 725002	GUARDRAIL TO BARRIER CONNECTION, APPROACH TYPE 1-31	7.000 EACH	2000.00000	14000.00	2415.00000	16905.00	2400.00000	16800.00
0920 726001	END ANCHORAGE 31	21.000 EACH	790.00000	16590.00	892.50000	18742.50	870.00000	18270.00
0930 727000	RIGHT-OF-WAY FENCE	27099.000 LF	10.50000	284539.50	10.50000	284539.50	10.50000	284539.50
0940 727001	RIGHT-OF-WAY FENCE GATE	3.000 EACH	720.00000	2160.00	722.75000	2168.25	705.00000	2115.00
0950 727014	CONSTRUCTION SAFETY FENCE	621.000 LF	1.60000	993.60	2.54000	1577.34	5.00000	3105.00
0960 727552	RESOURCE PROTECTION FENCE	5636.000 LF	2.05000	11553.80	1.94000	10933.84	5.00000	28180.00
0970 735501	HERBICIDE APPLICATION, NOXIOUS WEEDS	50.000 ACRE	126.00000	6300.00	2750.00000	137500.00	100.00000	5000.00
0980 737523	PLANTINGS	LUMP	110000.00000	110000.00	115710.00000	115710.00	120000.00000	120000.00
0990 743000	MAINTENANCE OF TRAFFIC	LUMP	300000.00000	300000.00	170000.00000	170000.00	200000.00000	200000.00
1000 743003	ARROWPANELS, TYPE C	189.000 EADY	25.75000	4866.75	16.07000	3037.23	16.00000	3024.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -40

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1010 743004	FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	317.000 EADY	73.90000	23426.30	69.62000	22069.54	67.00000	21239.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -41

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)	(4)		(5)		
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1020 743005	FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	91.000 EADY	72.00000	6552.00	69.00000	6279.00	103.00000	9373.00
1030 743006	PLASTIC DRUMS	290542.000 EADY	0.10000	29054.20	0.16000	46486.72	0.20000	58108.40
1040 743007	TRAFFIC OFFICERS	924.000 HOUR	75.00000	69300.00	75.00000	69300.00	75.00000	69300.00
1050 743010	FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II	534.000 EADY	85.00000	45390.00	171.29000	91468.86	20.00000	10680.00
1060 743015	FURNISH AND MAINTAIN PORTABLE PCC SAFETY BARRIER	1745.000 LF	27.15000	47376.75	25.04000	43694.80	32.00000	55840.00
1070 743016	RELOCATION PORATBLE SAFETY BARRIER	1960.000 LF	6.10000	11956.00	9.00000	17640.00	12.00000	23520.00
1080 743023	TEMPORARY BARRICADES, TYPE III	271614.000 LFDY	0.10000	27161.40	0.16000	43458.24	0.05000	13580.70
1090 743024	TEMPORARY WARNING SIGNS AND PLAQUES	65228.000 EADY	1.60000	104364.80	1.61000	105017.08	3.00000	195684.00
1100 743025	INSTALL TEMPORARY IMPACT ATTENUATOR	11.000 EACH	2140.00000	23540.00	1050.00000	11550.00	1230.00000	13530.00
1110 743029	FURNISH TEMPORARY IMPACT ATTENUATOR - NON-GATING, REDIRECTIVE, TEST LEVEL 3	9.000 EACH	1580.00000	14220.00	14700.00000	132300.00	8700.00000	78300.00
1120 743030	RELOCATE TEMPORARY IMPACT ATTENUATOR	3.000 EACH	2140.00000	6420.00	1470.00000	4410.00	1540.00000	4620.00
1130 743031	ATSSA CERTIFIED TRAFFIC CONTROL SUPERVISOR	1574.000 HOUR	90.00000	141660.00	63.40000	99791.60	114.00000	179436.00
1140 743056	FLAGGER, NEW CASTLE COUNTY, FEDERAL	5730.000 HOUR	48.00000	275040.00	48.62000	278592.60	49.00000	280770.00
1150 743065	FLAGGER, NEW CASTLE COUNTY, FEDERAL, OVERTIME	1146.000 HOUR	70.00000	80220.00	71.03000	81400.38	70.00000	80220.00
1160 744506	CONDUIT JUNCTION WELL, TYPE 7, PRECAST POLYMER CONCRETE	17.000 EACH	2100.00000	35700.00	2100.00000	35700.00	2870.00000	48790.00
1170 744519	RELOCATION OF EXISTING JUNCTION WELL	8.000 EACH	740.00000	5920.00	735.00000	5880.00	717.00000	5736.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -42

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1180 744520	CONDUIT JUNCTION WELL, TYPE 1, PRECAST CONCRETE	4.000 EACH	890.00000	3560.00	892.50000	3570.00	972.00000	3888.00
1190 744523	CONDUIT JUNCTION WELL, TYPE 4, PRECAST CONCRETE	1.000 EACH	1420.00000	1420.00	1417.50000	1417.50	1230.00000	1230.00
1200 744530	CONDUIT JUNCTION WELL, TYPE 11, PRECAST CONCRETE/ POLYMER LID-FRAME	125.000 EACH	970.00000	121250.00	971.25000	121406.25	972.00000	121500.00
1210 744531	CONDUIT JUNCTION WELL, TYPE 14, PRECAST CONCRETE/ POLYMER LID-FRAME	56.000 EACH	1390.00000	77840.00	1391.25000	77910.00	1230.00000	68880.00
1220 744541	FURNISH & INSTALL FRAME AND LID FOR JUNCTION WELL, TYPE 11	3.000 EACH	394.00000	1182.00	393.75000	1181.25	512.00000	1536.00
1230 744542	FURNISH & INSTALL FRAME AND LID FOR JUNCTION WELL, TYPE 14	1.000 EACH	770.00000	770.00	771.75000	771.75	665.00000	665.00
1240 744544	ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	6.000 EACH	368.00000	2208.00	367.50000	2205.00	486.00000	2916.00
1250 745602	FURNISH & INSTALL UP TO 4" SCHEDULE 80 HDPE CONDUIT (BORE)	651.000 LF	31.55000	20539.05	31.50000	20506.50	22.50000	14647.50
1260 745604	FURNISH & INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	45263.000 LF	7.25000	328156.75	7.30000	330419.90	7.15000	323630.45
1270 745606	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (TRENCH)	2087.000 LF	24.95000	52070.65	24.94000	52049.78	17.90000	37357.30
1280 745609	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (ON STRUCTURE)	20.000 LF	33.25000	665.00	33.23000	664.60	28.65000	573.00
1290 746509	RELOCATING LIGHT POLE	13.000 EACH	473.00000	6149.00	472.50000	6142.50	1840.00000	23920.00
1300 746511	CABLES, 1/#4 AWG	3986.000 LF	0.70000	2790.20	0.68000	2710.48	0.75000	2989.50
1310 746512	CABLES, 1/#6 AWG	33809.000 LF	0.50000	16904.50	0.48000	16228.32	0.60000	20285.40

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -43

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1320 746513	CABLES, 1/#8 AWG	318.000 LF	0.40000	127.20	0.42000	133.56	0.50000	159.00
1330 746515	INSULATED GROUND CABLES, 1/#6	9603.000 LF	0.50000	4801.50	0.48000	4609.44	0.60000	5761.80
1340 746517	ALUMINUM LIGHTING STANDARD WITH SINGLE DAVIT ARM, 30' POLE	19.000 EACH	2740.00000	52060.00	2740.50000	52069.50	2760.00000	52440.00
1350 746519	ALUMINUM LIGHTING STANDARD WITH SINGLE DAVIT ARM, 40' POLE	16.000 EACH	2940.00000	47040.00	2934.75000	46956.00	3070.00000	49120.00
1360 746527	CABLES, 1/#2 AWG	12711.000 LF	1.15000	14617.65	1.16000	14744.76	1.15000	14617.65
1370 746541	INSTALLATION OF ELECTRICAL WIRE OR CABLE IN EMPTY CONDUITS	93945.000 LF	1.70000	159706.50	1.72000	161585.40	0.90000	84550.50
1380 746564	INSULATED GROUND CABLES, 1/#4	625.000 LF	0.70000	437.50	0.68000	425.00	0.75000	468.75
1390 746577	INSULATED GROUND CABLE, 1/#8	165.000 LF	0.40000	66.00	0.42000	69.30	0.50000	82.50
1400 746586	RELOCATE SIGN	140.000 SF	21.00000	2940.00	21.00000	2940.00	15.35000	2149.00
1410 746590	FURNISH & INSTALL GROUND ROD	8.000 EACH	116.00000	928.00	115.50000	924.00	128.00000	1024.00
1420 746594	LUMINAIRE (HPS), 250 WATT	45.000 EACH	357.00000	16065.00	357.00000	16065.00	717.00000	32265.00
1430 746595	ALUMINUM LIGHTING STANDARD, 40' POLE	48.000 EACH	2710.00000	130080.00	2703.75000	129780.00	3070.00000	147360.00
1440 746598	INSULATED GROUND CABLE, 1/#2	3234.000 LF	1.15000	3719.10	1.16000	3751.44	1.15000	3719.10
1450 746615	PVC SCHEDULE 40 DUCT, 6"	80.000 LF	4.25000	340.00	21.00000	1680.00	2.05000	164.00
1460 746622	CABLES, 1/#4/0 AWG	6868.000 LF	3.35000	23007.80	3.36000	23076.48	3.50000	24038.00
1470 746653	ELECTRICAL TESTING	LUMP	5300.00000	5300.00	5250.00000	5250.00	30700.00000	30700.00
1480 746669	LUMINAIRE (HPS), 150 WATTS	19.000 EACH	357.00000	6783.00	357.00000	6783.00	691.00000	13129.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -44

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)	
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT							
ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1490 746717	3.000 EACH	1730.00000	5190.00	1732.50000	5197.50	4610.00000	13830.00
ELECTRIC SERVICE ON RACK WITH SERVICE RISER							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -45

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1500 746817	CABLES, 1/#2/0 AWG	9953.000 LF	2.35000	23389.55	2.36000	23489.08	2.25000	22394.25
1510 746847	POLE BASE, TYPE 3	4.000 EACH	2420.00000	9680.00	2415.00000	9660.00	2760.00000	11040.00
1520 746850	POLE BASE, TYPE 4A	4.000 EACH	700.00000	2800.00	698.25000	2793.00	614.00000	2456.00
1530 746852	POLE BASE, TYPE 6	82.000 EACH	1000.00000	82000.00	997.50000	81795.00	921.00000	75522.00
1540 746861	INSULATED GROUND CABLES, 1/350 KCMIL	6621.000 LF	5.10000	33767.10	5.15000	34098.15	6.40000	42374.40
1550 746872	LIGHTING CONTROL AND DISTRIBUTION ENCLOSURE	2.000 EACH	11500.00000	23000.00	11445.00000	22890.00	10700.00000	21400.00
1560 746903	INSULATED GROUND CABLES, 1/#2/0	4033.000 LF	2.35000	9477.55	2.36000	9517.88	2.25000	9074.25
1570 746904	INSULATED GROUND CABLES, 1/#4/0	1871.000 LF	3.35000	6267.85	3.36000	6286.56	3.50000	6548.50
1580 746924	FURNISH & INSTALL LOOP WIRE 1-CONDUCTOR #14 AWG ENCASED IN 1/4" FLEXIBLE TUBING IN A LOOP SAWCUT	3504.000 LF	14.50000	50808.00	14.44000	50597.76	14.35000	50282.40
1590 746951	RELOCATING POLE & MAST ARM	1.000 EACH	630.00000	630.00	630.00000	630.00	2560.00000	2560.00
1600 747515	CABINET BASE, TYPE M	4.000 EACH	1630.00000	6520.00	1627.50000	6510.00	1330.00000	5320.00
1610 747516	CABINET BASE, TYPE P	3.000 EACH	1630.00000	4890.00	1627.50000	4882.50	1330.00000	3990.00
1620 748015	PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	4301.000 SF	4.30000	18494.30	4.31000	18537.31	4.20000	18064.20
1630 748019	TEMPORARY MARKINGS, PAINT, 4"	9351.000 LF	0.30000	2805.30	0.29000	2711.79	0.30000	2805.30
1640 748026	TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	276.000 SF	3.20000	883.20	3.15000	869.40	3.05000	841.80
1650 748032	TEMPORARY MARKINGS, PAINT, 5"	258.000 LF	0.30000	77.40	0.32000	82.56	0.30000	77.40
1660 748033	PERMANENT PAVEMENT STRIPING, ALKYD-THERMOPLASTIC, 5"	62.000 LF	1.10000	68.20	1.05000	65.10	1.00000	62.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -46

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1670 748502	RAISED/RECESSED PAVEMENT MARKER	533.000 EACH	51.90000	27662.70	51.82000	27620.06	51.00000	27183.00
1680 748525	TEMPORARY MARKINGS, TAPE, 4"	37313.000 LF	1.35000	50372.55	1.37000	51118.81	1.35000	50372.55
1690 748527	TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS	520.000 SF	5.20000	2704.00	5.25000	2730.00	5.10000	2652.00
1700 748530	REMOVAL OF PAVEMENT STRIPING	10624.000 SF	2.40000	25497.60	2.42000	25710.08	2.35000	24966.40
1710 748548	PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	146717.000 LF	0.50000	73358.50	0.49000	71891.33	0.50000	73358.50
1720 748549	PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 10"	3812.000 LF	1.00000	3812.00	0.99000	3773.88	0.95000	3621.40
1730 748553	PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, BIKE SYMBOL	49.000 EACH	389.00000	19061.00	388.50000	19036.50	379.00000	18571.00
1740 748557	PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 3"	23558.000 LF	0.60000	14134.80	0.61000	14370.38	0.60000	14134.80
1750 748566	RETROREFLECTIVE PREFORMED PATTERNED MARKINGS, 8"	5475.000 LF	7.90000	43252.50	7.88000	43143.00	7.70000	42157.50
1760 748567	RETROREFLECTIVE PREFORMED PATTERNED MARKINGS, 13"	395.000 LF	12.60000	4977.00	12.60000	4977.00	12.30000	4858.50
1770 749500	SIGN PANEL	2553.000 SF	22.05000	56293.65	22.05000	56293.65	34.80000	88844.40
1840 749532	SUPPLY OF FLAT SHEET ALUMINUM SIGN PANEL, TYPE IX RETROREFLECTIVE SHEETING	20.000 SF	26.25000	525.00	26.25000	525.00	27.65000	553.00
1880 749687	INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	196.000 EACH	99.80000	19560.80	99.75000	19551.00	87.00000	17052.00
1890 749688	INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" DEPTH	10.000 EACH	105.00000	1050.00	105.00000	1050.00	128.00000	1280.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -47

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)	
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT							
ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1900 749689	4.000 EACH	105.00000	420.00	105.00000	420.00	154.00000	616.00
INSTALLATION OF 4" DIAMETER HOLE, GREATER THAN 6" DEPTH							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -48

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1910 749690	1069.000 SF		15.75000	16836.75	15.75000	16836.75	19.45000	20792.05
	INSTALLATION OR REMOVAL OF TRAFFIC SIGNS ON MULTIPLE SIGN POSTS							
1920 753503	262.000 LF		158.00000	41396.00	70.66000	18512.92	200.00000	52400.00
	INSTALLING SANITARY SEWER, PVC, 12"							
1930 758000	19253.000 SY		12.30000	236811.90	7.01000	134963.53	5.50000	105891.50
	REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.							
1940 759506	30.000 EAMO		13200.00000	396000.00	10231.80000	306954.00	17100.00000	513000.00
	FIELD OFFICE, TYPE II.22 SPECIAL COMPLE							
1950 760012	22362.000 LF		0.15000	3354.30	0.20000	4472.40	0.15000	3354.30
	RUMBLE STRIPS, BIKE-FRIENDLY, HOT-MIX							
1960 760017	59567.000 LF		0.45000	26805.15	0.38000	22635.46	0.50000	29783.50
	RUMBLE STRIPS, CONCRETE							
1970 760507	6786.000 SYIN		1.00000	6786.00	3.57000	24226.02	4.00000	27144.00
	PROFILE MILLING, BITUMINOUS CONCRETE							
1980 762001	4764.000 LF		1.05000	5002.20	3.15000	15006.60	2.00000	9528.00
	SAW CUTTING, BITUMINOUS CONCRETE							
1990 762002	697.000 LF		3.10000	2160.70	8.40000	5854.80	5.00000	3485.00
	SAW CUTTING, CONCRETE, FULL DEPTH							
2000 763000	LUMP		2400000.00000	2400000.00	2575000.00000	2575000.00	2400000.00000	2400000.00
	INITIAL EXPENSE							
2010 763501	LUMP		500000.00000	500000.00	369000.00000	369000.00	1000000.00000	1000000.00
	CONSTRUCTION ENGINEERING							
2020 763503	2000.000 HOUR		0.80000	1600.00	0.80000	1600.00	0.80000	1600.00
	TRAINEE							
2030 763508	LUMP		16000.00000	16000.00	31500.00000	31500.00	90000.00000	90000.00
	PROJECT CONTROL SYSTEM DEVELOPMENT PLAN							
2040 763509	30.000 EAMO		420.00000	12600.00	1575.00000	47250.00	3200.00000	96000.00
	CPM SCHEDULE UPDATES AND/OR REVISED UPDATES							
2050 763597	100.000 HOUR		122.00000	12200.00	136.50000	13650.00	170.00000	17000.00
	UTILITY CONSTRUCTION ENGINEERING							
2060 763619	LUMP		330000.00000	330000.00	350000.00000	350000.00	427000.00000	427000.00
	WEIGH IN MOTION SYSTEM (WIM)							
2070 763689	LUMP		140000.00000	140000.00	144000.00000	144000.00	149000.00000	149000.00
	STRUCTURAL WORK, GANTRY							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -49

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2080 900500	ENVIRONMENTAL PERFORMANCE INCENTIVE (DISINCENTIVE)	LUMP	488000.00000	488000.00	488000.00000	488000.00	488000.00000	488000.00
2090 905001	SILT FENCE	12571.000 LF	1.35000	16970.85	1.31000	16468.01	2.50000	31427.50
2100 905002	REINFORCED SILT FENCE	45734.000 LF	3.80000	173789.20	3.62000	165557.08	4.70000	214949.80
2110 905003	SEDIMENT TRAP	1303.000 CY	20.85000	27167.55	10.50000	13681.50	15.00000	19545.00
2120 905004	INLET SEDIMENT CONTROL, DRAINAGE INLET	16.000 EACH	266.00000	4256.00	246.86000	3949.76	240.00000	3840.00
2130 905005	INLET SEDIMENT CONTROL, CURB INLET	11.000 EACH	157.00000	1727.00	321.83000	3540.13	240.00000	2640.00
2140 906001	PORTABLE SEDIMENT TANK	1.000 EACH	5400.00000	5400.00	1223.72000	1223.72	2000.00000	2000.00
2150 906002	DEWATERING BAG	9.000 EACH	182.00000	1638.00	346.21000	3115.89	1000.00000	9000.00
2160 906003	SUMP PIT	1.000 EACH	1350.00000	1350.00	1476.19000	1476.19	4000.00000	4000.00
2170 906004	SKIMMER DEWATERING DEVICE	11.000 EACH	1050.00000	11550.00	2029.25000	22321.75	700.00000	7700.00
2180 907011	STONE CHECK DAM	47.000 TON	65.60000	3083.20	75.65000	3555.55	100.00000	4700.00
2190 908010	TOPSOILING, 6" DEPTH	500754.000 SY	1.65000	826244.10	1.29000	645972.66	2.00000	1001508.00
2200 908014	PERMANENT GRASS SEEDING, DRY GROUND	519169.000 SY	0.60000	311501.40	0.62000	321884.78	0.65000	337459.85
2210 908015	PERMANENT GRASS SEEDING, WET GROUND	450305.000 SY	0.55000	247667.75	0.53000	238661.65	0.55000	247667.75
2220 908017	TEMPORARY GRASS SEEDING	468154.000 SY	0.40000	187261.60	0.39000	182580.06	0.40000	187261.60
2230 908019	STREAMBANK SEED MIX, SEEDING	50.000 SY	10.95000	547.50	10.50000	525.00	100.00000	5000.00
2240 908020	EROSION CONTROL BLANKET MULCH	123047.000 SY	2.15000	264551.05	2.05000	252246.35	2.10000	258398.70
2250 908021	TURF REINFORCEMENT MATTING, TYPE 1	1824.000 SY	7.90000	14409.60	7.61000	13880.64	8.00000	14592.00
2260 908023	STABILIZED CONSTRUCTION ENTRANCE	1259.000 TON	28.95000	36448.05	39.76000	50057.84	50.00000	62950.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -50

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2270 908503	WETLAND MITIGATION GRASS SEEDING	25854.000 SY	0.60000	15512.40	0.58000	14995.32	0.60000	15512.40
2300 910004	CLAY BORROW, CUT-OFF TRENCH	2981.000 CY	3.35000	9986.35	25.00000	74525.00	43.00000	128183.00
2310 910007	OUTLET STRUCTURE	LUMP	500000.00000	500000.00	618000.00000	618000.00	800000.00000	800000.00
2320 910009	INFILTRATION TRENCH	200.000 LF	114.00000	22800.00	63.00000	12600.00	94.00000	18800.00
4040 605501	GROUND MOUNT BREAKAWAY TYPE SIGN SUPPORTS AND FOUNDATION	LUMP	105000.00000	105000.00	113400.00000	113400.00	188000.00000	188000.00
4060 201000	CLEARING AND GRUBBING	LUMP	1400000.00000	1400000.00	1530000.00000	1530000.00	3500000.00000	3500000.00
4080 907507	EARTH DIKE, TYPE A-2	1880.000 LF	14.50000	27260.00	16.00000	30080.00	6.00000	11280.00
4090 909005	STREAM DIVERSION	LUMP	35000.00000	35000.00	64310.00000	64310.00	200000.00000	200000.00
SECTION TOTALS			\$	40,880,828.75	\$	43,515,981.83	\$	44,164,592.43
SECTION 0002 BRIDGE 1-486 STANDARD ITEMS								
2330 202505	SETTLEMENT PLATFORM	4.000 EACH	1930.00000	7720.00	2500.00000	10000.00	1180.00000	4720.00
2340 207000	EXCAVATION AND BACKFILL FOR STRUCTURES	216.000 CY	38.00000	8208.00	21.10000	4557.60	38.95000	8413.20
2350 602006	PORTLAND CEMENT CONCRETE MASONRY, PIER FOOTING, CLASS B	94.000 CY	385.00000	36190.00	362.00000	34028.00	349.00000	32806.00
2360 602007	PORTLAND CEMENT CONCRETE MASONRY, PIER ABOVE FOOTING, CLASS A	70.000 CY	1200.00000	84000.00	1265.93000	88615.10	1040.00000	72800.00
2370 602013	PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D	195.000 CY	1180.00000	230100.00	1313.02000	256038.90	1100.00000	214500.00
2380 602014	PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D	110.000 CY	650.00000	71500.00	571.97000	62916.70	470.00000	51700.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -51

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2390 602015	PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A	70.000 CY	1180.00000	82600.00	994.40000	69608.00	1120.00000	78400.00

DATE : 01/21/16

PAGE : 001 -52

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)			(4)			(5)		
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC				ALLAN MYERS MD INC		
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT			
2400 602017	50.000 CY	1610.00000	80500.00	1549.22000	77461.00	1430.00000	71500.00				
PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A											
2410 602772	LUMP	600000.00000	600000.00	370000.00000	370000.00	289000.00000	289000.00				
MECHANICALLY STABILIZED EARTH WALLS											
2420 604000	135000.000 LB	1.20000	162000.00	1.12000	151200.00	1.05000	141750.00				
BAR REINFORCEMENT, EPOXY COATED											
2430 608000	20.000 TON	46.65000	933.00	87.00000	1740.00	35.55000	711.00				
COARSE AGGREGATE FOR FOUNDATION STABILIZATION AND SUBFOUNDATION BACKFILL											
2440 623003	LUMP	350000.00000	350000.00	292000.00000	292000.00	291000.00000	291000.00				
PRESTRESSED REINFORCED CONCRETE MEMBERS BULB T BEAM											
2450 727507	290.000 LF	90.80000	26332.00	102.92000	29846.80	124.00000	35960.00				
BRIDGE SAFETY FENCE											
SECTION TOTALS			\$ 1,740,083.00	\$ 1,448,012.10	\$ 1,293,260.20						
SECTION 0003 BRIDGE 1-486 PILE ALTERNATE 1											
2460 618062	854.000 LF	38.65000	33007.10	96.42000	82342.68	35.60000	30402.40				
STEEL H PILES, HP 14 X 73											
2470 618065	142.000 LF	38.00000	5396.00	116.31000	16516.02	35.10000	4984.20				
STEEL H TEST PILES, HP 14 X 73											
2480 619042	854.000 LF	40.55000	34629.70	34.00000	29036.00	43.00000	36722.00				
INSTALL STEEL H PILES, HP 14 X 73											
2490 619045	142.000 LF	142.00000	20164.00	41.71000	5922.82	142.00000	20164.00				
INSTALL STEEL H TEST PILES, HP 14 X 73											
2500 619501	1.000 EACH	500.00000	500.00	500.00000	500.00	500.00000	500.00				
PRODUCTION PILE RESTRIKE											
2510 619502	1.000 EADY	1000.00000	1000.00	1000.00000	1000.00	1000.00000	1000.00				
TEST PILE RESTRIKE											
2520 619519	4.000 EACH	690.00000	2760.00	3150.00000	12600.00	1230.00000	4920.00				
DYNAMIC PILE TESTING BY CONTRACTOR											
2530 619539	4.000 EACH	690.00000	2760.00	315.00000	1260.00	358.00000	1432.00				
SIGNAL MATCHING ANALYSIS BY CONTRACTOR											
SECTION TOTALS			\$ 100,216.80	\$ 149,177.52	\$ 100,124.60						
SECTION 0004 BRIDGE 1-486 PILE ALTERNATE 2											

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -53

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2540 618552	924.000 LF		0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH PIPE PILE, SCHEDULE 40, OPEN								
END, 14"								
2550 618557	152.000 LF		0.00000	0.00	0.00000	0.00	0.00000	0.00
FURNISH TEST PIPE PILE, SCHEDULE 40,								
OPEN END, 14"								
2560 619501	1.000 EACH		0.00000	0.00	0.00000	0.00	0.00000	0.00
PRODUCTION PILE RESTRIKE								
2570 619502	1.000 EADY		0.00000	0.00	0.00000	0.00	0.00000	0.00
TEST PILE RESTRIKE								
2580 619519	4.000 EACH		0.00000	0.00	0.00000	0.00	0.00000	0.00
DYNAMIC PILE TESTING BY CONTRACTOR								
2590 619539	4.000 EACH		0.00000	0.00	0.00000	0.00	0.00000	0.00
SIGNAL MATCHING ANALYSIS BY CONTRACTOR								
2600 619540	924.000 LF		0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL PIPE PILE, SCHEDULE 40, OPEN								
END, 14"								
2610 619558	152.000 LF		0.00000	0.00	0.00000	0.00	0.00000	0.00
INSTALL TEST PIPE PILE, SCHEDULE 40,								
OPEN END, 14"								
SECTION TOTALS			\$	0.00	\$	0.00	\$	0.00
SECTION 0005 BRIDGE 1-482 STANDARD ITEMS								
2620 202505	4.000 EACH		1930.00000	7720.00	2305.91000	9223.64	1180.00000	4720.00
SETTLEMENT PLATFORM								
2630 207000	313.000 CY		38.00000	11894.00	18.68000	5846.84	40.00000	12520.00
EXCAVATION AND BACKFILL FOR STRUCTURES								
2640 602006	178.000 CY		360.00000	64080.00	329.25000	58606.50	341.00000	60698.00
PORTLAND CEMENT CONCRETE MASONRY, PIER								
FOOTING, CLASS B								
2650 602007	111.000 CY		1120.00000	124320.00	1158.79000	128625.69	1010.00000	112110.00
PORTLAND CEMENT CONCRETE MASONRY, PIER								
ABOVE FOOTING, CLASS A								
2660 602013	443.000 CY		1000.00000	443000.00	992.80000	439810.40	893.00000	395599.00
PORTLAND CEMENT CONCRETE MASONRY,								
SUPERSTRUCTURE, CLASS D								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -54

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2670 602014	PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D	237.000 CY	520.00000	123240.00	538.54000	127633.98	419.00000	99303.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -55

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2680 602015	120.000 CY PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A		990.00000	118800.00	780.53000	93663.60	1100.00000	132000.00
2690 602017	51.000 CY PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A		1580.00000	80580.00	1545.49000	78819.99	1570.00000	80070.00
2700 602772	LUMP MECHANICALLY STABILIZED EARTH WALLS		750000.00000	750000.00	494000.00000	494000.00	600000.00000	600000.00
2710 604000	258953.000 LB BAR REINFORCEMENT, EPOXY COATED		1.15000	297795.95	1.12000	290027.36	1.05000	271900.65
2720 608000	18.000 TON COARSE AGGREGATE FOR FOUNDATION STABILIZATION AND SUBFOUNDATION BACKFILL		46.65000	839.70	89.84000	1617.12	35.55000	639.90
2730 623003	LUMP PRESTRESSED REINFORCED CONCRETE MEMBERS BULB T BEAM		500000.00000	500000.00	391000.00000	391000.00	444000.00000	444000.00
2740 727507	354.000 LF BRIDGE SAFETY FENCE		88.00000	31152.00	99.62000	35265.48	101.00000	35754.00
	SECTION TOTALS		\$	2,553,421.65	\$	2,154,140.60	\$	2,249,314.55
SECTION 0006 BRIDGE 1-482 PILE ALTERNATE 1								
2750 618062	1836.000 LF STEEL H PILES, HP 14 X 73		37.15000	68207.40	51.55000	94645.80	35.60000	65361.60
2760 618065	135.000 LF STEEL H TEST PILES, HP 14 X 73		39.55000	5339.25	64.70000	8734.50	32.35000	4367.25
2770 619042	1836.000 LF INSTALL STEEL H PILES, HP 14 X 73		33.00000	60588.00	15.82000	29045.52	48.00000	88128.00
2780 619045	135.000 LF INSTALL STEEL H TEST PILES, HP 14 X 73		86.40000	11664.00	43.87000	5922.45	150.00000	20250.00
2790 619501	1.000 EACH PRODUCTION PILE RESTRIKE		500.00000	500.00	500.00000	500.00	500.00000	500.00
2800 619502	1.000 EADY TEST PILE RESTRIKE		1000.00000	1000.00	1000.00000	1000.00	1000.00000	1000.00
2810 619519	4.000 EACH DYNAMIC PILE TESTING BY CONTRACTOR		690.00000	2760.00	2100.00000	8400.00	1230.00000	4920.00
2820 619539	4.000 EACH SIGNAL MATCHING ANALYSIS BY CONTRACTOR		690.00000	2760.00	315.00000	1260.00	358.00000	1432.00
	SECTION TOTALS		\$	152,818.65	\$	149,508.27	\$	185,958.85

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -56

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0007 BRIDGE 1-482 PILE ALTERNATE 2								
2830 618552	FURNISH PIPE PILE, SCHEDULE 40, OPEN END, 14"	2156.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2840 618557	FURNISH TEST PIPE PILE, SCHEDULE 40, OPEN END, 14"	155.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2850 619501	PRODUCTION PILE RESTRIKE	1.000 EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
2860 619502	TEST PILE RESTRIKE	1.000 EADY	0.00000	0.00	0.00000	0.00	0.00000	0.00
2870 619519	DYNAMIC PILE TESTING BY CONTRACTOR	4.000 EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
2880 619539	SIGNAL MATCHING ANALYSIS BY CONTRACTOR	4.000 EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
2890 619540	INSTALL PIPE PILE, SCHEDULE 40, OPEN END, 14"	2156.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2900 619558	INSTALL TEST PIPE PILE, SCHEDULE 40, OPEN END, 14"	155.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
SECTION TOTALS			\$	0.00	\$	0.00	\$	0.00
SECTION 0008 BRIDGE 1-482 PILE ALTERNATE 3								
2910 618050	FURNISH STEEL SHELL PILES, 14"	1612.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2920 618051	FURNISH TEST STEEL SHELL PILES, 14"	121.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2930 619055	INSTALL STEEL SHELL PILES, 14"	1612.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2940 619056	INSTALL TEST STEEL SHELL PILES, 14"	121.000 LF	0.00000	0.00	0.00000	0.00	0.00000	0.00
2950 619501	PRODUCTION PILE RESTRIKE	1.000 EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
2960 619502	TEST PILE RESTRIKE	1.000 EADY	0.00000	0.00	0.00000	0.00	0.00000	0.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -57

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
2970 619519	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
DYNAMIC PILE TESTING BY CONTRACTOR								
2980 619539	4.000	EACH	0.00000	0.00	0.00000	0.00	0.00000	0.00
SIGNAL MATCHING ANALYSIS BY CONTRACTOR								
SECTION TOTALS			\$	0.00	\$	0.00	\$	0.00
SECTION 0009 MARYLAND QUANTITIES								
2990 202000	56440.000	CY	6.20000	349928.00	1.00000	56440.00	2.00000	112880.00
EXCAVATION AND EMBANKMENT								
3000 202569	2602.000	SY	29.00000	75458.00	45.00000	117090.00	35.00000	91070.00
POND ACCESS ROAD, MARYLAND								
3010 208000	333.000	CY	0.05000	16.65	5.00000	1665.00	6.00000	1998.00
EXCAVATION AND BACKFILLING FOR PIPE TRENCHES								
3020 208001	6.000	CY	172.00000	1032.00	500.00000	3000.00	423.00000	2538.00
FLOWABLE FILL								
3030 209002	2837.000	CY	10.40000	29504.80	23.00000	65251.00	6.00000	17022.00
BORROW, TYPE B								
3040 211002	63.000	LF	2.95000	185.85	10.00000	630.00	10.00000	630.00
REMOVAL OF STRUCTURES AND OBSTRUCTIONS (GUARDRAIL)								
3050 255502	3.000	TON	339.00000	1017.00	1000.00000	3000.00	2000.00000	6000.00
GABION OUTLET STRUCTURE, MARYLAND								
3060 272511		LUMP	150000.00000	150000.00	201400.00000	201400.00	350000.00000	350000.00
POND OUTLET STRUCTURE, CONCRETE, MARYLAND								
3070 302007	966.000	CY	52.10000	50328.60	51.00000	49266.00	67.00000	64722.00
GRADED AGGREGATE BASE COURSE, TYPE B								
3080 302012	2923.000	TON	49.15000	143665.45	31.75000	92805.25	53.00000	154919.00
DELAWARE NO. 57 STONE								
3090 304501	14264.000	SY	9.55000	136221.20	10.50000	149772.00	9.60000	136934.40
PERMEABLE TREATED BASE, 4"								
3100 304502	13852.000	SY	12.15000	168301.80	9.71000	134502.92	8.30000	114971.60
SOIL CEMENT BASE COURSE, 6"								
3110 304506	247.000	TON	131.00000	32357.00	147.00000	36309.00	133.00000	32851.00
PORTLAND CEMENT								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -58

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)	
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT							
ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3120 401801	547.000 TON	87.80000	48026.60	74.20000	40587.40	105.00000	57435.00
BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS PG 64-22 (CARBONATE STONE)							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -59

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(3) RICHARD E PIERSON CONST CO I		(4) GEORGE & LYNCH INC		(5) ALLAN MYERS MD INC	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3130 401810 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22	63.000 TON	111.00000	6993.00	150.00000	9450.00	150.00000	9450.00
3140 401819 BITUMINOUS CONCRETE, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22	2232.000 TON	73.40000	163828.80	72.90000	162712.80	70.00000	156240.00
3150 401825 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 64-22, WEDGE	33.000 TON	146.00000	4818.00	150.00000	4950.00	200.00000	6600.00
3160 401827 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22 (NON-CARBONATE STONE)	2772.000 TON	76.70000	212612.40	71.00000	196812.00	80.00000	221760.00
3170 501006 PORTLAND CEMENT CONCRETE PAVEMENT, 12"	14264.000 SY	57.30000	817327.20	61.95000	883654.80	54.00000	770256.00
3180 612022 REINFORCED CONCRETE PIPE, 18", CLASS IV	70.000 LF	53.60000	3752.00	50.00000	3500.00	91.00000	6370.00
3190 612023 REINFORCED CONCRETE PIPE, 24", CLASS IV	362.000 LF	54.40000	19692.80	84.50000	30589.00	94.00000	34028.00
3200 612205 REINFORCED CONCRETE ELLIPTICAL PIPE, 19"X30", CLASS IV	88.000 LF	97.50000	8580.00	141.00000	12408.00	119.00000	10472.00
3210 612210 REINFORCED CONCRETE ELLIPTICAL PIPE, 22"X34", CLASS IV	66.000 LF	108.00000	7128.00	157.00000	10362.00	154.00000	10164.00
3220 612505 PVC PIPE, 12"	291.000 LF	45.85000	13342.35	17.50000	5092.50	40.00000	11640.00
3230 612526 CORRUGATED POLYETHYLENE PIPE, TYPE S, 36"	100.000 LF	91.10000	9110.00	40.00000	4000.00	105.00000	10500.00
3240 612535 CLEANING DRAINAGE PIPE, 15"-24" DIA	70.000 LF	6.25000	437.50	5.00000	350.00	5.00000	350.00
3250 612536 CLEANING DRAINAGE PIPE, GREATER THAN 24" DIA	255.000 LF	9.35000	2384.25	7.00000	1785.00	5.00000	1275.00
3260 617519 CONCRETE END SECTION, 24", MARYLAND	4.000 EACH	1060.00000	4240.00	750.00000	3000.00	1180.00000	4720.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -60

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3270 617520	CONCRETE END SECTION, 19"X 30", MARYLAN	1.000 EACH	1860.00000	1860.00	1275.00000	1275.00	2500.00000	2500.00
3280 617521	CONCRETE END SECTION, 22"X34", MARYLAND	1.000 EACH	1600.00000	1600.00	1375.00000	1375.00	2580.00000	2580.00
3290 708660	DRAINAGE INLET, TYPE K, SINGLE, MARYLAN	6.000 EACH	3540.00000	21240.00	2500.00000	15000.00	5290.00000	31740.00
3300 712005	RIPRAP, R-4	783.000 SY	33.35000	26113.05	61.00000	47763.00	50.00000	39150.00
3310 712552	RIPRAP SLOPE PROTECTION, MARYLAND	476.000 SY	47.90000	22800.40	61.00000	29036.00	98.00000	46648.00
3320 713003	GEOTEXTILES, RIPRAP	3713.000 SY	1.05000	3898.65	1.10000	4084.30	2.00000	7426.00
3330 715001	PERFORATED PIPE UNDERDRAINS, 6"	3238.000 LF	16.45000	53265.10	11.00000	35618.00	13.00000	42094.00
3340 715004	PERFORATED PIPE UNDERDRAINS, 12"	520.000 LF	25.00000	13000.00	28.00000	14560.00	85.00000	44200.00
3350 715500	UNDERDRAIN OUTLET PIPE, 6"	273.000 LF	22.90000	6251.70	12.50000	3412.50	11.00000	3003.00
3360 720043	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-27	653.000 LF	24.15000	15769.95	23.00000	15019.00	22.50000	14692.50
3370 720044	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 2-27	63.000 LF	29.45000	1855.35	31.50000	1984.50	30.70000	1934.10
3380 720050	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-31	300.000 LF	24.50000	7350.00	23.00000	6900.00	22.50000	6750.00
3390 720051	GALVANIZED STEEL BEAM GUARDRAIL, TYPE 2-31	50.000 LF	31.55000	1577.50	33.00000	1650.00	30.70000	1535.00
3400 720585	GUARDRAIL END TREATMENT ATTENUATOR, TYPE 1-31	1.000 EACH	2730.00000	2730.00	2750.00000	2750.00	2660.00000	2660.00
3410 720611	FLEXIBLE DELINEATOR, PERMANENT	17.000 EACH	56.80000	965.60	43.00000	731.00	41.00000	697.00
3420 727552	RESOURCE PROTECTION FENCE	1785.000 LF	2.05000	3659.25	2.00000	3570.00	3.00000	5355.00
3430 727553	DIVERSION FENCE, MARYLAND	335.000 LF	2.05000	686.75	10.00000	3350.00	10.25000	3433.75

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -61

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)			(4)			(5)		
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC				ALLAN MYERS MD INC		
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT			
3440 734555	TEMPORARY VEGETATVIE STABILIZATION, MARYLAND	91022.000 SY	0.50000	45511.00	0.50000	45511.00	0.45000	40959.90			
3450 734556	PERMANENT VEGETATIVE STABILIZATION, MARYLAND	82149.000 SY	0.75000	61611.75	0.75000	61611.75	0.65000	53396.85			
3460 737531	PLANTINGS, MARYLAND	LUMP	120000.00000	120000.00	125000.00000	125000.00	98900.00000	98900.00			
3470 743003	ARROWPANELS, TYPE C	4.000 EADY	25.75000	103.00	2000.00000	8000.00	15.35000	61.40			
3480 743004	FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	72.000 EADY	73.90000	5320.80	69.62000	5012.64	67.00000	4824.00			
3490 743006	PLASTIC DRUMS	57020.000 EADY	0.15000	8553.00	0.16000	9123.20	0.30000	17106.00			
3500 743010	FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II	223.000 EADY	133.00000	29659.00	171.29000	38197.67	20.00000	4460.00			
3510 743015	FURNISH AND MAINTAIN PORTABLE PCC SAFETY BARRIER	2205.000 LF	27.15000	59865.75	25.00000	55125.00	31.70000	69898.50			
3520 743016	RELOCATION PORATBLE SAFETY BARRIER	1190.000 LF	6.10000	7259.00	9.00000	10710.00	10.25000	12197.50			
3530 743023	TEMPORARY BARRICADES, TYPE III	10650.000 LFDY	0.10000	1065.00	0.16000	1704.00	0.05000	532.50			
3540 743024	TEMPORARY WARNING SIGNS AND PLAQUES	32564.000 EADY	1.60000	52102.40	1.61000	52428.04	1.00000	32564.00			
3550 743025	INSTALL TEMPORARY IMPACT ATTENUATOR	5.000 EACH	2140.00000	10700.00	7000.00000	35000.00	1230.00000	6150.00			
3560 743029	FURNISH TEMPORARY IMPACT ATTENUATOR - NON-GATING, REDIRECTIVE, TEST LEVEL 3	2.000 EACH	1580.00000	3160.00	10000.00000	20000.00	8700.00000	17400.00			
3570 743030	RELOCATE TEMPORARY IMPACT ATTENUATOR	2.000 EACH	2140.00000	4280.00	1500.00000	3000.00	1540.00000	3080.00			
3580 744506	CONDUIT JUNCTION WELL, TYPE 7, PRECAST POLYMER CONCRETE	2.000 EACH	2100.00000	4200.00	2100.00000	4200.00	2870.00000	5740.00			

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -62

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)		
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC		
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3590 744530	CONDUIT JUNCTION WELL, TYPE 11, PRECAST CONCRETE/ POLYMER LID-FRAME	9.000 EACH	980.00000	8820.00	1000.00000	9000.00	972.00000	8748.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -63

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)		
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC		
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3600 744531	CONDUIT JUNCTION WELL, TYPE 14, PRECAST CONCRETE/ POLYMER LID-FRAME	4.000 EACH	1390.00000	5560.00	1500.00000	6000.00	1230.00000	4920.00
3610 745602	FURNISH & INSTALL UP TO 4" SCHEDULE 80 HDPE CONDUIT (BORE)	295.000 LF	31.55000	9307.25	32.00000	9440.00	22.50000	6637.50
3620 745604	FURNISH & INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	2880.000 LF	7.35000	21168.00	7.50000	21600.00	8.70000	25056.00
3630 745606	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (TRENCH)	5.000 LF	24.95000	124.75	25.00000	125.00	28.65000	143.25
3640 746586	RELOCATE SIGN	52.000 SF	10.50000	546.00	10.50000	546.00	22.50000	1170.00
3650 746852	POLE BASE, TYPE 6	2.000 EACH	1000.00000	2000.00	1000.00000	2000.00	870.00000	1740.00
3660 748032	TEMPORARY MARKINGS, PAINT, 5"	9079.000 LF	0.30000	2723.70	0.30000	2723.70	0.30000	2723.70
3670 748034	TEMPORARY MARKINGS, PAINT, 10"	810.000 LF	0.60000	486.00	0.60000	486.00	0.55000	445.50
3680 748525	TEMPORARY MARKINGS, TAPE, 4"	10915.000 LF	1.35000	14735.25	1.50000	16372.50	1.35000	14735.25
3690 748527	TEMPORARY MARKINGS, TAPE, WORDS/SYMBOLS	120.000 SF	5.25000	630.00	7.00000	840.00	5.10000	612.00
3700 748530	REMOVAL OF PAVEMENT STRIPING	3551.000 SF	2.40000	8522.40	2.50000	8877.50	2.35000	8344.85
3710 748560	5" WHITE PERMANENT PATTERNED REFLECTIVE PAVEMENT MARKING TAPE, MARYLAND	20532.000 LF	4.15000	85207.80	4.10000	84181.20	4.00000	82128.00
3720 748563	SNOWPLOWABLE RAISED PAVEMENT MARKERS, MARYLAND	115.000 EACH	33.65000	3869.75	34.00000	3910.00	32.75000	3766.25
3730 749500	SIGN PANEL	320.000 SF	26.00000	8320.00	25.73000	8233.60	38.90000	12448.00
3790 749687	INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	26.000 EACH	105.00000	2730.00	105.00000	2730.00	87.00000	2262.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -64

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

		(3)		(4)		(5)	
		RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT							
ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3800 749690	477.000 SF	15.75000	7512.75	15.75000	7512.75	20.45000	9754.65
INSTALLATION OR REMOVAL OF TRAFFIC SIGNS ON MULTIPLE SIGN POSTS							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -65

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
3810 756000	SAND	143.000 TON	33.00000	4719.00	40.00000	5720.00	100.00000	14300.00
3820 760006	PAVEMENT - MILLING, HOT-MIX, 2" DEPTH	21343.000 SY	1.35000	28813.05	1.60000	34148.80	2.60000	55491.80
3830 760016	RUMBLE STRIPS, HOT-MIX	11700.000 LF	0.15000	1755.00	0.20000	2340.00	0.15000	1755.00
3840 760017	RUMBLE STRIPS, CONCRETE	5800.000 LF	0.45000	2610.00	0.38000	2204.00	0.40000	2320.00
3850 760507	PROFILE MILLING, BITUMINOUS CONCRETE	2887.000 SYIN	1.30000	3753.10	3.20000	9238.40	4.00000	11548.00
3860 762001	SAW CUTTING, BITUMINOUS CONCRETE	2763.000 LF	1.05000	2901.15	1.50000	4144.50	2.00000	5526.00
3870 763573	SIGN, MARYLAND	1.000 EACH	1050.00000	1050.00	1050.00000	1050.00	12300.00000	12300.00
3880 763656	ASBUILT CERTIFICATION, MARYLAND	LUMP	6500.00000	6500.00	42500.00000	42500.00	22500.00000	22500.00
3890 763686	TRAFFIC OFFICER, MARYLAND	432.000 HOUR	98.16000	42405.12	98.16000	42405.12	98.16000	42405.12
3900 763691	FLAGGER, MARYLAND, STATE	500.000 HOUR	36.90000	18450.00	60.00000	30000.00	52.00000	26000.00
3910 763692	FLAGGER, MARYLAND, STATE, OVERTIME	100.000 HOUR	55.30000	5530.00	60.00000	6000.00	73.00000	7300.00
3920 905001	SILT FENCE	216.000 LF	1.35000	291.60	1.50000	324.00	10.00000	2160.00
3930 905003	SEDIMENT TRAP	2818.000 CY	20.85000	58755.30	10.50000	29589.00	20.00000	56360.00
3940 905004	INLET SEDIMENT CONTROL, DRAINAGE INLET	7.000 EACH	349.00000	2443.00	200.00000	1400.00	240.00000	1680.00
3950 905500	SUPER SILT FENCE	5311.000 LF	6.85000	36380.35	6.75000	35849.25	9.00000	47799.00
3960 906002	DEWATERING BAG	1.000 EACH	182.00000	182.00	110.00000	110.00	1000.00000	1000.00
3970 907011	STONE CHECK DAM	9.000 TON	65.60000	590.40	100.00000	900.00	100.00000	900.00
3980 908010	TOPSOILING, 6" DEPTH	53274.000 SY	2.00000	106548.00	1.50000	79911.00	1.75000	93229.50
3990 908020	EROSION CONTROL BLANKET MULCH	7828.000 SY	2.20000	17221.60	2.15000	16830.20	3.00000	23484.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 01/21/16

PAGE : 001 -66

TABULATION OF BIDS

FINAL

CONTRACT TITLE : US 301, MARYLAND STATE LINE TO LEVELS ROAD

CALL ORDER : 001

CONTRACT ID : T200811301.01

COUNTIES : NEW CASTLE

LETTING DATE : 12/22/15

DISTRICT : M7

SET-ASIDE :

			(3)		(4)		(5)	
			RICHARD E PIERSON CONST CO I		GEORGE & LYNCH INC		ALLAN MYERS MD INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
4000 908023	STABILIZED CONSTRUCTION ENTRANCE	529.000 TON	28.95000	15314.55	40.00000	21160.00	50.00000	26450.00
4010 910002	INFILTRATION STONE, NO. 8	844.000 TON	39.05000	32958.20	46.00000	38824.00	50.00000	42200.00
4020 910004	CLAY BORROW, CUT-OFF TRENCH	4926.000 CY	3.35000	16502.10	25.00000	123150.00	43.00000	211818.00
4030 910500	BIORETENTION SOIL MIX	290.000 CY	59.40000	17226.00	60.00000	17400.00	90.00000	26100.00
4050 605501	GROUND MOUNT BREAKAWAY TYPE SIGN SUPPORTS AND FOUNDATION	LUMP	26000.00000	26000.00	21000.00000	21000.00	38300.00000	38300.00
4070 201000	CLEARING AND GRUBBING	LUMP	150000.00000	150000.00	550000.00000	550000.00	300000.00000	300000.00
SECTION TOTALS			\$	3,839,466.42	\$	4,243,862.79	\$	4,280,026.37
CONTRACT TOTALS			\$	49,266,835.27	\$	51,660,683.11	\$	52,273,277.00
DBE GOALS				8 %		8 %		8 %