

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

STATE/FEDERAL AID NO: EBRN-N159(2)

CONTRACT TIME : 632 CALENDAR DAYS

CONTRACT DESCRIPTION :

URBAN (5,000 POPULATION OR MORE)

PROJECT(S) : EBRN-N159(2)

THE REPLACEMENT OF BRIDGE 1-159. THE EXISTING BRIDGE 1-159 IS AN INOPERABLE MOVABLE STEEL SUPERSTRUCTURE BRIDGE SUPPORTED ON REINFORCED CONCRETE ABUTMENTS AND PIERS. BRIDGE 1-159 CARRIES JAMES STREET OVER CHRISTINA RIVER IN NEWPORT, DELAWARE. THIS PROJECT INVOLVES THE REPLACEMENT OF THE EXISTING BRIDGE WITH A 5-SPAN PRE-STRESSED CONCRETE BOX BEAM BRIDGE SUPPORTED BY NEW REINFORCED CONCRETE ABUTMENTS AND PIERS ON DRILLED SHAFTS. THE PROPOSED CONSTRUCTION WILL BE OFF THE EXISTING ALIGNMENT TO ENSURE ACCESS DURING THE PROJECT, AND TO MINIMIZE IMPACT TO THE EXISTING 72" DIAMETER NEW CASTLE COUNTY SEWER FORCE MAIN THAT IS NEARING THE END OF ITS SERVICE LIFE. THE PROPOSED STRUCTURE WILL PROVIDE HIGHER UNDER CLEARANCE TO ALLOW FOR RECREATIONAL BOATING.

SET-ASIDE :

VENDOR RANKING : Contract was awarded on 09/10/19 to vendor MUMFORD & MILLER CONCRETE, INC.

RANK	VENDOR NAME				TOTAL BID	% OVER LOW BID	% OVER EST
0	ENGINEER'S ESTIMATE				\$ 13,336,500.00	88.7737%	100.0000%
1	MUMFORD & MILLER CONCRETE, INC., 1005 INDUSTRIAL DRIVE, MIDDLETOWN, DE, 19709				\$ 15,023,028.75	100.0000%	112.6460%
2	DRISCOLL CONSTRUCTION COMPANY, INC., 1740 WALTON ROAD SUITE 200, BLUE BELL, PA, \$				\$ 15,222,617.01	101.3285%	114.1425%
3	RICHARD E PIERSON CONSTRUCTION COMPANY, INC., P O BOX 430, WOODSTOWN, NJ, 08098				\$ 15,695,235.10	104.4745%	117.6863%

LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE UNIT PRICE	AMOUNT	(1) MUMFORD & MILLER CONCRETE IN UNIT PRICE	AMOUNT	(2) DRISCOLL CONSTRUCTION CO INC UNIT PRICE	AMOUNT
SECTION 0001	REGULAR ITEMS							
0010 201000	CLEARING AND GRUBBING	LUMP	100000.00000	100000.00	54000.00000	54000.00	150000.00000	150000.00
0020 202000	EXCAVATION AND EMBANKMENT	1698.000 CY	40.00000	67920.00	21.00000	35658.00	40.00000	67920.00
0030 202510	TEMPORARY COMPOSITE MATTING	1710.000 SF	14.00000	23940.00	50.00000	85500.00	25.00000	42750.00
0040 207000	EXCAVATION AND BACKFILL FOR STRUCTURES	213.000 CY	40.00000	8520.00	25.50000	5431.50	100.00000	21300.00
0050 207501	SHEETING AND SHORING	LUMP	600000.00000	600000.00	355700.00000	355700.00	1750000.00000	1750000.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -2

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE		(1) MUMFORD & MILLER CONCRETE IN		(2) DRISCOLL CONSTRUCTION CO INC	
		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0060 208000 EXCAVATION AND BACKFILLING FOR PIPE TRENCHES	320.000 CY	40.00000	12800.00	25.50000	8160.00	25.00000	8000.00
0070 209006 BORROW, TYPE F	632.000 CY	30.00000	18960.00	31.50000	19908.00	40.00000	25280.00
0080 209511 LIGHT WEIGHT AGGREGATE	901.000 CY	150.00000	135150.00	133.00000	119833.00	105.00000	94605.00
0090 210000 FURNISHING BORROW TYPE "C" FOR PIPE, UTILITY TRENCH, AND STRUCTURE BACKFILL	296.000 CY	20.00000	5920.00	26.00000	7696.00	25.00000	7400.00
0100 211000 REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP	30000.00000	30000.00	90000.00000	90000.00	25000.00000	25000.00
0110 211550 DEMOLITION OF EXISTING BRIDGE	LUMP	1000000.00000	1000000.00	1199600.00000	1199600.00	1200000.00000	1200000.00
0120 302007 GRADED AGGREGATE BASE COURSE, TYPE B	444.000 CY	55.00000	24420.00	68.00000	30192.00	125.00000	55500.00
0130 302011 DELAWARE NO. 3 STONE	179.000 TON	50.00000	8950.00	49.50000	8860.50	15.00000	2685.00
0140 401801 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS PG 64-22 (CARBONATE STONE)	8.000 TON	125.00000	1000.00	258.00000	2064.00	200.00000	1600.00
0150 401816 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 76-22	267.000 TON	110.00000	29370.00	120.00000	32040.00	130.00000	34710.00
0160 401819 BITUMINOUS CONCRETE, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22	264.000 TON	100.00000	26400.00	104.00000	27456.00	125.00000	33000.00
0170 401833 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)	323.000 TON	110.00000	35530.00	120.00000	38760.00	135.00000	43605.00
0180 503009 PATCHING P.C.C. PAVEMENT	41.000 SY	200.00000	8200.00	385.00000	15785.00	400.00000	16400.00
0190 602002 PORTLAND CEMENT CONCRETE MASONRY, CLASS B	3.000 CY	1200.00000	3600.00	2350.00000	7050.00	3000.00000	9000.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -3

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
0200 602004	PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT FOOTING, CLASS B	14.000 CY	1525.00000	21350.00	2010.00000	28140.00	2500.00000
							35000.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -4

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0210 602007	146.000 CY PORTLAND CEMENT CONCRETE MASONRY, PIER ABOVE FOOTING, CLASS A		2200.00000	321200.00	2295.00000	335070.00	3800.00000	554800.00
0220 602013	495.000 CY PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D		1200.00000	594000.00	1075.00000	532125.00	1800.00000	891000.00
0230 602014	89.000 CY PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D		1000.00000	89000.00	660.00000	58740.00	1000.00000	89000.00
0240 602015	129.000 CY PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A		1000.00000	129000.00	825.00000	106425.00	2000.00000	258000.00
0250 602017	137.000 CY PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A		2000.00000	274000.00	1485.00000	203445.00	1600.00000	219200.00
0260 602520	169.000 SY EPOXY PROTECTIVE COATING FOR CONCRETE		40.00000	6760.00	109.00000	18421.00	140.00000	23660.00
0270 602549	1851.000 SF FORM LINERS		18.00000	33318.00	13.65000	25266.15	25.00000	46275.00
0280 602616	550.000 SF WATERPROOFING P.C.C. MASONRY SURFACES		10.00000	5500.00	8.00000	4400.00	15.00000	8250.00
0290 602646	4100.000 SF SILICONE ACRYLIC CONCRETE SEALER		5.00000	20500.00	9.00000	36900.00	7.00000	28700.00
0300 604000	297500.000 LB BAR REINFORCEMENT, EPOXY COATED		2.00000	595000.00	1.55000	461125.00	1.60000	476000.00
0310 605002	LUMP STEEL STRUCTURES		350000.00000	350000.00	370400.00000	370400.00	400000.00000	400000.00
0320 605511	86.000 LF PREFABRICATED EXPANSION JOINT SYSTEM, 3		500.00000	43000.00	484.00000	41624.00	500.00000	43000.00
0330 606002	481.000 LF METAL BRIDGE RAILING, ALUMINUM		150.00000	72150.00	77.00000	37037.00	150.00000	72150.00
0340 606003	464.000 LF METAL BRIBGE RAILING (PEDESTRIAN)		275.00000	127600.00	197.00000	91408.00	250.00000	116000.00
0350 608000	14.000 TON COARSE AGGREGATE FOR FOUNDATION STABILIZATION AND SUBFOUNDATION BACKFILL		115.00000	1610.00	124.00000	1736.00	60.00000	840.00
0360 612002	29.000 LF REINFORCED CONCRETE PIPE, 15", CLASS II		50.00000	1450.00	133.00000	3857.00	100.00000	2900.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -5

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0370 612003	38.000 LF		60.00000	2280.00	140.00000	5320.00	150.00000	5700.00
REINFORCED CONCRETE PIPE, 18", CLASS II								
0380 612005	145.000 LF		75.00000	10875.00	152.00000	22040.00	110.00000	15950.00
REINFORCED CONCRETE PIPE, 24", CLASS II								
0390 617005	1.000 EACH		1500.00000	1500.00	1650.00000	1650.00	1800.00000	1800.00
REINFORCED CONCRETE FLARED END SECTION, 24"								
0400 618529	2697.000 LF		1500.00000	4045500.00	1515.00000	4085955.00	1400.00000	3775800.00
DRILLED SHAFT, 48"								
0410 618530	101.000 LF		1400.00000	141400.00	2115.00000	213615.00	1500.00000	151500.00
TECHNIQUE SHAFT, 48"								
0420 618531	2581.000 LF		200.00000	516200.00	293.00000	756233.00	325.00000	838825.00
PERMANENT CASING FOR DRILLED SHAFT, 48" DIAMETER								
0430 618532	1.000 EACH		150000.00000	150000.00	140800.00000	140800.00	150000.00000	150000.00
LOAD TESTING OF DRILLED SHAFTS								
0440 619511	110.000 LF		120.00000	13200.00	41.00000	4510.00	200.00000	22000.00
EXPLORATORY DRILLING								
0450 622001	2500.000 SF		50.00000	125000.00	32.00000	80000.00	75.00000	187500.00
STEEL SHEET PILES, PZ 22 (UNPROTECTED)								
0460 623002	LUMP		1250000.00000	1250000.00	702700.00000	702700.00	750000.00000	750000.00
PRESTRESSED REINFORCED CONCRETE MEMBERS BOX-BEAMS								
0470 701020	195.000 LF		40.00000	7800.00	57.00000	11115.00	26.00000	5070.00
INTEGRAL PORTLAND CEMENT CONCRETE CURB & GUTTER, TYPE 1-8								
0480 705001	421.000 SF		8.00000	3368.00	19.00000	7999.00	17.00000	7157.00
P.C.C. SIDEWALK, 4"								
0490 705002	608.000 SF		12.00000	7296.00	20.00000	12160.00	20.00000	12160.00
P.C.C. SIDEWALK, 6"								
0500 705006	679.000 SF		16.00000	10864.00	22.00000	14938.00	17.00000	11543.00
P.C.C. SIDEWALK, VARIABLE DEPTH								
0510 705007	84.000 SF		35.00000	2940.00	45.50000	3822.00	37.00000	3108.00
SIDEWALK SURFACE DETECTABLE WARNING SYSTEM								
0520 705009	757.000 SF		20.00000	15140.00	42.00000	31794.00	55.00000	41635.00
CURB RAMP, TYPE 2, 3, AND/OR 4								
0530 708050	1.000 EACH		2000.00000	2000.00	4200.00000	4200.00	3000.00000	3000.00
DRAINAGE INLET, 34" X 18"								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -6

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE		(1) MUMFORD & MILLER CONCRETE IN		(2) DRISCOLL CONSTRUCTION CO INC	
			UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0540 708052 DRAINAGE INLET, 48" X 30"	1.000	EACH	4000.00000	4000.00	5150.00000	5150.00	4200.00000	4200.00
0550 708053 DRAINAGE INLET, 48" X 48"	1.000	EACH	4500.00000	4500.00	5250.00000	5250.00	3700.00000	3700.00
0560 708112 MANHOLE, 48" X 48"	1.000	EACH	3500.00000	3500.00	4200.00000	4200.00	5000.00000	5000.00
0570 710001 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	1.000	EACH	1000.00000	1000.00	1300.00000	1300.00	650.00000	650.00
0580 710002 ADJUSTING AND REPAIRING EXISTING MANHOL	2.000	EACH	1000.00000	2000.00	1300.00000	2600.00	1100.00000	2200.00
0590 710506 ADJUST AND REPAIR EXISTING SANITARY MANHOLE	4.000	EACH	1000.00000	4000.00	1300.00000	5200.00	1100.00000	4400.00
0600 712020 RIPRAP, R-4	116.000	TON	75.00000	8700.00	82.50000	9570.00	75.00000	8700.00
0610 712021 RIPRAP, R-5	816.000	TON	75.00000	61200.00	87.00000	70992.00	75.00000	61200.00
0620 712531 CHANNEL BED FILL	115.000	CY	50.00000	5750.00	42.00000	4830.00	150.00000	17250.00
0630 713002 GEOTEXTILES, SEPARATION	2192.000	SY	4.00000	8768.00	5.25000	11508.00	2.50000	5480.00
0640 713003 GEOTEXTILES, RIPRAP	765.000	SY	5.00000	3825.00	5.25000	4016.25	4.00000	3060.00
0650 720529 P.C.C. SAFETY BARRIER PERMANENT, SINGLE FACE	82.000	LF	450.00000	36900.00	350.00000	28700.00	750.00000	61500.00
0660 720636 FURNISH AND MAINTAIN PORTABLE P.C.C. PINNED SAFETY BARRIER, DOUBLE FACE	210.000	LF	50.00000	10500.00	29.50000	6195.00	85.00000	17850.00
0670 727004 CHAIN-LINK FENCE, 6' HIGH	152.000	LF	30.00000	4560.00	40.50000	6156.00	41.00000	6232.00
0680 727012 VEHICULAR GATES	2.000	EACH	1300.00000	2600.00	2100.00000	4200.00	2100.00000	4200.00
0690 727014 CONSTRUCTION SAFETY FENCE	320.000	LF	2.50000	800.00	3.25000	1040.00	20.00000	6400.00
0700 743000 MAINTENANCE OF TRAFFIC		LUMP	120000.00000	120000.00	185700.00000	185700.00	20000.00000	20000.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -7

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
ITEM DESCRIPTION								
0710 743004	124.000	EADY	90.00000	11160.00	90.00000	11160.00	100.00000	12400.00
FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN								
0720 743005	806.000	EADY	40.00000	32240.00	60.00000	48360.00	1.00000	806.00
FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY								
0730 743006	38821.000	EADY	1.00000	38821.00	0.40000	15528.40	0.35000	13587.35
PLASTIC DRUMS								
0740 743008	19.000	EACH	25.00000	475.00	55.00000	1045.00	25.00000	475.00
REFLECTOR PANELS								
0750 743015	238.000	LF	40.00000	9520.00	16.50000	3927.00	71.00000	16898.00
FURNISH AND MAINTAIN PORTABLE PCC SAFETY BARRIER								
0760 743023	6306.000	LFDY	0.25000	1576.50	0.50000	3153.00	0.50000	3153.00
TEMPORARY BARRICADES, TYPE III								
0770 743024	5890.000	EADY	2.50000	14725.00	2.50000	14725.00	2.25000	13252.50
TEMPORARY WARNING SIGNS AND PLAQUES								
0780 743053	3968.000	HOOR	60.00000	238080.00	85.00000	337280.00	53.70000	213081.60
FLAGGER, NEW CASTLE COUNTY, HEAVY CONSTRUCTION, STATE								
0790 743068	1068.000	HOOR	75.00000	80100.00	110.00000	117480.00	69.17000	73873.56
FLAGGER, NEW CASTLE COUNTY, HEAVY CONSTRUCTION, STATE, OVERTIME								
0800 744520	2.000	EACH	1100.00000	2200.00	1610.00000	3220.00	1150.00000	2300.00
CONDUIT JUNCTION WELL, TYPE 1, PRECAST CONCRETE								
0810 744523	2.000	EACH	1330.00000	2660.00	2320.00000	4640.00	1400.00000	2800.00
CONDUIT JUNCTION WELL, TYPE 4, PRECAST CONCRETE								
0820 744529	7.000	EACH	1000.00000	7000.00	5575.00000	39025.00	3900.00000	27300.00
P.C.C. BARRIER JUNCTION WELL								
0830 745500	189.000	LF	8.00000	1512.00	12.50000	2362.50	12.50000	2362.50
GALVANIZED CONDUIT IN/ON STRUCTURE, 1"								
0840 745502	755.000	LF	10.00000	7550.00	22.50000	16987.50	29.00000	21895.00
GALVANIZED CONDUIT IN/ON STRUCTURE, 2 1/2"								
0850 745604	248.000	LF	12.00000	2976.00	12.00000	2976.00	18.50000	4588.00
FURNISH & INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -8

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(0)	(1)	(2)			
			ENGINEER'S ESTIMATE	MUMFORD & MILLER CONCRETE IN	DRISCOLL CONSTRUCTION CO INC			
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0860 745606	75.000 LF		23.00000	1725.00	38.50000	2887.50	36.00000	2700.00
FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (TRENCH)								
0870 746517	2.000 EACH		4000.00000	8000.00	4265.00000	8530.00	2875.00000	5750.00
ALUMINUM LIGHTING STANDARD WITH SINGLE DAVIT ARM, 30' POLE								
0880 746653	LUMP		1500.00000	1500.00	4360.00000	4360.00	5100.00000	5100.00
ELECTRICAL TESTING								
0890 746669	2.000 EACH		500.00000	1000.00	855.00000	1710.00	515.00000	1030.00
LUMINAIRE (HPS), 150 WATTS								
0900 746852	2.000 EACH		950.00000	1900.00	1320.00000	2640.00	925.00000	1850.00
POLE BASE, TYPE 6								
0910 747508	1.000 EACH		6500.00000	6500.00	11750.00000	11750.00	11250.00000	11250.00
LIGHTING CONTROL CENTER - 100 A								
0920 747515	1.000 EACH		930.00000	930.00	1685.00000	1685.00	1550.00000	1550.00
CABINET BASE, TYPE M								
0930 748015	504.000 SF		7.00000	3528.00	6.00000	3024.00	5.25000	2646.00
PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC								
0940 748019	5828.000 LF		0.50000	2914.00	0.50000	2914.00	0.50000	2914.00
TEMPORARY MARKINGS, PAINT, 4"								
0950 748026	413.000 SF		1.50000	619.50	2.35000	970.55	2.00000	826.00
TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND								
0960 748530	104.000 SF		8.00000	832.00	19.75000	2054.00	17.50000	1820.00
REMOVAL OF PAVEMENT STRIPING								
0970 748548	3519.000 LF		0.50000	1759.50	1.15000	4046.85	1.00000	3519.00
PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"								
0980 749687	59.000 EACH		75.00000	4425.00	175.00000	10325.00	100.00000	5900.00
INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST								
0990 749688	3.000 EACH		75.00000	225.00	135.00000	405.00	200.00000	600.00
INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" DEPTH								
1000 749689	1.000 EACH		100.00000	100.00	135.00000	135.00	215.00000	215.00
INSTALLATION OF 4" DIAMETER HOLE, GREATER THAN 6" DEPTH								

DATE : 09/10/19

PAGE : 001 -9

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

		(0)		(1)		(2)	
		ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1010 758000 REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	243.000 SY	30.00000	7290.00	25.00000	6075.00	15.00000	3645.00

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -10

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1020 759004	26.000	EAMO	3800.00000	98800.00	2180.00000	56680.00	2500.00000	65000.00
FIELD OFFICE, TYPE I								
1030 760000	2604.000	SYIN	3.00000	7812.00	2.35000	6119.40	7.50000	19530.00
PAVEMENT - MILLING, HOT-MIX								
1040 762001	746.000	LF	3.00000	2238.00	2.50000	1865.00	3.00000	2238.00
SAW CUTTING, BITUMINOUS CONCRETE								
1050 762002	20.000	LF	5.50000	110.00	10.00000	200.00	40.00000	800.00
SAW CUTTING, CONCRETE, FULL DEPTH								
1060 763000		LUMP	422947.50000	422947.50	462000.00000	462000.00	750000.00000	750000.00
INITIAL EXPENSE								
1070 763501		LUMP	400000.00000	400000.00	209300.00000	209300.00	125000.00000	125000.00
CONSTRUCTION ENGINEERING								
1080 763503	1040.000	HOUR	0.80000	832.00	0.80000	832.00	0.80000	832.00
TRAINEE								
1090 763508		LUMP	20000.00000	20000.00	2900.00000	2900.00	2100.00000	2100.00
PROJECT CONTROL SYSTEM DEVELOPMENT PLAN								
1100 763509	33.000	EAMO	500.00000	16500.00	100.00000	3300.00	500.00000	16500.00
CPM SCHEDULE UPDATES AND/OR REVISED UPDATES								
1110 763522		LUMP	25000.00000	25000.00	1140100.00000	1140100.00	20000.00000	20000.00
COAST GUARD SPECIFIC CONDITIONS								
1120 763620		LUMP	300000.00000	300000.00	1342700.00000	1342700.00	475000.00000	475000.00
PROTECTION OF UTILITY BY CONTRACTOR								
1130 763623		LUMP	20000.00000	20000.00	66200.00000	66200.00	40000.00000	40000.00
NETTING MIGRATORY BIRD EXCLUSION								
1140 905001	242.000	LF	3.00000	726.00	4.00000	968.00	6.00000	1452.00
SILT FENCE								
1150 905002	489.000	LF	4.50000	2200.50	6.00000	2934.00	10.00000	4890.00
REINFORCED SILT FENCE								
1160 905004	5.000	EACH	150.00000	750.00	175.00000	875.00	800.00000	4000.00
INLET SEDIMENT CONTROL, DRAINAGE INLET								
1170 906001	3.000	EACH	1500.00000	4500.00	875.00000	2625.00	7000.00000	21000.00
PORTABLE SEDIMENT TANK								
1180 906003	3.000	EACH	2000.00000	6000.00	600.00000	1800.00	3000.00000	9000.00
SUMP PIT								
1190 907510	271.000	LF	8.50000	2303.50	12.00000	3252.00	6.50000	1761.50
COMPOST FILTER LOG								
1200 908002	112.000	CY	20.00000	2240.00	90.00000	10080.00	55.00000	6160.00
TOPSOIL (CY)								

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -11

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(0)		(1)		(2)	
			ENGINEER'S ESTIMATE		MUMFORD & MILLER CONCRETE IN		DRISCOLL CONSTRUCTION CO INC	
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1210 908004	TOPSOIL, 6" DEPTH	3964.000 SY	10.00000	39640.00	8.50000	33694.00	8.00000	31712.00
1220 908014	PERMANENT GRASS SEEDING, DRY GROUND	3903.000 SY	1.50000	5854.50	1.25000	4878.75	1.00000	3903.00
1230 908017	TEMPORARY GRASS SEEDING	4151.000 SY	1.50000	6226.50	1.15000	4773.65	1.00000	4151.00
1240 908019	STREAMBANK SEED MIX, SEEDING	194.000 SY	5.00000	970.00	5.00000	970.00	5.00000	970.00
1250 908020	EROSION CONTROL BLANKET MULCH	313.000 SY	4.00000	1252.00	3.75000	1173.75	5.00000	1565.00
1260 908023	STABILIZED CONSTRUCTION ENTRANCE	73.000 TON	150.00000	10950.00	47.50000	3467.50	65.00000	4745.00
1270 909004	TURBIDITY CURTAIN, FLOATING	1024.000 LF	30.00000	30720.00	18.25000	18688.00	80.00000	81920.00
SECTION TOTALS			\$	13,336,500.00	\$	15,023,028.75	\$	15,222,617.01
CONTRACT TOTALS			\$	13,336,500.00	\$	15,023,028.75	\$	15,222,617.01
DBE GOALS				8 %		8 %		8 %

DATE : 09/10/19

PAGE : 001 -12

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)		()		()	
			RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
SECTION 0001 REGULAR ITEMS								
0010 201000	CLEARING AND GRUBBING	LUMP	350000.00000	350000.00				
0020 202000	EXCAVATION AND EMBANKMENT	1698.000 CY	40.00000	67920.00				
0030 202510	TEMPORARY COMPOSITE MATTING	1710.000 SF	40.00000	68400.00				
0040 207000	EXCAVATION AND BACKFILL FOR STRUCTURES	213.000 CY	300.00000	63900.00				
0050 207501	SHEETING AND SHORING	LUMP	40000.00000	40000.00				
0060 208000	EXCAVATION AND BACKFILLING FOR PIPE TRENCHES	320.000 CY	15.00000	4800.00				
0070 209006	BORROW, TYPE F	632.000 CY	37.00000	23384.00				
0080 209511	LIGHT WEIGHT AGGREGATE	901.000 CY	165.00000	148665.00				
0090 210000	FURNISHING BORROW TYPE "C" FOR PIPE, UTILITY TRENCH, AND STRUCTURE BACKFILL	296.000 CY	60.00000	17760.00				
0100 211000	REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LUMP	50000.00000	50000.00				
0110 211550	DEMOLITION OF EXISTING BRIDGE	LUMP	1400000.00000	1400000.00				
0120 302007	GRADED AGGREGATE BASE COURSE, TYPE B	444.000 CY	67.00000	29748.00				
0130 302011	DELAWARE NO. 3 STONE	179.000 TON	45.00000	8055.00				
0140 401801	BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS PG 64-22 (CARBONATE STONE)	8.000 TON	280.00000	2240.00				
0150 401816	BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 76-22	267.000 TON	150.00000	40050.00				

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -13

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

=====		(3)		()		()	
		RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
-----		-----	-----	-----	-----	-----	-----
0160 401819	264.000 TON	132.00000	34848.00				
BITUMINOUS CONCRETE, SUPERPAVE,							
BITUMINOUS CONCRETE BASE COURSE, 160							
GYRATIONS, PG 64-22							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -14

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

=====		=====		=====		=====	
		(3)		()		()	
RICHARD E PIERSON CONST CO I							
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
-----		-----	-----	-----	-----	-----	-----
0170 401833	323.000 TON		155.00000	50065.00			
BITUMINOUS CONCRETE, SUPERPAVE, TYPE C,							
160 GYRATIONS, PG 76-22, (NON-CARBONATE							
STONE)							

DATE : 09/10/19

PAGE : 001 -15

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)	()		()		
			RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0180 503009	PATCHING P.C.C. PAVEMENT	41.000 SY	225.00000	9225.00				
0190 602002	PORTLAND CEMENT CONCRETE MASONRY, CLASS B	3.000 CY	2000.00000	6000.00				
0200 602004	PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT FOOTING, CLASS B	14.000 CY	2000.00000	28000.00				
0210 602007	PORTLAND CEMENT CONCRETE MASONRY, PIER ABOVE FOOTING, CLASS A	146.000 CY	3000.00000	438000.00				
0220 602013	PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D	495.000 CY	2200.00000	1089000.00				
0230 602014	PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D	89.000 CY	1200.00000	106800.00				
0240 602015	PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A	129.000 CY	1800.00000	232200.00				
0250 602017	PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A	137.000 CY	2500.00000	342500.00				
0260 602520	EPOXY PROTECTIVE COATING FOR CONCRETE	169.000 SY	75.00000	12675.00				
0270 602549	FORM LINERS	1851.000 SF	28.00000	51828.00				
0280 602616	WATERPROOFING P.C.C. MASONRY SURFACES	550.000 SF	5.25000	2887.50				
0290 602646	SILICONE ACRYLIC CONCRETE SEALER	4100.000 SF	5.00000	20500.00				
0300 604000	BAR REINFORCEMENT, EPOXY COATED	297500.000 LB	1.50000	446250.00				
0310 605002	STEEL STRUCTURES	LUMP	750000.00000	750000.00				
0320 605511	PREFABRICATED EXPANSION JOINT SYSTEM, 3	86.000 LF	500.00000	43000.00				
0330 606002	METAL BRIDGE RAILING, ALUMINUM	481.000 LF	175.00000	84175.00				

DATE : 09/10/19

PAGE : 001 -16

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)	()		()		
			RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0340 606003	METAL BRIBGE RAILING (PEDESTRIAN)	464.000 LF	225.00000	104400.00				
0350 608000	COARSE AGGREGATE FOR FOUNDATION STABILIZATION AND SUBFOUNDATION BACKFILL	14.000 TON	150.00000	2100.00				
0360 612002	REINFORCED CONCRETE PIPE, 15", CLASS II	29.000 LF	150.00000	4350.00				
0370 612003	REINFORCED CONCRETE PIPE, 18", CLASS II	38.000 LF	125.00000	4750.00				
0380 612005	REINFORCED CONCRETE PIPE, 24", CLASS II	145.000 LF	140.00000	20300.00				
0390 617005	REINFORCED CONCRETE FLARED END SECTION, 24"	1.000 EACH	1600.00000	1600.00				
0400 618529	DRILLED SHAFT, 48"	2697.000 LF	1400.00000	3775800.00				
0410 618530	TECHNIQUE SHAFT, 48"	101.000 LF	1200.00000	121200.00				
0420 618531	PERMANENT CASING FOR DRILLED SHAFT, 48" DIAMETER	2581.000 LF	345.00000	890445.00				
0430 618532	LOAD TESTING OF DRILLED SHAFTS	1.000 EACH	100000.00000	100000.00				
0440 619511	EXPLORATORY DRILLING	110.000 LF	100.00000	11000.00				
0450 622001	STEEL SHEET PILES, PZ 22 (UNPROTECTED)	2500.000 SF	40.00000	100000.00				
0460 623002	PRESTRESSED REINFORCED CONCRETE MEMBERS BOX-BEAMS	LUMP	1410000.00000	1410000.00				
0470 701020	INTEGRAL PORTLAND CEMENT CONCRETE CURB & GUTTER, TYPE 1-8	195.000 LF	25.00000	4875.00				
0480 705001	P.C.C. SIDEWALK, 4"	421.000 SF	10.00000	4210.00				
0490 705002	P.C.C. SIDEWALK, 6"	608.000 SF	12.00000	7296.00				
0500 705006	P.C.C. SIDEWALK, VARIABLE DEPTH	679.000 SF	15.00000	10185.00				

DATE : 09/10/19

PAGE : 001 -17

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)	()		()		
			RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0510 705007	SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	84.000 SF	37.00000	3108.00				
0520 705009	CURB RAMP, TYPE 2, 3, AND/OR 4	757.000 SF	40.00000	30280.00				
0530 708050	DRAINAGE INLET, 34" X 18"	1.000 EACH	3000.00000	3000.00				
0540 708052	DRAINAGE INLET, 48" X 30"	1.000 EACH	4000.00000	4000.00				
0550 708053	DRAINAGE INLET, 48" X 48"	1.000 EACH	4000.00000	4000.00				
0560 708112	MANHOLE, 48" X 48"	1.000 EACH	3500.00000	3500.00				
0570 710001	ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	1.000 EACH	450.00000	450.00				
0580 710002	ADJUSTING AND REPAIRING EXISTING MANHOL	2.000 EACH	410.00000	820.00				
0590 710506	ADJUST AND REPAIR EXISTING SANITARY MANHOLE	4.000 EACH	413.50000	1654.00				
0600 712020	RIPRAP, R-4	116.000 TON	160.00000	18560.00				
0610 712021	RIPRAP, R-5	816.000 TON	210.00000	171360.00				
0620 712531	CHANNEL BED FILL	115.000 CY	210.00000	24150.00				
0630 713002	GEOTEXTILES, SEPARATION	2192.000 SY	2.00000	4384.00				
0640 713003	GEOTEXTILES, RIPRAP	765.000 SY	4.00000	3060.00				
0650 720529	P.C.C. SAFETY BARRIER PERMANENT, SINGLE FACE	82.000 LF	370.00000	30340.00				
0660 720636	FURNISH AND MAINTAIN PORTABLE P.C.C. PINNED SAFETY BARRIER, DOUBLE FACE	210.000 LF	80.00000	16800.00				
0670 727004	CHAIN-LINK FENCE, 6' HIGH	152.000 LF	35.00000	5320.00				

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -18

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)		()		()	
			RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0680 727012	VEHICULAR GATES	2.000 EACH	1200.00000	2400.00				
0690 727014	CONSTRUCTION SAFETY FENCE	320.000 LF	11.00000	3520.00				
0700 743000	MAINTENANCE OF TRAFFIC	LUMP	90000.00000	90000.00				
0710 743004	FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	124.000 EADY	250.00000	31000.00				
0720 743005	FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY	806.000 EADY	35.00000	28210.00				
0730 743006	PLASTIC DRUMS	38821.000 EADY	0.45000	17469.45				
0740 743008	REFLECTOR PANELS	19.000 EACH	24.00000	456.00				
0750 743015	FURNISH AND MAINTAIN PORTABLE PCC SAFETY BARRIER	238.000 LF	67.00000	15946.00				
0760 743023	TEMPORARY BARRICADES, TYPE III	6306.000 LFDY	0.30000	1891.80				
0770 743024	TEMPORARY WARNING SIGNS AND PLAQUES	5890.000 EADY	4.00000	23560.00				
0780 743053	FLAGGER, NEW CASTLE COUNTY, HEAVY CONSTRUCTION, STATE	3968.000 HOUR	57.00000	226176.00				
0790 743068	FLAGGER, NEW CASTLE COUNTY, HEAVY CONSTRUCTION, STATE, OVERTIME	1068.000 HOUR	85.00000	90780.00				
0800 744520	CONDUIT JUNCTION WELL, TYPE 1, PRECAST CONCRETE	2.000 EACH	1200.00000	2400.00				
0810 744523	CONDUIT JUNCTION WELL, TYPE 4, PRECAST CONCRETE	2.000 EACH	1500.00000	3000.00				
0820 744529	P.C.C. BARRIER JUNCTION WELL	7.000 EACH	4000.00000	28000.00				
0830 745500	GALVANIZED CONDUIT IN/ON STRUCTURE, 1"	189.000 LF	12.00000	2268.00				

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -19

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

		(3)		()		()	
		RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
0840 745502	GALVANIZED CONDUIT IN/ON STRUCTURE, 2 1/2"	755.000 LF	28.00000	21140.00			
0850 745604	FURNISH & INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	248.000 LF	18.00000	4464.00			
0860 745606	FURNISH & INSTALL UP TO 4" GALVANIZED STEEL CONDUIT (TRENCH)	75.000 LF	35.00000	2625.00			
0870 746517	ALUMINUM LIGHTING STANDARD WITH SINGLE DAVIT ARM, 30' POLE	2.000 EACH	2800.00000	5600.00			
0880 746653	ELECTRICAL TESTING	LUMP	5000.00000	5000.00			
0890 746669	LUMINAIRE (HPS), 150 WATTS	2.000 EACH	500.00000	1000.00			
0900 746852	POLE BASE, TYPE 6	2.000 EACH	900.00000	1800.00			
0910 747508	LIGHTING CONTROL CENTER - 100 A	1.000 EACH	11250.00000	11250.00			
0920 747515	CABINET BASE, TYPE M	1.000 EACH	1500.00000	1500.00			
0930 748015	PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	504.000 SF	8.00000	4032.00			
0940 748019	TEMPORARY MARKINGS, PAINT, 4"	5828.000 LF	0.30000	1748.40			
0950 748026	TEMPORARY MARKINGS, PAINT SYMBOL/LEGEND	413.000 SF	4.00000	1652.00			
0960 748530	REMOVAL OF PAVEMENT STRIPING	104.000 SF	15.50000	1612.00			
0970 748548	PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	3519.000 LF	1.25000	4398.75			
0980 749687	INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	59.000 EACH	105.00000	6195.00			

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -20

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

=====		=====		=====		=====	
		(3)		()		()	
		RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
-----		-----	-----	-----	-----	-----	-----
0990 749688	INSTALLATION OF 4" DIAMETER HOLE, LESS THAN OR EQUAL TO 6" DEPTH	3.000 EACH	185.00000	555.00			

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -21

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)		()		()
			RICHARD E PIERSON CONST CO I				
LINE NO / ITEM CODE / ALT	QUANTITY		UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE
ITEM DESCRIPTION							AMOUNT
1000 749689	1.000	EACH	220.00000	220.00			
INSTALLATION OF 4" DIAMETER HOLE, GREATER THAN 6" DEPTH							
1010 758000	243.000	SY	7.00000	1701.00			
REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.							
1020 759004	26.000	EAMO	3500.00000	91000.00			
FIELD OFFICE, TYPE I							
1030 760000	2604.000	SYIN	7.75000	20181.00			
PAVEMENT - MILLING, HOT-MIX							
1040 762001	746.000	LF	1.00000	746.00			
SAW CUTTING, BITUMINOUS CONCRETE							
1050 762002	20.000	LF	3.40000	68.00			
SAW CUTTING, CONCRETE, FULL DEPTH							
1060 763000		LUMP	775000.00000	775000.00			
INITIAL EXPENSE							
1070 763501		LUMP	250000.00000	250000.00			
CONSTRUCTION ENGINEERING							
1080 763503	1040.000	HOUR	0.80000	832.00			
TRAINEE							
1090 763508		LUMP	40000.00000	40000.00			
PROJECT CONTROL SYSTEM DEVELOPMENT PLAN							
1100 763509	33.000	EAMO	250.00000	8250.00			
CPM SCHEDULE UPDATES AND/OR REVISED UPDATES							
1110 763522		LUMP	15000.00000	15000.00			
COAST GUARD SPECIFIC CONDITIONS							
1120 763620		LUMP	650000.00000	650000.00			
PROTECTION OF UTILITY BY CONTRACTOR							
1130 763623		LUMP	125000.00000	125000.00			
NETTING MIGRATORY BIRD EXCLUSION							
1140 905001	242.000	LF	3.10000	750.20			
SILT FENCE							
1150 905002	489.000	LF	4.20000	2053.80			
REINFORCED SILT FENCE							
1160 905004	5.000	EACH	260.00000	1300.00			
INLET SEDIMENT CONTROL, DRAINAGE INLET							

DELAWARE DEPARTMENT OF TRANSPORTATION

DATE : 09/10/19

PAGE : 001 -22

TABULATION OF BIDS

FINAL

CONTRACT TITLE : BR 1-159 ON JAMES STREET OVER CHRISTINA RIVER

CALL ORDER : 001

CONTRACT ID : T201207101.02

COUNTIES : NEW CASTLE

LETTING DATE : 08/14/19

DISTRICT : G1

SET-ASIDE :

			(3)	()		()		
			RICHARD E PIERSON CONST CO I					
LINE NO / ITEM CODE / ALT	ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
1170 906001	PORTABLE SEDIMENT TANK	3.000 EACH	2500.00000	7500.00				
1180 906003	SUMP PIT	3.000 EACH	1000.00000	3000.00				
1190 907510	COMPOST FILTER LOG	271.000 LF	6.25000	1693.75				
1200 908002	TOPSOIL (CY)	112.000 CY	150.00000	16800.00				
1210 908004	TOPSOIL, 6" DEPTH	3964.000 SY	8.25000	32703.00				
1220 908014	PERMANENT GRASS SEEDING, DRY GROUND	3903.000 SY	0.90000	3512.70				
1230 908017	TEMPORARY GRASS SEEDING	4151.000 SY	0.70000	2905.70				
1240 908019	STREAMBANK SEED MIX, SEEDING	194.000 SY	4.15000	805.10				
1250 908020	EROSION CONTROL BLANKET MULCH	313.000 SY	4.15000	1298.95				
1260 908023	STABILIZED CONSTRUCTION ENTRANCE	73.000 TON	100.00000	7300.00				
1270 909004	TURBIDITY CURTAIN, FLOATING	1024.000 LF	33.00000	33792.00				
SECTION TOTALS			\$	15,695,235.10	\$		\$	
CONTRACT TOTALS			\$	15,695,235.10	\$	0.00	\$	
DBE GOALS			8	%		%		%