TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3
STATE/FEDERAL AID NO: 5307-2012(04) CONTRACT TIME : 75 CALENDAR DAYS
CONTRACT DESCRIPTION : URBAN (5,000 POPULATION OR MORE) PROJECT(S) : 5307-2012(04)
THE PROPOSED PROJECT IS LOCATED IN KENT COUNTY, DELAWARE, AT
THE DELAWARE TRANSIT CORPORATION (DTC)
DOVER ADMINISTRATION AND MAINTENANCE FACILITY ON PUBLIC
SAFETY BOULEVARD. THE PURPOSE OF THIS PROJECT
IS TO RECONFIGURE THE EXISTING PARKING LOT TO ALLOW FOR
INCREASED PARKING EFFICIENCY AND INCREASED
OPERATING AREA FOR BUSSES AND OTHER VEHICLES. IMPROVEMENTS
INCLUDE: NEW PARKING AREAS, ADA SITE IMPROVEMENTS, HANDICAP
PARKING SPACES,VISTOR PARKING SPACES, RAMPS AND CURB RAMPS,
AND SIDEWALK WILL BE ADDED AND EXISTING IMPERVIOUS AREAS
THAT ARE NOT UTILIZED WILL BE REMOVED. BUS PARKING WILL BE
INCREASED FROM 65 TO 80 AND VEHICLE PARKING WILL BE
INCREASED FROM 184 TO 228. IN ORDER TO LIMIT INTERFERENCE
WITH DAILY OPERATIONS, MOST OF THE PARKING LOT WORK MUST BE
PERFORMED AROUND WEEKENDS (FRIDAY, SATURDAY, SUNDAY,
MONDAY). THE CONTRACTOR IS RESPONSIBLE FOR ALL NECESSARY
PERMITS. THIS WORK IS CONSIDERED REHABILITATION TO EXISTING
ROADWORK, AND OTHER INCIDENTAL CONSTRUCTION IN ACCORDANCE
WITH THE LOCATION, NOTES AND DETAILS SHOWN ON THE PLANS AND
AS DIRECTED BY THE ENGINEER.

SET-ASIDE :

VENDOR RANKING : Contract was awarded on 03/07/16 to vendor GEORGE & LYNCH, INC.

RANK	VENDOR NAME	TOTAL BID	% OVER LOW BID	% OVER EST
0	ENGINEER'S ESTIMATE	$ 623,721.32	73.8452%	100.0000%
1	GEORGE & LYNCH, INC., 150 LAFFERTY LANE, DOVER, DE, 19901	$ 844,633.34	100.0000%	135.4184%
2	JJID INC, 100 JULIAN LANE, BEAR, DE, 19701	$ 989,017.37	117.0943%	158.5672%

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	AMOUNT	(2) JJID INC UNIT PRICE	AMOUNT
SECTION 0001 DOVER PARKING RECONFIGURATION								
0010 201000 CLEARING AND GRUBBING		LUMP	1000.00000	1000.00	11800.00000	11800.00	15000.00000	15000.00
0020 202000 EXCAVATION AND EMBANKMENT	1771.000	CY	16.00000	28336.00	26.50000	46931.50	28.66000	50756.86

TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	 AMOUNT	(2) JJID INC UNIT PRICE	 AMOUNT
0030 208000 EXCAVATION AND BACKFILLING FOR PIPE TRENCHES	100.000 CY	12.00000	1200.00	17.50000	1750.00	23.95000	2395.00

TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	 AMOUNT	(2) JJID INC UNIT PRICE	 AMOUNT
0040 209001 BORROW, TYPE A	138.000	CY	20.00000	2760.00	29.50000	4071.00	41.05000	5664.90
0050 211000 REMOVAL OF STRUCTURES AND OBSTRUCTIONS		LUMP	3000.00000	3000.00	6161.00000	6161.00	7953.34000	7953.34
0060 212000 UNDERCUT EXCAVATION	115.000	CY	16.00000	1840.00	28.22000	3245.30	29.19000	3356.85
0070 302008 GRADED AGGREGATE BASE COURSE, TYPE B, PATCHING	799.000	CY	58.00000	46342.00	94.84000	75777.16	124.05000	99115.95
0080 401754 FOG SEAL	4150.000	GAL	10.74845	44606.07	4.57000	18965.50	7.20000	29880.00
0090 401816 BITUMINOUS CONCRETE, SUPERPAVE, TYPE B, 160 GYRATIONS, PG 76-22	441.000	TON	85.00000	37485.00	133.10000	58697.10	171.27000	75530.07
0100 401821 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 64-22, PATCHING	307.000	TON	90.00000	27630.00	124.50000	38221.50	140.83000	43234.81
0110 401823 BITUMINOUS CONCRETE, SUPERPAVE, BITUMINOUS CONCRETE BASE COURSE, 160 GYRATIONS, PG 64-22, PATCHING	732.000	TON	80.00000	58560.00	88.00000	64416.00	132.26000	96814.32
0120 401833 BITUMINOUS CONCRETE, SUPERPAVE, TYPE C, 160 GYRATIONS, PG 76-22, (NON-CARBONATE STONE)	874.000	TON	92.00000	80408.00	104.00000	90896.00	132.59000	115883.66
0130 501004 PORTLAND CEMENT CONCRETE PAVEMENT, 10"	655.000	SY	65.00000	42575.00	112.00000	73360.00	99.93000	65454.15
0140 612021 REINFORCED CONCRETE PIPE, 15", CLASS IV	12.000	LF	65.00000	780.00	187.00000	2244.00	161.60000	1939.20
0150 701010 PORTLAND CEMENT CONCRETE CURB, TYPE 1-8	1400.000	LF	24.00000	33600.00	36.00000	50400.00	42.93000	60102.00
0160 701505 P.C.C. PARKING BUMPER	20.000	EACH	85.00000	1700.00	132.00000	2640.00	70.23000	1404.60
0170 705001 P.C.C. SIDEWALK, 4"	1383.000	SF	6.25000	8643.75	12.60000	17425.80	13.01000	17992.83
0180 705002 P.C.C. SIDEWALK, 6"	842.000	SF	8.00000	6736.00	14.80000	12461.60	16.32000	13741.44

TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	 AMOUNT	(2) JJID INC UNIT PRICE	 AMOUNT
0190 705007 SIDEWALK SURFACE DETECTABLE WARNING SYSTEM	273.000 SF	30.00000	8190.00	36.75000	10032.75	57.46000	15686.58

TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	 AMOUNT	(2) JJID INC UNIT PRICE	 AMOUNT
0200 705528 TEMPORARY CURB RAMP	2.000	EACH	1800.00000	3600.00	2630.00000	5260.00	2382.70000	4765.40
0210 708052 DRAINAGE INLET, 48" X 30"	1.000	EACH	3200.00000	3200.00	6370.00000	6370.00	2788.12000	2788.12
0220 710001 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	10.000	EACH	975.00000	9750.00	1260.00000	12600.00	1045.60000	10456.00
0230 715001 PERFORATED PIPE UNDERDRAINS, 6"	155.000	LF	15.00000	2325.00	24.15000	3743.25	28.37000	4397.35
0240 715500 UNDERDRAIN OUTLET PIPE, 6"	36.000	LF	20.00000	720.00	74.32000	2675.52	43.88000	1579.68
0250 716502 CONVERTING EXISTING CATCH BASIN TO DRAINAGE INLET	2.000	EACH	1800.00000	3600.00	2331.00000	4662.00	2794.12000	5588.24
0260 720578 BOLLARD, STEEL	2.000	EACH	1500.00000	3000.00	960.00000	1920.00	2299.40000	4598.80
0270 737523 PLANTINGS		LUMP	6954.00000	6954.00	4080.00000	4080.00	4972.28000	4972.28
0280 743000 MAINTENANCE OF TRAFFIC		LUMP	4000.00000	4000.00	34400.00000	34400.00	12500.00000	12500.00
0290 743004 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	25.000	EADY	75.00000	1875.00	83.94000	2098.50	71.82000	1795.50
0300 743006 PLASTIC DRUMS	2312.000	EADY	0.75000	1734.00	0.38000	878.56	0.28000	647.36
0310 743023 TEMPORARY BARRICADES, TYPE III	1330.000	LFDY	1.00000	1330.00	0.22000	292.60	0.28000	372.40
0320 743024 TEMPORARY WARNING SIGNS AND PLAQUES	465.000	EADY	2.10000	976.50	3.35000	1557.75	1.93000	897.45
0330 743051 FLAGGER, KENT COUNTY, STATE	480.000	HOUR	55.00000	26400.00	52.60000	25248.00	56.90000	27312.00
0340 743063 FLAGGER, KENT COUNTY, STATE, OVERTIME	60.000	HOUR	75.00000	4500.00	73.50000	4410.00	82.60000	4956.00
0350 748001 PAINTING OF WHITE OR YELLOW, 4" LINE	13199.000	LF	0.75000	9899.25	0.65000	8579.35	0.33000	4355.67
0360 748015 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND ALKYD-THERMOPLAST IC	835.000	SF	5.85000	4884.75	5.25000	4383.75	13.26000	11072.10

TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	 AMOUNT	(2) JJID INC UNIT PRICE	 AMOUNT
0370 748530 REMOVAL OF PAVEMENT STRIPING	430.000	SF	5.00000	2150.00	3.47000	1492.10	3.31000	1423.30
0380 748555 PREFORMED RETROREFLECTIVE THERMOPLASTIC PAVEMENT MARKINGS, HANDICAP SYMBOL	8.000	EACH	250.00000	2000.00	220.50000	1764.00	497.23000	3977.84
0390 749587 SUPPLY OF FLAT SHEET ALUMINUM SIGN PANEL TYPE XI REFLECTIVE SHEETING (SINGLE SIDED)	5.000	SF	175.00000	875.00	132.00000	660.00	44.20000	221.00
0400 749588 SUPPLY OF FLAT SHEET ALUMINUM SIGN PANEL TYPE XI REFLECTIVE SHEETING (DOUBLE SIDED)	2.000	SF	100.00000	200.00	160.00000	320.00	55.25000	110.50
0410 749687 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	6.000	EACH	75.00000	450.00	108.50000	651.00	110.50000	663.00
0420 749689 INSTALLATION OF 4" DIAMETER HOLE, GREATER THAN 6" DEPTH	8.000	EACH	95.00000	760.00	275.00000	2200.00	27.62000	220.96
0430 758000 REMOVAL OF EXISTING PORTLAND CEMENTCONCRETE PAVEMENT, CURB, SIDEWALK, ETC.	430.000	SY	25.00000	10750.00	18.70000	8041.00	20.28000	8720.40
0440 760006 PAVEMENT - MILLING, HOT-MIX, 2" DEPTH	9032.000	SY	2.50000	22580.00	3.48000	31431.36	4.86000	43895.52
0450 762001 SAW CUTTING, BITUMINOUS CONCRETE	3958.000	LF	1.50000	5937.00	3.15000	12467.70	1.66000	6570.28
0460 762002 SAW CUTTING, CONCRETE, FULL DEPTH	172.000	LF	8.00000	1376.00	7.35000	1264.20	11.05000	1900.60
0470 763000 INITIAL EXPENSE		LUMP	28876.00000	28876.00	55200.00000	55200.00	61300.00000	61300.00
0480 763501 CONSTRUCTION ENGINEERING		LUMP	17325.00000	17325.00	5520.00000	5520.00	20000.00000	20000.00
0490 905001 SILT FENCE	200.000	LF	2.50000	500.00	3.04000	608.00	2.21000	442.00
0500 905004 INLET SEDIMENT CONTROL, DRAINAGE INLET	4.000	EACH	150.00000	600.00	217.00000	868.00	183.62000	734.48
0510 905005 INLET SEDIMENT CONTROL, CURB INLET	8.000	EACH	150.00000	1200.00	230.00000	1840.00	195.47000	1563.76

TABULATION OF BIDS
FINAL

CONTRACT TITLE : DOVER FACILITY BUS PARKING RECONFIGURATION
CALL ORDER : 003 CONTRACT ID : T201253106.01 COUNTIES : KENT
LETTING DATE : 02/16/16 DISTRICT : G3

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) GEORGE & LYNCH INC UNIT PRICE	 AMOUNT	(2) JJID INC UNIT PRICE	 AMOUNT
0520 908004 TOPSOIL, 6" DEPTH	667.000 SY	5.00000	3335.00	9.52000	6349.84	16.80000	11205.60
0530 908014 PERMANENT GRASS SEEDING, DRY GROUND	667.000 SY	1.00000	667.00	1.95000	1300.65	1.66000	1107.22
SECTION TOTALS		$	623,721.32	$	844,633.34	$	989,017.37
CONTRACT TOTALS		$	623,721.32	$	844,633.34	$	989,017.37
DBE GOALS		6	%	6	%	6	%