



Vendor Ranking

Page 1 of 1

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD**Call Order:** 007**Contract ID:** T201407106.02**Counties:** NEW CASTLE**Letting Date:** January 20, 2026**District(s):** G1**Project(s):** BFP-N1235(1)**Federal Aid No:** BFP-N1235(1)**Contract Time:** 169 CALENDAR DAYS**Contract Description:** REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD -

This project involves the replacement of one existing corrugated metal pipe with a precast concrete frame. Additional work includes minor reconstruction of the approach roadway, installation of guardrail as needed, and placement of riprap in the stream to prevent scour. The work will be performed under detour with roadway closure. There is significant corrosion at the waterline with 100% section loss at several locations throughout the pipes. The existing pipes are hydraulically inadequate and have caused flooding of adjacent property owners. This issue was brought to the attention of the Bridge Section, which inspected and inventoried the existing structure and then programmed the bridge for replacement. Follow other incidental construction in accordance with the location, notes and details shown on the plans, and as directed by the Engineer.

Set-Aside:**Vendor Ranking:** Contract was awarded on 02/16/26 to vendor A-DEL CONSTRUCTION COMPANY, INC.

Rank	Vendor ID/Name	Total Bid	Percent Of Low Bid	Percent Of Estimate
1	A-DEL CONSTRUCTION COMPANY, INC.	\$1,248,753.00	100.00%	98.51%
0	Engineer's Estimate	\$1,267,603.00	101.51%	100.00%
2	RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	\$1,280,661.56	102.56%	101.03%
3	MUMFORD & MILLER CONCRETE, INC.	\$1,316,416.25	105.42%	103.85%
4	GREGGO & FERRARA, INCORPORATED	\$1,450,735.50	116.17%	114.45%
5	EASTERN HIGHWAY SPECIALISTS, INC.	\$1,513,773.50	121.22%	119.42%



Delaware Department of Transportation

Tabulation of Bids

Page 1 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0010	201000	(1)	17,500.00000	17,500.00	8,500.00000	8,500.00	20,000.00000	20,000.00
CLEARING AND GRUBBING		LS						
0020	202000	624.000	50.00000	31,200.00	15.00000	9,360.00	36.70000	22,900.80
EXCAVATION AND EMBANKMENT		CY						
0030	207001	600.000	55.00000	33,000.00	15.00000	9,000.00	23.30000	13,980.00
PIPE, CULVERT, AND STRUCTURE BACKFILLING		CY						
0040	207002	1,100.000	30.00000	33,000.00	65.00000	71,500.00	30.50000	33,550.00
PIPE, CULVERT, AND STRUCTURE EXCAVATION		CY						
0050	207021	770.000	30.00000	23,100.00	15.00000	11,550.00	28.00000	21,560.00
STRUCTURAL BACKFILL, (BORROW TYPE C)		CY						
0060	209004	120.000	60.00000	7,200.00	44.50000	5,340.00	28.00000	3,360.00
BORROW, TYPE C		CY						
0070	209012	412.000	25.00000	10,300.00	20.00000	8,240.00	16.95000	6,983.40
BORROW, TYPE C, PROVIDING ONLY		TON						



Delaware Department of Transportation

Tabulation of Bids

Page 2 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0080	211000	(1)	30,000.00000	30,000.00	22,500.00000	22,500.00	3,230.00000	3,230.00
REMOVAL OF STRUCTURES AND OBSTRUCTIONS		LS						
0090	211001	19.000	25.00000	475.00	100.00000	1,900.00	70.00000	1,330.00
REMOVAL OF PORTLAND CEMENT CONCRETE PAVEMENT, CURB AND SIDEWALK		SY						
0100	211508	(1)	15,000.00000	15,000.00	4,500.00000	4,500.00	5,348.00000	5,348.00
VIDEO RECORDING BUILDINGS		LS						
0110	301001	380.000	80.00000	30,400.00	60.00000	22,800.00	90.00000	34,200.00
GABC		CY						
0120	301002	60.000	6.00000	360.00	65.00000	3,900.00	136.00000	8,160.00
GABC, PATCHING		CY						
0130	302002	130.000	70.00000	9,100.00	60.00000	7,800.00	99.00000	12,870.00
DELAWARE NO. 3 STONE		TON						
0140	302005	348.000	75.00000	26,100.00	45.00000	15,660.00	73.00000	25,404.00
DELAWARE NO. 57 STONE		TON						



Delaware Department of Transportation

Tabulation of Bids

Page 3 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0150	401005	210.000	145.00000	30,450.00	120.00000	25,200.00	157.00000	32,970.00
SUPERPAVE TYPE C, PG 64-22 (CARBONATE STONE)		TON						
0160	401014	130.000	150.00000	19,500.00	115.00000	14,950.00	138.00000	17,940.00
SUPERPAVE TYPE B, PG 64-22		TON						
0170	401030	5.000	135.00000	675.00	550.00000	2,750.00	225.00000	1,125.00
SUPERPAVE TYPE B, PG 64- 22, PATCHING		TON						
0180	401506	31.000	90.00000	2,790.00	190.00000	5,890.00	234.92000	7,282.52
SPEED HUMP		LF						
0190	601032	69.000	90.00000	6,210.00	60.00000	4,140.00	113.00000	7,797.00
REINFORCED CONCRETE PIPE, 15", CLASS IV		LF						
0200	601033	165.000	100.00000	16,500.00	65.00000	10,725.00	120.00000	19,800.00
REINFORCED CONCRETE PIPE, 18", CLASS IV		LF						
0210	601191	65.000	75.00000	4,875.00	28.00000	1,820.00	60.00000	3,900.00
PVC PIPE, 6"		LF						



Delaware Department of Transportation

Tabulation of Bids

Page 4 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0220	602003	1.000	4,000.00000	4,000.00	5,600.00000	5,600.00	4,740.00000	4,740.00
	DRAINAGE INLET, 34" X 24"	EACH						
0230	602004	1.000	4,250.00000	4,250.00	5,400.00000	5,400.00	5,810.00000	5,810.00
	DRAINAGE INLET, 48" X 30"	EACH						
0240	602009	2.000	5,500.00000	11,000.00	8,050.00000	16,100.00	7,057.00000	14,114.00
	DRAINAGE INLET, 72" X 24"	EACH						
0250	602010	1.000	5,000.00000	5,000.00	8,675.00000	8,675.00	7,931.00000	7,931.00
	DRAINAGE INLET, 72" X 48"	EACH						
0260	612001	310.000	1,300.00000	403,000.00	1,475.00000	457,250.00	1,327.00000	411,370.00
	PRECAST CONCRETE RIGID FRAME	CY						
0270	612010	26.000	1,700.00000	44,200.00	1,550.00000	40,300.00	1,523.00000	39,598.00
	PRECAST CONCRETE RETAINING WALL	CY						
0280	612505	4,760.000	13.00000	61,880.00	18.00000	85,680.00	22.00000	104,720.00
	ARTICULATED PRECAST CONCRETE BLOCKS	SF						



Delaware Department of Transportation

Tabulation of Bids

Page 5 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description		Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 No Category		Cat Alt Set:		Cat Alt Member:		LCC:	
0290 701018	399.000	60.00000	23,940.00	48.00000	19,152.00	54.00000	21,546.00
I.PCC CURB AND GUTTER, TYPE 1-8							
	LF						
0300 705001	174.000	5.45977	950.00	19.50000	3,393.00	15.00000	2,610.00
PCC SIDEWALK, 4"							
	SF						
0310 706000	10.000	300.00000	3,000.00	120.00000	1,200.00	250.00000	2,500.00
MONUMENT							
	EACH						
0320 707021	173.000	105.00000	18,165.00	112.50000	19,462.50	55.00000	9,515.00
CHANNEL BED FILL							
	CY						
0330 708001	718.000	5.00000	3,590.00	1.25000	897.50	1.25000	897.50
GEOTEXTILES, STABILIZATION							
	SY						
0340 708003	529.000	7.00000	3,703.00	7.50000	3,967.50	1.25000	661.25
GEOTEXTILES, RIPRAP							
	SY						
0350 710002	1.000	750.00000	750.00	700.00000	700.00	125.00000	125.00
ADJUST WATER VALVE BOXES							
	EACH						
0360 711002	(1)	75,000.00000	75,000.00	105,000.00000	105,000.00	90,000.00000	90,000.00
SANITARY SEWER SYSTEM							
	LS						



Delaware Department of Transportation

Tabulation of Bids

Page 6 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0370	711500	1.000	1,300.00000	1,300.00	1,600.00000	1,600.00	1,270.00000	1,270.00
ADJUST AND REPAIR EXISTING SANITARY MANHOLE		EACH						
0380	727006	10.000	332.00000	3,320.00	10.00000	100.00	15.00000	150.00
TEMPORARY CONSTRUCTION FENCE		LF						
0390	727030	150.000	50.00000	7,500.00	45.00000	6,750.00	55.65000	8,347.50
FENCE RELOCATION		LF						
0400	760010	719.000	5.00000	3,595.00	4.50000	3,235.50	14.61000	10,504.59
PAVEMENT MILLING, BITUMINOUS CONCRETE PAVEMENT		SYIN						
0410	762000	90.000	3.00000	270.00	5.00000	450.00	2.00000	180.00
SAW CUTTING, BITUMINOUS CONCRETE		LF						
0420	762001	190.000	20.00000	3,800.00	7.00000	1,330.00	1.00000	190.00
SAW CUTTING, CONCRETE, FULL DEPTH		LF						



Delaware Department of Transportation

Tabulation of Bids

Page 7 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0430	763000	(1)	40,000.00000	40,000.00	40,000.00000	40,000.00	62,000.00000	62,000.00
INITIAL EXPENSE/DE-MOBILIZATION		LS						
0440	763001	(1)	12,000.00000	12,000.00	5,000.00000	5,000.00	1,000.00000	1,000.00
BASELINE SCHEDULE TYPE 1		LS						
0450	763002	3.000	700.00000	2,100.00	750.00000	2,250.00	100.00000	300.00
MONTHLY UPDATE SCHEDULE TYPE 1		EAMO						
0460	763501	(1)	30,000.00000	30,000.00	15,500.00000	15,500.00	3,685.00000	3,685.00
CONSTRUCTION ENGINEERING		LS						
0470	763597	150.000	24.00000	3,600.00	50.00000	7,500.00	1.00000	150.00
UTILITY CONSTRUCTION ENGINEERING		HOOR						
0480	763598	4.000	5,000.00000	20,000.00	3,000.00000	12,000.00	3,500.00000	14,000.00
FIELD OFFICE, SPECIAL I		EAMO						
0490	801500	(1)	30,000.00000	30,000.00	18,000.00000	18,000.00	19,500.00000	19,500.00
MAINTENANCE OF TRAFFIC, ALL INCLUSIVE		LS						



Delaware Department of Transportation

Tabulation of Bids

Page 8 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0500	811001	40.000	75.00000	3,000.00	87.50000	3,500.00	65.00000	2,600.00
FLAGGER, NEW CASTLE COUNTY		HOUR						
0510	811013	10.000	100.00000	1,000.00	87.50000	875.00	97.50000	975.00
FLAGGER, NEW CASTLE COUNTY, OVERTIME		HOUR						
0520	819011	1.000	35.00000	35.00	215.00000	215.00	160.00000	160.00
GALVANIZED TELESOPING STEEL SIGN POSTS, 12' X 2", COMPLETE W/ BASEPOSTS AND HARDWARE		EACH						
0530	819018	2.000	115.00000	230.00	100.00000	200.00	100.00000	200.00
INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST		EACH						
0540	905001	340.000	5.00000	1,700.00	5.00000	1,700.00	7.00000	2,380.00
SILT FENCE		LF						
0550	905005	9.000	250.00000	2,250.00	160.00000	1,440.00	129.00000	1,161.00
INLET SEDIMENT CONTROL, CURB INLET		EACH						



Delaware Department of Transportation

Tabulation of Bids

Page 9 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0560	906002	1.000	900.00000	900.00	2,000.00000	2,000.00	150.00000	150.00
DEWATERING BAG		EACH						
0570	906003	1.000	2,000.00000	2,000.00	3,500.00000	3,500.00	5,000.00000	5,000.00
SUMP PIT		EACH						
0580	908004	2,100.000	10.00000	21,000.00	12.50000	26,250.00	10.40000	21,840.00
TOPSOIL, 6" DEPTH		SY						
0590	908016	2,100.000	2.00000	4,200.00	4.75000	9,975.00	2.50000	5,250.00
PERMANENT GRASS SEEDING, SUBDIVISION		SY						
0600	908019	12.000	15.00000	180.00	15.00000	180.00	15.00000	180.00
PERMANENT GRASS SEEDING, STREAMBANK		SY						
0610	908020	12.000	15.00000	180.00	20.00000	240.00	5.00000	60.00
EROSION CONTROL BLANKET MULCH		SY						
0620	909005	(1)	60,000.00000	60,000.00	42,500.00000	42,500.00	99,000.00000	99,000.00
STREAM DIVERSION		LS						
0630	909006	4.000	820.00000	3,280.00	415.00000	1,660.00	150.00000	600.00
STILLING WELL		CY						

**Contract Title:** REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD**Contract ID:** T201407106.02**Counties:** NEW CASTLE

Line No / Item ID Item Description		Engineer's Estimate		(1) A-DEL CONSTRUCTION COMPANY, INC.		(2) RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	
Alt Set / Alt Member	Quantity and Units	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
Section Totals:			\$1,267,603.00		\$1,248,753.00		\$1,280,661.56
Life Cycle Costs:							
Section Total with LCC:			\$1,267,603.00		\$1,248,753.00		\$1,280,661.56
Contract Item Totals			\$1,267,603.00		\$1,248,753.00		\$1,280,661.56
Contract Time Totals			\$0.00				
Contract Life Cycle Costs Totals			\$0.00		\$0.00		\$0.00
Contract Grand Totals			\$1,267,603.00		\$1,248,753.00		1,280,661.56

() indicates item is bid as Lump Sum



Delaware Department of Transportation

Tabulation of Bids

Page 11 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0010	201000	(1)	10,000.00000	10,000.00	30,000.00000	30,000.00	15,000.00000	15,000.00
CLEARING AND GRUBBING		LS						
0020	202000	624.000	17.00000	10,608.00	40.00000	24,960.00	40.00000	24,960.00
EXCAVATION AND EMBANKMENT		CY						
0030	207001	600.000	10.00000	6,000.00	23.00000	13,800.00	26.00000	15,600.00
PIPE, CULVERT, AND STRUCTURE BACKFILLING		CY						
0040	207002	1,100.000	17.00000	18,700.00	36.00000	39,600.00	42.00000	46,200.00
PIPE, CULVERT, AND STRUCTURE EXCAVATION		CY						
0050	207021	770.000	31.00000	23,870.00	30.00000	23,100.00	26.00000	20,020.00
STRUCTURAL BACKFILL, (BORROW TYPE C)		CY						
0060	209004	120.000	47.00000	5,640.00	54.00000	6,480.00	48.00000	5,760.00
BORROW, TYPE C		CY						
0070	209012	412.000	31.00000	12,772.00	20.00000	8,240.00	16.00000	6,592.00
BORROW, TYPE C, PROVIDING ONLY		TON						



Delaware Department of Transportation

Tabulation of Bids

Page 12 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0080	211000	(1)	70,000.00000	70,000.00	30,000.00000	30,000.00	21,000.00000	21,000.00
REMOVAL OF STRUCTURES AND OBSTRUCTIONS		LS						
0090	211001	19.000	30.00000	570.00	30.00000	570.00	143.00000	2,717.00
REMOVAL OF PORTLAND CEMENT CONCRETE PAVEMENT, CURB AND SIDEWALK		SY						
0100	211508	(1)	13,500.00000	13,500.00	6,500.00000	6,500.00	5,600.00000	5,600.00
VIDEO RECORDING BUILDINGS		LS						
0110	301001	380.000	74.75000	28,405.00	56.00000	21,280.00	73.00000	27,740.00
GABC		CY						
0120	301002	60.000	87.25000	5,235.00	75.00000	4,500.00	74.00000	4,440.00
GABC, PATCHING		CY						
0130	302002	130.000	58.75000	7,637.50	50.00000	6,500.00	85.00000	11,050.00
DELAWARE NO. 3 STONE		TON						
0140	302005	348.000	58.75000	20,445.00	50.00000	17,400.00	85.00000	29,580.00
DELAWARE NO. 57 STONE		TON						



Delaware Department of Transportation

Tabulation of Bids

Page 13 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 No Category			Cat Alt Set:		Cat Alt Member:		LCC:	
0150 401005	210.000		139.00000	29,190.00	160.00000	33,600.00	174.00000	36,540.00
SUPERPAVE TYPE C, PG 64-22 (CARBONATE STONE)	TON							
0160 401014	130.000		165.00000	21,450.00	158.00000	20,540.00	186.00000	24,180.00
SUPERPAVE TYPE B, PG 64-22	TON							
0170 401030	5.000		189.00000	945.00	200.00000	1,000.00	539.00000	2,695.00
SUPERPAVE TYPE B, PG 64- 22, PATCHING	TON							
0180 401506	31.000		188.00000	5,828.00	110.00000	3,410.00	234.00000	7,254.00
SPEED HUMP	LF							
0190 601032	69.000		92.00000	6,348.00	58.00000	4,002.00	85.00000	5,865.00
REINFORCED CONCRETE PIPE, 15", CLASS IV	LF							
0200 601033	165.000		100.00000	16,500.00	64.00000	10,560.00	89.00000	14,685.00
REINFORCED CONCRETE PIPE, 18", CLASS IV	LF							
0210 601191	65.000		40.00000	2,600.00	34.00000	2,210.00	90.00000	5,850.00
PVC PIPE, 6"	LF							
0220 602003	1.000		4,450.00000	4,450.00	2,700.00000	2,700.00	4,200.00000	4,200.00
DRAINAGE INLET, 34" X 24"	EACH							



Delaware Department of Transportation

Tabulation of Bids

Page 14 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 No Category			Cat Alt Set:		Cat Alt Member:		LCC:	
0230 602004	1.000		5,200.00000	5,200.00	3,800.00000	3,800.00	5,600.00000	5,600.00
DRAINAGE INLET, 48" X 30"	EACH							
0240 602009	2.000		6,320.00000	12,640.00	5,800.00000	11,600.00	6,500.00000	13,000.00
DRAINAGE INLET, 72" X 24"	EACH							
0250 602010	1.000		6,885.00000	6,885.00	6,200.00000	6,200.00	7,000.00000	7,000.00
DRAINAGE INLET, 72" X 48"	EACH							
0260 612001	310.000		1,340.00000	415,400.00	1,000.00000	310,000.00	1,600.00000	496,000.00
PRECAST CONCRETE RIGID FRAME	CY							
0270 612010	26.000		1,500.00000	39,000.00	5,600.00000	145,600.00	285.00000	7,410.00
PRECAST CONCRETE RETAINING WALL	CY							
0280 612505	4,760.000		24.40000	116,144.00	48.00000	228,480.00	23.00000	109,480.00
ARTICULATED PRECAST CONCRETE BLOCKS	SF							
0290 701018	399.000		48.75000	19,451.25	84.00000	33,516.00	35.00000	13,965.00
I.PCC CURB AND GUTTER, TYPE 1-8	LF							
0300 705001	174.000		19.00000	3,306.00	36.00000	6,264.00	15.00000	2,610.00
PCC SIDEWALK, 4"	SF							



Delaware Department of Transportation

Tabulation of Bids

Page 15 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0310	706000	10.000	350.00000	3,500.00	280.00000	2,800.00	500.00000	5,000.00
MONUMENT		EACH						
0320	707021	173.000	77.00000	13,321.00	140.00000	24,220.00	150.00000	25,950.00
CHANNEL BED FILL		CY						
0330	708001	718.000	4.00000	2,872.00	4.00000	2,872.00	4.50000	3,231.00
GEOTEXTILES, STABILIZATION		SY						
0340	708003	529.000	4.00000	2,116.00	4.50000	2,380.50	4.50000	2,380.50
GEOTEXTILES, RIPRAP		SY						
0350	710002	1.000	750.00000	750.00	550.00000	550.00	600.00000	600.00
ADJUST WATER VALVE BOXES		EACH						
0360	711002	(1)	92,500.00000	92,500.00	178,000.00000	178,000.00	212,000.00000	212,000.00
SANITARY SEWER SYSTEM		LS						
0370	711500	1.000	1,125.00000	1,125.00	2,150.00000	2,150.00	1,200.00000	1,200.00
ADJUST AND REPAIR EXISTING SANITARY MANHOLE		EACH						
0380	727006	10.000	80.00000	800.00	100.00000	1,000.00	15.00000	150.00
TEMPORARY CONSTRUCTION FENCE		LF						



Delaware Department of Transportation

Tabulation of Bids

Page 16 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 No Category			Cat Alt Set:		Cat Alt Member:		LCC:	
0390 727030	150.000		53.50000	8,025.00	60.00000	9,000.00	32.00000	4,800.00
FENCE RELOCATION	LF							
0400 760010	719.000		7.50000	5,392.50	4.00000	2,876.00	12.00000	8,628.00
PAVEMENT MILLING, BITUMINOUS CONCRETE PAVEMENT	SYIN							
0410 762000	90.000		5.00000	450.00	3.50000	315.00	6.60000	594.00
SAW CUTTING, BITUMINOUS CONCRETE	LF							
0420 762001	190.000		6.00000	1,140.00	7.00000	1,330.00	16.50000	3,135.00
SAW CUTTING, CONCRETE, FULL DEPTH	LF							
0430 763000	(1)		48,000.00000	48,000.00	10,000.00000	10,000.00	65,000.00000	65,000.00
INITIAL EXPENSE/DE- MOBILIZATION	LS							
0440 763001	(1)		850.00000	850.00	2,250.00000	2,250.00	3,500.00000	3,500.00
BASELINE SCHEDULE TYPE 1	LS							
0450 763002	3.000		85.00000	255.00	220.00000	660.00	704.00000	2,112.00
MONTHLY UPDATE SCHEDULE TYPE 1	EAMO							



Delaware Department of Transportation

Tabulation of Bids

Page 17 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description		(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units	Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 No Category		Cat Alt Set:		Cat Alt Member:		LCC:	
0460 763501	(1)	42,400.00000	42,400.00	18,000.00000	18,000.00	7,500.00000	7,500.00
CONSTRUCTION ENGINEERING	LS						
0470 763597	150.000	169.00000	25,350.00	270.00000	40,500.00	147.00000	22,050.00
UTILITY CONSTRUCTION ENGINEERING	HOURL						
0480 763598	4.000	5,000.00000	20,000.00	2,000.00000	8,000.00	3,100.00000	12,400.00
FIELD OFFICE, SPECIAL I	EAMO						
0490 801500	(1)	11,250.00000	11,250.00	10,000.00000	10,000.00	24,000.00000	24,000.00
MAINTENANCE OF TRAFFIC, ALL INCLUSIVE	LS						
0500 811001	40.000	88.00000	3,520.00	88.00000	3,520.00	98.50000	3,940.00
FLAGGER, NEW CASTLE COUNTY	HOURL						
0510 811013	10.000	100.00000	1,000.00	130.00000	1,300.00	148.00000	1,480.00
FLAGGER, NEW CASTLE COUNTY, OVERTIME	HOURL						
0520 819011	1.000	200.00000	200.00	200.00000	200.00	188.00000	188.00
GALVANIZED TELESOPING STEEL SIGN POSTS, 12' X 2", COMPLETE W/ BASEPOSTS AND HARDWARE	EACH						



Delaware Department of Transportation

Tabulation of Bids

Page 18 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 No Category			Cat Alt Set:		Cat Alt Member:		LCC:	
0530 819018	2.000		100.00000	200.00	220.00000	440.00	117.00000	234.00
INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST		EACH						
0540 905001	340.000		3.00000	1,020.00	4.00000	1,360.00	5.10000	1,734.00
SILT FENCE		LF						
0550 905005	9.000		150.00000	1,350.00	260.00000	2,340.00	542.00000	4,878.00
INLET SEDIMENT CONTROL, CURB INLET		EACH						
0560 906002	1.000		200.00000	200.00	300.00000	300.00	1,500.00000	1,500.00
DEWATERING BAG		EACH						
0570 906003	1.000		850.00000	850.00	1,900.00000	1,900.00	1,200.00000	1,200.00
SUMP PIT		EACH						
0580 908004	2,100.000		8.00000	16,800.00	12.00000	25,200.00	14.00000	29,400.00
TOPSOIL, 6" DEPTH		SY						
0590 908016	2,100.000		2.00000	4,200.00	1.00000	2,100.00	1.40000	2,940.00
PERMANENT GRASS SEEDING, SUBDIVISION		SY						



Delaware Department of Transportation

Tabulation of Bids

Page 19 of 20

AASHTOWare Project

Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD **Contract ID:** T201407106.02 **Counties:** NEW CASTLE

Line No / Item ID Item Description			(3) MUMFORD & MILLER CONCRETE, INC.		(4) GREGGO & FERRARA, INCORPORATED		(5) EASTERN HIGHWAY SPECIALISTS, INC.	
Alt Set / Alt Member	Quantity and Units		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION:	0001	No Category	Cat Alt Set:		Cat Alt Member:		LCC:	
0600	908019	12.000	20.00000	240.00	10.00000	120.00	97.50000	1,170.00
PERMANENT GRASS SEEDING, STREAMBANK								
0610	908020	12.000	10.00000	120.00	20.00000	240.00	97.50000	1,170.00
EROSION CONTROL BLANKET MULCH								
0620	909005	(1)	67,000.00000	67,000.00	20,000.00000	20,000.00	65,000.00000	65,000.00
STREAM DIVERSION								
0630	909006	4.000	225.00000	900.00	4,600.00000	18,400.00	529.00000	2,116.00
STILLING WELL								
Section Totals:				\$1,316,416.25		\$1,450,735.50		\$1,513,773.50
Life Cycle Costs:								
Section Total with LCC:				\$1,316,416.25		\$1,450,735.50		\$1,513,773.50
Contract Item Totals				\$1,316,416.25		\$1,450,735.50		\$1,513,773.50
Contract Time Totals								
Contract Life Cycle Costs Totals				\$0.00		\$0.00		\$0.00
Contract Grand Totals				\$1,316,416.25		\$1,450,735.50		1,513,773.50

() indicates item is bid as Lump Sum



Contract Title: REPLACEMENT OF BRIDGE 1-185 ON OAK RIDGE ROAD

Contract ID: T201407106.02

Counties: NEW CASTLE