TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9
STATE/FEDERAL AID NO: EBHN-S014(13) CONTRACT TIME : 327 CALENDAR DAYS
CONTRACT DESCRIPTION : PROJECT(S) : EBHN-S014(13)
THE BRIDGES NEED TO BE REPAIRED DUE TO SIGNIFICANT
DELAMINATION OF THE DECK, DAMAGE TO THE APPROACH SLABS, AND
MISALIGNMENT OF THE GIRDERS. THIS PROJECT INVOLVES DECK
REPLACEMENT AND SUBSTRUCTURE WORK. THE DECK REPLACEMENT WILL
BE PERFORMED UNDER PHASED CONSTRUCTION, IMPLEMENTING A CROSS
OVER AND CONTRA-FLOW TO CLOSE ONE BRIDGE AT A TIME.
ADDITIONAL WORK INCLUDES REPLACING THE APPROACH SLABS AND
CORRECTING THE VERTICAL ALIGNMENT, REPLACING THE JOINTS,
REPAIRING CONCRETE SPALLS THROUGHOUT THE SUBSTRUCTURE,
STRENGTHENING THE CONCRETE PIERS AND SEALING THE CONCRETE
ABUTMENTS AND PIERS. THE NORTH AND SOUTH CANAL EMBANKMENTS
WILL BE STABILIZED WITH R-5 RIPRAP AND GEOTEXTILE.
CORRUGATED METAL PIPES THAT OUTFALL IN THE CANAL NORTH AND
SOUTH OF THE BRIDGE WILL BE REPLACED WITH REINFORCED
CONCRETE PIPES.

SET-ASIDE :

VENDOR RANKING : Contract was awarded on 06/10/19 to vendor KIEWIT INFRASTRUCTURE SOUTH COMPANY

RANK	VENDOR NAME	TOTAL BID	% OVER LOW BID	% OVER EST
0	ENGINEER'S ESTIMATE	$ 15,864,738.00	100.0000%	100.0000%
1	KIEWIT INFRASTRUCTURE SOUTH COMPANY, 7250 PARKWAY DR, HANOVER, MD, 21076	$ 15,864,737.23	100.0000%	100.0000%

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
SECTION 0001 REHABILATION OF BR 3-150								
0010 201000 CLEARING AND GRUBBING		LUMP	130000.00000	130000.00	130000.00000	130000.00		
0020 202000 EXCAVATION AND EMBANKMENT	1973.000	CY	63.50000	125285.50	63.50000	125285.50		
0030 207000 STRUCTURAL EXCAVATION	70.000	CY	70.00000	4900.00	70.00000	4900.00		
0040 207021 STRUCTURAL BACKFILL, (BORROW TYPE C)	96.000	CY	180.00000	17280.00	180.00000	17280.00		
0050 209002 BORROW, TYPE B	12.000	CY	180.00000	2160.00	180.00000	2160.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

		(0) ENGINEER'S ESTIMATE		(1) KIEWIT INFRASTRUCTURE SOUTH		( )	
LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT	UNIT PRICE	AMOUNT
0060 209005 FURNISHING BORROW, TYPE C FOR PIPE AND UTILITY TRENCH BACKFILL	1815.000 CY	52.00000	94380.00	52.00000	94380.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0070 211000 REMOVAL OF STRUCTURES AND OBSTRUCTIONS		LUMP	2862000.00000	2862000.00	2862000.00000	2862000.00		
0080 211001 REMOVAL OF PORTLAND CEMENT CONCRETE PAVEMENT, CURB AND SIDEWALK	2456.000	SY	46.00000	112976.00	46.00000	112976.00		
0090 211002 REMOVAL OF STRUCTURES AND OBSTRUCTIONS (GUARDRAIL)	2578.000	LF	23.10000	59551.80	23.10000	59551.80		
0100 301001 GRADED AGGREGATE BASE COURSE, TYPE B	1506.000	CY	184.00000	277104.00	184.00000	277104.00		
0110 302002 DELAWARE NO. 3 STONE	740.000	TON	133.00000	98420.00	133.00000	98420.00		
0120 302005 DELAWARE NO. 57 STONE	169.000	TON	132.00000	22308.00	132.00000	22308.00		
0130 401014 SUPERPAVE TYPE B, PG 64-22	2262.000	TON	108.00000	244296.00	108.00000	244296.00		
0140 401016 SUPERPAVE TYPE B, PG 76-22	49.000	TON	188.00000	9212.00	188.00000	9212.00		
0150 401021 SUPERPAVE TYPE BCBC, PG 64-22	98.000	TON	125.00000	12250.00	125.00000	12250.00		
0160 401037 SUPERPAVE TYPE B, PG 64-22, WEDGE	811.000	TON	98.00000	79478.00	98.00000	79478.00		
0170 401046 SUPERPAVE TYPE C, PG 76-22 (NON-CARBONATE STONE)	1983.000	TON	148.00000	293484.00	148.00000	293484.00		
0180 503001 PATCHING PORTLAND CEMENT CONCRETE PAVEMENT, 6' TO 15', TYPE A	257.000	SY	196.00000	50372.00	196.00000	50372.00		
0190 503006 DOWEL BARS	460.000	EACH	26.91000	12378.60	26.91220	12379.61		
0200 601032 REINFORCED CONCRETE PIPE, 15", CLASS IV	272.000	LF	234.00000	63648.00	234.00000	63648.00		
0210 601033 REINFORCED CONCRETE PIPE, 18", CLASS IV	191.000	LF	292.00000	55772.00	292.00000	55772.00		
0220 601039 REINFORCED CONCRETE PIPE, 36", CLASS IV	72.000	LF	521.00000	37512.00	521.00000	37512.00		
0230 601040 REINFORCED CONCRETE PIPE, 42", CLASS IV	158.000	LF	646.00000	102068.00	646.00000	102068.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0240 602003 DRAINAGE INLET, 34" X 24"	8.000	EACH	11100.00000	88800.00	11100.00000	88800.00		
0250 602004 DRAINAGE INLET, 48" X 30"	1.000	EACH	16000.00000	16000.00	16000.00000	16000.00		
0260 602010 DRAINAGE INLET, 72" X 48"	1.000	EACH	28000.00000	28000.00	28000.00000	28000.00		
0270 602011 DRAINAGE INLET, 72" X 72"	1.000	EACH	34800.00000	34800.00	34800.00000	34800.00		
0280 602130 ADJUSTING AND REPAIRING EXISTING DRAINAGE INLET	14.000	EACH	2400.00000	33600.00	2400.00000	33600.00		
0290 604000 JACKING BRIDGE		LUMP	843000.00000	843000.00	843000.00000	843000.00		
0300 604001 PROTECTIVE SHIELD		LUMP	883000.00000	883000.00	883000.00000	883000.00		
0310 604002 COFFERDAMS		LUMP	195000.00000	195000.00	195000.00000	195000.00		
0320 610002 PORTLAND CEMENT CONCRETE MASONRY, ABUTMENT ABOVE FOOTING, CLASS A	68.000	CY	3008.00000	204544.00	3008.00000	204544.00		
0330 610005 PORTLAND CEMENT CONCRETE MASONRY, SUBSTRUCTURE, CLASS A	20.000	CY	2805.00000	56100.00	2805.00000	56100.00		
0340 610008 PORTLAND CEMENT CONCRETE MASONRY, PARAPET, CLASS A	258.000	CY	1200.00000	309600.00	1200.00000	309600.00		
0350 610017 PORTLAND CEMENT CONCRETE MASONRY, SUPERSTRUCTURE, CLASS D	1257.000	CY	1530.00000	1923210.00	1530.00000	1923210.00		
0360 610018 PORTLAND CEMENT CONCRETE MASONRY, APPROACH SLAB, CLASS D	326.000	CY	654.00000	213204.00	654.00000	213204.00		
0370 610507 REHABILITATION OF CONCRETE STRUCTURE	21.000	CF	8500.00000	178500.00	8500.00000	178500.00		
0380 611001 BAR REINFORCEMENT, EPOXY COATED	343800.000	LB	1.48000	508824.00	1.48000	508824.00		
0390 613000 EPOXY CONCRETE SEALER	2708.000	SF	9.20000	24913.60	9.20000	24913.60		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0400 613001 SILICONE-BASED ACRYLIC CONCRETE SEALER	39752.000	SF	9.90000	393544.80	9.90000	393544.80		
0410 613003 HIGH MOLECULAR WEIGHT METHACRYLATE CONCRETE SEALER	39846.000	SF	2.00000	79692.00	2.00000	79692.00		
0420 613500 CONCRETE ACRYLIC PRIMER, SEALER, AND TEXTURED TOPCOAT	7248.000	SF	10.00000	72480.00	10.00000	72480.00		
0430 615001 STEEL STRUCTURES		LUMP	461000.00000	461000.00	461000.00000	461000.00		
0440 615510 NAVIGATION LIGHTS FOR FIXED BRIDGES		LUMP	29000.00000	29000.00	29000.00000	29000.00		
0450 623000 ELASTOMERIC BEARINGS	84.000	EACH	2000.00000	168000.00	2000.00000	168000.00		
0460 623003 REPLACE ANCHOR BOLTS	112.000	EACH	1000.00000	112000.00	1000.00000	112000.00		
0470 624000 PREFABRICATED EXPANSION JOINT SYSTEM, 3	209.000	LF	847.00000	177023.00	847.00000	177023.00		
0480 626010 ALUMINUM PEDESTRIAN RAILING	941.000	LF	183.00000	172203.00	183.00000	172203.00		
0490 628001 REPAIR OF CONCRETE STRUCTURE BY EPOXY INJECTION	339.000	LF	53.00000	17967.00	53.00000	17967.00		
0500 628040 SHALLOW SPALL REPAIR	8.000	CF	1296.00000	10368.00	1296.00000	10368.00		
0510 628041 DEEP SPALL REPAIR	44.000	CF	1620.00000	71280.00	1620.00000	71280.00		
0520 628070 DRILLING HOLES AND INSTALLING DOWELS	908.000	EACH	31.00000	28148.00	31.00000	28148.00		
0530 628504 REHABILITATION OF EXISTING CONCRETE STRUCTURE, FRP WRAP		LUMP	280000.00000	280000.00	280000.00000	280000.00		
0540 701010 PORTLAND CEMENT CONCRETE CURB, TYPE 1-2	822.000	LF	48.00000	39456.00	48.00000	39456.00		
0550 701011 PORTLAND CEMENT CONCRETE CURB, TYPE 1-4	1992.000	LF	40.00000	79680.00	40.00000	79680.00		
0560 701013 PORTLAND CEMENT CONCRETE CURB, TYPE 1-8	1461.000	LF	56.00000	81816.00	56.00000	81816.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0570 701023 INTEGRAL PORTLAND CEMENT CONCRETE CURB AND GUTTER, TYPE 3-8	114.000	LF	58.00000	6612.00	58.00000	6612.00		
0580 705001 PORTLAND CEMENT CONCRETE SIDEWALK, 4"	10864.000	SF	10.50000	114072.00	10.50000	114072.00		
0590 707016 RIPRAP, R-5	2959.000	TON	122.50000	362477.50	122.50000	362477.50		
0600 707500 CHANNEL BED FILL	550.000	CY	100.00000	55000.00	100.00000	55000.00		
0610 708003 GEOTEXTILES, RIPRAP	3200.000	SY	9.50000	30400.00	9.50000	30400.00		
0620 720021 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-31	2098.000	LF	25.00000	52450.00	25.00000	52450.00		
0630 720031 GUARDRAIL MOUNTED RAILING	1954.000	LF	14.00000	27356.00	14.00000	27356.00		
0640 720034 GALVANIZED STEEL BEAM GUARDRAIL, TYPE 1-27	32.000	LF	37.00000	1184.00	37.00000	1184.00		
0650 721001 GUARDRAIL END TREATMENT, TYPE 1-31, TEST LEVEL 3	2.000	EACH	3600.00000	7200.00	3600.00000	7200.00		
0660 721004 GUARDRAIL END TREATMENT, TYPE 3-31	2.000	EACH	5400.00000	10800.00	5400.00000	10800.00		
0670 721006 END ANCHORAGE 31	2.000	EACH	1500.00000	3000.00	1500.00000	3000.00		
0680 721010 GUARDRAIL TO BARRIER CONNECTION, APPROACH TYPE 1-31	8.000	EACH	3250.00000	26000.00	3250.00000	26000.00		
0690 760010 PAVEMENT MILLING, BITUMINOUS CONCRETE PAVEMENT	24163.000	SYIN	1.90000	45909.70	1.90000	45909.70		
0700 762000 SAW CUTTING, BITUMINOUS CONCRETE	5710.000	LF	2.45000	13989.50	2.45000	13989.50		
0710 762001 SAW CUTTING, CONCRETE, FULL DEPTH	497.000	LF	5.50000	2733.50	5.50000	2733.50		
0720 763000 INITIAL EXPENSE/DE-MOBILIZATION		LUMP	704097.51000	704097.51	704160.00000	704160.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0730 763501 CONSTRUCTION ENGINEERING		LUMP	81000.00000	81000.00	81000.00000	81000.00		
0740 763508 PROJECT CONTROL SYSTEM DEVELOPMENT PLAN		LUMP	216000.00000	216000.00	216000.00000	216000.00		
0750 763509 CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	10.000	EAMO	5400.00000	54000.00	5400.00000	54000.00		
0760 763522 COAST GUARD SPECIFIC CONDITIONS		LUMP	5400.00000	5400.00	5400.00000	5400.00		
0770 763598 FIELD OFFICE, SPECIAL I	10.000	EAMO	9200.00000	92000.00	9200.00000	92000.00		
0780 801000 MAINTENANCE OF TRAFFIC		LUMP	250000.00000	250000.00	250000.00000	250000.00		
0790 802003 ARROW PANELS TYPE C	676.000	EADY	22.25000	15041.00	22.24800	15039.65		
0800 803001 FURNISH AND MAINTAIN PORTABLE CHANGEABLE MESSAGE SIGN	135.000	EADY	84.00000	11340.00	84.00000	11340.00		
0810 803502 TEMPORARY QUEUE DETECTION SYSTEM		LUMP	105000.00000	105000.00	105000.00000	105000.00		
0820 804001 FURNISH AND MAINTAIN PORTABLE LIGHT ASSEMBLY (FLOOD LIGHTS)	440.000	EADY	202.00000	88880.00	202.00000	88880.00		
0830 805001 PLASTIC DRUMS	34334.000	EADY	0.39000	13390.26	0.38880	13349.06		
0840 806001 TRAFFIC OFFICERS	360.000	HOUR	75.00000	27000.00	75.00000	27000.00		
0850 807002 FURNISH AND INSTALL TEMPORARY PORTLAND CEMENT CONCRETE SAFETY BARRIER, PINNED IN BITUMINOUS PAVEMENT	650.000	LF	67.00000	43550.00	67.00000	43550.00		
0860 807003 FURNISH AND INSTALL TEMPORARY PORTLAND CEMENT CONCRETE SAFETY BARRIER, PINNED IN CONCRETE	487.000	LF	98.00000	47726.00	98.00000	47726.00		
0870 807005 RELOCATE TEMPORARY PORTLAND CEMENT CCONCRETE SAFETY BARRIER, PINNED IN BITUMINOUS PAVEMENT	744.000	LF	17.00000	12648.00	17.00000	12648.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
0880 807007 REFLECTOR PANELS	13.000	EACH	35.00000	455.00	35.00000	455.00		
0890 807010 REMOVE TEMPORARY PORTLAND CEMENT CONCRETE SAFETY BARRIER, PINNED IN BITUMINOUS PAVEMENT	650.000	LF	18.00000	11700.00	18.00000	11700.00		
0900 807011 REMOVE TEMPORART PORTLAND CEMENT CONCRETE BARRIER, PINNED IN CONCRETE	487.000	LF	27.00000	13149.00	27.00000	13149.00		
0910 808002 FURNISH AND MAINTAIN TRUCK MOUNTED ATTENUATOR, TYPE II	456.000	EADY	167.50000	76380.00	167.50000	76380.00		
0920 809001 INSTALL TEMPORARY IMPACT ATTENUATOR	2.000	EACH	1950.00000	3900.00	1950.00000	3900.00		
0930 809004 FURNISH TEMPORARY IMPACT ATTENUATOR - NON-GATING, REDIRECTIVE, TEST LEVEL 2	2.000	EACH	7600.00000	15200.00	7600.00000	15200.00		
0940 809006 RELOCATE TEMPORARY IMPACT ATTENUATOR	3.000	EACH	2800.00000	8400.00	2800.00000	8400.00		
0950 810001 TEMPORARY WARNING SIGNS AND PLAQUES	33270.000	EADY	2.70000	89829.00	2.70000	89829.00		
0960 811012 FLAGGER, SUSSEX COUNTY, HEAVY CONSTRUCTION, FEDERAL	1920.000	HOUR	76.00000	145920.00	76.00000	145920.00		
0970 811024 FLAGGER, SUSSEX COUNTY, HEAVY CONSTRUCTION, FEDERAL, OVERTIME	480.000	HOUR	113.00000	54240.00	113.00000	54240.00		
0980 813001 TEMPORARY BARRICADES, TYPE III	16750.000	LFDY	0.39000	6532.50	0.38880	6512.40		
0990 817002 PERMANENT PAVEMENT STRIPING, SYMBOL/LEGEND, ALKYD-THERMOPLASTIC	592.000	SF	4.55000	2693.60	4.55000	2693.60		
1000 817003 TEMPORARY MARKINGS, PAINT, 4"	16583.000	LF	0.27000	4477.41	0.27000	4477.41		
1010 817004 TEMPORARY MARKINGS, PAINT, SYMBOL/LEGEN	19.000	SF	5.50000	104.50	5.50000	104.50		
1020 817013 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 5"	11882.000	LF	0.66000	7842.12	0.66000	7842.12		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1030 817014 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, WHITE/YELLOW, 10"	405.000	LF	1.30000	526.50	1.29600	524.88		
1040 817015 PREFORMED RETROREFLECTIVE THERMOPLASTIC MARKINGS, BIKE SYMBOL	11.000	EACH	362.00000	3982.00	362.00000	3982.00		
1050 817018 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 3"`	805.000	LF	1.10000	885.50	1.10000	885.50		
1060 817019 PERMANENT PAVEMENT STRIPING, EPOXY RESIN PAINT, BLACK, 5"	200.000	LF	2.20000	440.00	2.20000	440.00		
1070 817027 RAISED/RECESSED PAVEMENT MARKER	49.000	EACH	44.00000	2156.00	44.00000	2156.00		
1080 817030 REMOVAL OF RAISED/RECESSED PAVEMENT MARKER HOUSING	49.000	EACH	42.00000	2058.00	42.00000	2058.00		
1090 817031 REMOVAL OF PAVEMENT STRIPING	10479.000	SF	2.25000	23577.75	2.25000	23577.75		
1100 819018 INSTALLATION OR REMOVAL OF TRAFFIC SIGN(S) ON SINGLE SIGN POST	2.000	EACH	500.00000	1000.00	500.00000	1000.00		
1110 825001 TUBULAR MARKERS	200.000	EACH	83.00000	16600.00	83.00000	16600.00		
1120 830001 CONDUIT JUNCTION WELL, TYPE 1, 20" X 20" PRECAST CONCRETE	10.000	EACH	2000.00000	20000.00	2000.00000	20000.00		
1130 830002 CONDUIT JUNCTION WELL, TYPE 4, 20" X 42-1/2" PRECAST CONCRETE	3.000	EACH	2125.00000	6375.00	2125.00000	6375.00		
1140 830004 CONDUIT JUNCTION WELL, TYPE 7, 36" X 60" PRECAST POLYMER CONCRETE	2.000	EACH	3800.00000	7600.00	3800.00000	7600.00		
1150 830008 ADJUST OR REPAIR EXISTING CONDUIT JUNCTION WELL	10.000	EACH	425.00000	4250.00	425.00000	4250.00		
1160 830010 REMOVAL OF EXISTING JUNCTION WELL	10.000	EACH	467.00000	4670.00	467.00000	4670.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY		(0) ENGINEER'S ESTIMATE UNIT PRICE	 AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	 AMOUNT	( ) UNIT PRICE	 AMOUNT
1170 830500 PORTLAND CEMENT CONCRETE BARRIER JUNCTION WELL	19.000	EACH	1700.00000	32300.00	1700.00000	32300.00		
1180 830501 JUNCTION BOX ON STRUCTURE	6.000	EACH	1450.00000	8700.00	1450.00000	8700.00		
1190 831001 FURNISH AND INSTALL UP TO 3" FLEXIBLE METALLIC-LIQUID TIGHT CONDUIT	60.000	LF	49.00000	2940.00	49.00000	2940.00		
1200 831004 FURNISH AND INSTALL UP TO 4" SCHEDULE 80 PVC CONDUIT (TRENCH)	2426.000	LF	10.50000	25473.00	10.50000	25473.00		
1210 831538 FURNISH AND INSTALL 2" GALVANIZED STEEL CONDUIT (ON STRUCTURE)	1076.000	LF	11.40000	12266.40	11.40000	12266.40		
1220 831540 FURNISH AND INSTALL 3" GALVANIZED STEEL CONDUIT (ON STRUCTURE)	470.000	LF	14.00000	6580.00	14.00000	6580.00		
1230 832007 FURNISH AND INSTALL 1-CONDUCTOR #4 AWG STRANDED COPPER, TYPE USE-2	4794.000	LF	3.25000	15580.50	3.25000	15580.50		
1240 832008 FURNISH AND INSTALL 1-CONDUCTOR #6 STRANDED COPPER, TYPE USE-2	200.000	LF	3.00000	600.00	3.00000	600.00		
1250 832018 FURNISH AND INSTALL STRANDED INSULATED COPPER GROUND WIRE, 1/#4 AWG	2397.000	LF	3.25000	7790.25	3.25000	7790.25		
1260 832019 FURNISH AND INSTALL STRANDED INSULATED COPPER GROUND WIRE, 1/#6 AWG	100.000	LF	3.00000	300.00	3.00000	300.00		
1270 834006 POLE BASE, TYPE 6	4.000	EACH	1130.00000	4520.00	1130.00000	4520.00		
1280 834501 PARTIAL REMOVAL OF CONCRETE POLE BASES AND CABINET FOUNDATIONS	1.000	CY	523.00000	523.00	523.00000	523.00		
1290 843001 ELECTRICAL TESTING		LUMP	3500.00000	3500.00	3500.00000	3500.00		
1300 850503 LUMINAIRE (LED), 160 WATTS	4.000	EACH	1000.00000	4000.00	1000.00000	4000.00		

TABULATION OF BIDS
FINAL

CONTRACT TITLE : BR 3-150N/S ON S014 SR1 OVER LEWES REHOBOTH CANAL
CALL ORDER : 002 CONTRACT ID : T201407602.01 COUNTIES : SUSSEX
LETTING DATE : 06/10/19 DISTRICT : M9

SET-ASIDE :

LINE NO / ITEM CODE / ALT ITEM DESCRIPTION	QUANTITY	(0) ENGINEER'S ESTIMATE UNIT PRICE	(0) ENGINEER'S ESTIMATE AMOUNT	(1) KIEWIT INFRASTRUCTURE SOUTH UNIT PRICE	(1) KIEWIT INFRASTRUCTURE SOUTH AMOUNT	( ) UNIT PRICE	( ) AMOUNT
1310 850504 UNDERPASS LIGHT FIXTURE (LED)	8.000 EACH	1100.00000	8800.00	1100.00000	8800.00		
1320 851001 ALUMINUM LIGHTING STANDARD WITH SINGLE DAVIT ARM, 30' POLE	4.000 EACH	4300.00000	17200.00	4300.00000	17200.00		
1330 851527 REMOVE AND REINSTALL LIGHTING POLE, MAST ARM, AND METAL TRANSFORMER BASE	4.000 EACH	517.00000	2068.00	517.00000	2068.00		
1340 905001 SILT FENCE	3262.000 LF	3.75000	12232.50	3.75000	12232.50		
1350 905004 INLET SEDIMENT CONTROL, DRAINAGE INLET	13.000 EACH	216.00000	2808.00	216.00000	2808.00		
1360 906002 DEWATERING BAG	2.000 EACH	1500.00000	3000.00	1500.00000	3000.00		
1370 906003 SUMP PIT	2.000 EACH	3000.00000	6000.00	3000.00000	6000.00		
1380 908004 TOPSOIL, 6" DEPTH	2395.000 SY	10.50000	25147.50	10.50000	25147.50		
1390 908014 PERMANENT GRASS SEEDING, DRY GROUND	2248.000 SY	2.20000	4945.60	2.20000	4945.60		
1400 908019 PERMANENT GRASS SEEDING, STREAMBANK	147.000 SY	6.50000	955.50	6.50000	955.50		
1410 908020 EROSION CONTROL BLANKET MULCH	147.000 SY	3.30000	485.10	3.30000	485.10		
1420 909004 TURBIDITY CURTAIN, FLOATING	395.000 LF	33.50000	13232.50	33.50000	13232.50		
SECTION TOTALS			$ 15,864,738.00		$ 15,864,737.23		$
CONTRACT TOTALS			$ 15,864,738.00		$ 15,864,737.23		$
DBE GOALS		5 %		5 %			%