Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal

Call Order: 005

Contract ID: T201707602

Counties: SUSSEX

Letting Date: August 10, 2021

District(s): 0003

Project(s):

Federal Aid No:

Contract Time: 186 CALENDAR DAYS

Contract Description: REMOVAL OF BRIDGE 3-928R, LEWES RR SWING BRIDGE -
Remove the steel superstructure and move it a new locations for display and preservation in coordination with the SHPO. The steel will most likely be moved out by barge. Remove the pivot and rest pier, cut off piles below the mudline, remove the timber approach trestles, remove embankment to the current edge of the canal and place rip rap along the edge of the canal.

Set-Aside:

Vendor Ranking: Contract was awarded on 08/30/21 to vendor RICHARD E PIERSON CONSTRUCTION COMPANY, INC.

Rank	Vendor ID/Name	Total Bid	Percent Of Low Bid	Percent Of Estimate
1	RICHARD E PIERSON CONSTRUCTION COMPANY, INC.	$2,219,409.95	100.00%	93.29%
0	Engineer's Estimate	$2,379,000.00	107.19%	100.00%
2	JJID INC	$3,143,000.00	141.61%	132.11%
3	J D ECKMAN, INC.	$3,477,905.00	156.70%	146.19%
4	MUMFORD & MILLER CONCRETE, INC.	$3,625,093.30	163.34%	152.38%
5	A P CONSTRUCTION, INC.	$6,290,373.60	283.43%	264.41%

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	Engineer's Estimate Unit Price	Engineer's Estimate Ext Amount	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Unit Price	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Ext Amount	(2) JJID INC Unit Price	(2) JJID INC Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE **Cat Alt Set:**				**Cat Alt Member:**		**LCC:**	
0010 201000	(1)	75,000.00000	75,000.00	24,000.00000	24,000.00	20,000.00000	20,000.00
CLEARING AND GRUBBING	LS						
0020 202000	2,720.000	40.00000	108,800.00	33.00000	89,760.00	27.00000	73,440.00
EXCAVATION AND EMBANKMENT	CY						
0030 203000	2,900.000	50.00000	145,000.00	31.00000	89,900.00	27.00000	78,300.00
CHANNEL EXCAVATION	CY						
0040 207000	15.000	150.00000	2,250.00	35.00000	525.00	100.00000	1,500.00
STRUCTURAL EXCAVATION	CY						
0050 209002	52.000	20.00000	1,040.00	26.00000	1,352.00	70.00000	3,640.00
BORROW, TYPE B	CY						
0060 211000	(1)	350,000.00000	350,000.00	315,000.00000	315,000.00	350,000.00000	350,000.00
REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS						
0070 211507	1.000	450,000.00000	450,000.00	375,000.00000	375,000.00	470,000.00000	470,000.00
BRIDGE RELOCATION	LS						
0080 301001	37.000	80.00000	2,960.00	97.00000	3,589.00	85.00000	3,145.00
GRADED AGGREGATE BASE COURSE, TYPE B	CY						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	Engineer's Estimate Unit Price	 Ext Amount	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Unit Price	 Ext Amount	(2) JJID INC Unit Price	 Ext Amount
SECTION: 0001	REMOVAL OF EXISTING RR BRIDGE	**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0090 302002	352.000	45.00000	15,840.00	64.00000	22,528.00	60.00000	21,120.00
DELAWARE NO. 3 STONE	TON						
0100 401005	129.000	160.00000	20,640.00	145.00000	18,705.00	160.00000	20,640.00
SUPERPAVE TYPE C, PG 64-22 (CARBONATE STONE)	TON						
0110 401027	73.000	160.00000	11,680.00	123.00000	8,979.00	190.00000	13,870.00
BITUMINOUS CONCRETE, SUPERPAVE TYPE B, 160 GYRATIONS PG 64-22 PATCHING	TON						
0120 604002	(1)	480,000.00000	480,000.00	560,000.00000	560,000.00	975,000.00000	975,000.00
COFFERDAMS	LS						
0130 605001	440.000	30.00000	13,200.00	37.00000	16,280.00	700.00000	308,000.00
FURNISH TIMBER PILES - TREATED, 14"	LF						
0140 605101	440.000	50.00000	22,000.00	36.00000	15,840.00	15.00000	6,600.00
INSTALL TIMBER PILES - TREATED, 14"	LF						
0150 608010	3,067.000	50.00000	153,350.00	39.00000	119,613.00	55.00000	168,685.00
STEEL SHEET PILES, PZC 13	SF						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	Engineer's Estimate Unit Price	 Ext Amount	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Unit Price	 Ext Amount	(2) JJID INC Unit Price	 Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE		**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0160 610005	34.000	1,000.00000	34,000.00	1,450.00000	49,300.00	1,650.00000	56,100.00
PORTLAND CEMENT CONCRETE MASONRY, SUBSTRUCTURE, CLASS A	CY						
0170 611001	2,260.000	2.50000	5,650.00	1.70000	3,842.00	2.75000	6,215.00
BAR REINFORCEMENT, EPOXY COATED	LB						
0180 615001	(1)	46,000.00000	46,000.00	50,000.00000	50,000.00	25,000.00000	25,000.00
STEEL STRUCTURES	LS						
0190 623003	32.000	500.00000	16,000.00	715.00000	22,880.00	185.00000	5,920.00
REPLACE ANCHOR BOLTS	EACH						
0200 705002	440.000	20.00000	8,800.00	13.00000	5,720.00	18.00000	7,920.00
PORTLAND CEMENT CONCRETE SIDEWALK, 6"	SF						
0210 707018	1,541.000	50.00000	77,050.00	95.00000	146,395.00	120.00000	184,920.00
RIPRAP, R-7	TON						
0220 707500	32.000	50.00000	1,600.00	72.00000	2,304.00	160.00000	5,120.00
CHANNEL BED FILL	CY						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	Engineer's Estimate Unit Price	 Ext Amount	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Unit Price	 Ext Amount	(2) JJID INC Unit Price	 Ext Amount
SECTION: 0001	REMOVAL OF EXISTING RR BRIDGE	**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0230 708003	958.000	4.00000	3,832.00	4.65000	4,454.70	4.00000	3,832.00
GEOTEXTILES, RIPRAP	SY						
0240 720556	1.000	1,500.00000	1,500.00	1,060.00000	1,060.00	1,384.00000	1,384.00
BOLLARD	EACH						
0250 727005	272.000	200.00000	54,400.00	120.00000	32,640.00	135.00000	36,720.00
DECORATIVE FENCE	LF						
0260 727510	987.000	17.00000	16,779.00	28.00000	27,636.00	28.00000	27,636.00
WOOD RAIL FENCE	LF						
0270 763000	(1)	112,084.00000	112,084.00	110,000.00000	110,000.00	125,000.00000	125,000.00
INITIAL EXPENSE/DE-MOBILIZATION	LS						
0280 763501	(1)	23,000.00000	23,000.00	10,000.00000	10,000.00	35,000.00000	35,000.00
CONSTRUCTION ENGINEERING	LS						
0290 763502	(1)	10,000.00000	10,000.00	3,700.00000	3,700.00	12,000.00000	12,000.00
SITE FURNISHING	LS						
0300 763508	(1)	5,000.00000	5,000.00	1.00000	1.00	1,500.00000	1,500.00
PROJECT CONTROL SYSTEM DEVELOPMENT PLAN	LS						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	Engineer's Estimate Unit Price	Engineer's Estimate Ext Amount	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Unit Price	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Ext Amount	(2) JJID INC Unit Price	(2) JJID INC Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE **Cat Alt Set:**				**Cat Alt Member:**		**LCC:**	
0310 763509	6.000	500.00000	3,000.00	1.00000	6.00	750.00000	4,500.00
CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	EAMO						
0320 763522	(1)	5,000.00000	5,000.00	10,000.00000	10,000.00	5,000.00000	5,000.00
COAST GUARD SPECIFIC CONDITIONS	LS						
0330 801500	(1)	50,000.00000	50,000.00	10,000.00000	10,000.00	20,000.00000	20,000.00
MAINTENANCE OF TRAFFIC, ALL INCLUSIVE	LS						
0340 811003	160.000	46.20000	7,392.00	80.00000	12,800.00	78.00000	12,480.00
FLAGGER, SUSSEX COUNTY, STATE	HOUR						
0350 811015	40.000	69.30000	2,772.00	119.00000	4,760.00	110.00000	4,400.00
FLAGGER, SUSSEX COUNTY, STATE, OVERTIME	HOUR						
0360 905001	1,236.000	4.00000	4,944.00	4.00000	4,944.00	3.00000	3,708.00
SILT FENCE	LF						
0370 908004	2,353.000	9.50000	22,353.50	13.50000	31,765.50	12.00000	28,236.00
TOPSOIL, 6" DEPTH	SY						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	Engineer's Estimate Unit Price	Engineer's Estimate Ext Amount	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Unit Price	(1) RICHARD E PIERSON CONSTRUCTION COMPANY, INC. Ext Amount	(2) JJID INC Unit Price	(2) JJID INC Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE		**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0380 908014	1,583.000	2.50000	3,957.50	2.00000	3,166.00	2.50000	3,957.50
PERMANENT GRASS SEEDING, DRY GROUND	SY						
0390 908019	771.000	2.00000	1,542.00	4.00000	3,084.00	3.00000	2,313.00
PERMANENT GRASS SEEDING, STREAMBANK	SY						
0400 908020	771.000	4.00000	3,084.00	3.25000	2,505.75	3.50000	2,698.50
EROSION CONTROL BLANKET MULCH	SY						
0410 909004	250.000	30.00000	7,500.00	21.50000	5,375.00	30.00000	7,500.00
TURBIDITY CURTAIN, FLOATING	LF						
Section Totals:			$2,379,000.00		$2,219,409.95		$3,143,000.00
Life Cycle Costs:							
Section Total with LCC:			$2,379,000.00		$2,219,409.95		$3,143,000.00
Contract Item Totals			**$2,379,000.00**		**$2,219,409.95**		**$3,143,000.00**
Contract Time Totals			**$0.00**				
Contract Life Cycle Costs Totals			**$0.00**		**$0.00**		**$0.00**
Contract Grand Totals			**$2,379,000.00**		**$2,219,409.95**		**3,143,000.00**

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal

Contract ID: T201707602

Counties: SUSSEX

( ) indicates item is bid as Lump Sum

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(3) J D ECKMAN, INC.		(4) MUMFORD & MILLER CONCRETE, INC.		(5) A P CONSTRUCTION, INC.	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE		**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0010 201000	(1)	18,000.00000	18,000.00	19,500.00000	19,500.00	75,000.00000	75,000.00
CLEARING AND GRUBBING	LS						
0020 202000	2,720.000	21.00000	57,120.00	17.30000	47,056.00	87.00000	236,640.00
EXCAVATION AND EMBANKMENT	CY						
0030 203000	2,900.000	25.00000	72,500.00	17.30000	50,170.00	163.00000	472,700.00
CHANNEL EXCAVATION	CY						
0040 207000	15.000	34.00000	510.00	40.00000	600.00	22,100.00000	331,500.00
STRUCTURAL EXCAVATION	CY						
0050 209002	52.000	55.00000	2,860.00	106.75000	5,551.00	220.00000	11,440.00
BORROW, TYPE B	CY						
0060 211000	(1)	425,000.00000	425,000.00	216,800.00000	216,800.00	400,000.00000	400,000.00
REMOVAL OF STRUCTURES AND OBSTRUCTIONS	LS						
0070 211507	1.000	500,000.00000	500,000.00	504,000.00000	504,000.00	157,000.00000	157,000.00
BRIDGE RELOCATION	LS						
0080 301001	37.000	61.00000	2,257.00	91.35000	3,379.95	1,210.00000	44,770.00
GRADED AGGREGATE BASE COURSE, TYPE B	CY						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(3) J D ECKMAN, INC. Unit Price	(3) J D ECKMAN, INC. Ext Amount	(4) MUMFORD & MILLER CONCRETE, INC. Unit Price	(4) MUMFORD & MILLER CONCRETE, INC. Ext Amount	(5) A P CONSTRUCTION, INC. Unit Price	(5) A P CONSTRUCTION, INC. Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE **Cat Alt Set:**				**Cat Alt Member:**		**LCC:**	
0090 302002	352.000	39.00000	13,728.00	59.00000	20,768.00	58.00000	20,416.00
DELAWARE NO. 3 STONE	TON						
0100 401005	129.000	136.00000	17,544.00	169.75000	21,897.75	157.00000	20,253.00
SUPERPAVE TYPE C, PG 64-22 (CARBONATE STONE)	TON						
0110 401027	73.000	122.00000	8,906.00	153.00000	11,169.00	231.00000	16,863.00
BITUMINOUS CONCRETE, SUPERPAVE TYPE B, 160 GYRATIONS PG 64-22 PATCHING	TON						
0120 604002	(1)	1,580,000.00000	1,580,000.00	2,015,700.00000	2,015,700.00	2,735,200.00000	2,735,200.00
COFFERDAMS	LS						
0130 605001	440.000	72.00000	31,680.00	24.60000	10,824.00	13.00000	5,720.00
FURNISH TIMBER PILES - TREATED, 14"	LF						
0140 605101	440.000	62.00000	27,280.00	27.25000	11,990.00	45.00000	19,800.00
INSTALL TIMBER PILES - TREATED, 14"	LF						
0150 608010	3,067.000	45.00000	138,015.00	42.00000	128,814.00	152.00000	466,184.00
STEEL SHEET PILES, PZC 13	SF						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(3) J D ECKMAN, INC.		(4) MUMFORD & MILLER CONCRETE, INC.		(5) A P CONSTRUCTION, INC.	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001	REMOVAL OF EXISTING RR BRIDGE	**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0160 610005	34.000	810.00000	27,540.00	1,790.00000	60,860.00	1,630.00000	55,420.00
PORTLAND CEMENT CONCRETE MASONRY, SUBSTRUCTURE, CLASS A	CY						
0170 611001	2,260.000	2.65000	5,989.00	3.00000	6,780.00	6.00000	13,560.00
BAR REINFORCEMENT, EPOXY COATED	LB						
0180 615001	(1)	48,000.00000	48,000.00	85,500.00000	85,500.00	188,000.00000	188,000.00
STEEL STRUCTURES	LS						
0190 623003	32.000	220.00000	7,040.00	235.00000	7,520.00	750.00000	24,000.00
REPLACE ANCHOR BOLTS	EACH						
0200 705002	440.000	14.00000	6,160.00	12.30000	5,412.00	25.00000	11,000.00
PORTLAND CEMENT CONCRETE SIDEWALK, 6"	SF						
0210 707018	1,541.000	58.00000	89,378.00	87.80000	135,299.80	105.00000	161,805.00
RIPRAP, R-7	TON						
0220 707500	32.000	49.00000	1,568.00	151.50000	4,848.00	225.00000	7,200.00
CHANNEL BED FILL	CY						
0230 708003	958.000	6.00000	5,748.00	4.00000	3,832.00	40.00000	38,320.00
GEOTEXTILES, RIPRAP	SY						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID Item Description Alt Set / Alt Member	Quantity and Units	(3) J D ECKMAN, INC.		(4) MUMFORD & MILLER CONCRETE, INC.		(5) A P CONSTRUCTION, INC.	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001	REMOVAL OF EXISTING RR BRIDGE	**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0240 720556	1.000	3,800.00000	3,800.00	1,430.00000	1,430.00	7,500.00000	7,500.00
BOLLARD	EACH						
0250 727005	272.000	120.00000	32,640.00	60.50000	16,456.00	225.00000	61,200.00
DECORATIVE FENCE	LF						
0260 727510	987.000	60.00000	59,220.00	22.70000	22,404.90	30.00000	29,610.00
WOOD RAIL FENCE	LF						
0270 763000	(1)	180,000.00000	180,000.00	110,000.00000	110,000.00	450,000.00000	450,000.00
INITIAL EXPENSE/DE-MOBILIZATION	LS						
0280 763501	(1)	7,500.00000	7,500.00	17,500.00000	17,500.00	45,000.00000	45,000.00
CONSTRUCTION ENGINEERING	LS						
0290 763502	(1)	12,000.00000	12,000.00	4,400.00000	4,400.00	37,500.00000	37,500.00
SITE FURNISHING	LS						
0300 763508	(1)	2,000.00000	2,000.00	600.00000	600.00	7,500.00000	7,500.00
PROJECT CONTROL SYSTEM DEVELOPMENT PLAN	LS						
0310 763509	6.000	300.00000	1,800.00	40.00000	240.00	750.00000	4,500.00
CPM SCHEDULE UPDATES AND/OR REVISED UPDATES	EAMO						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(3) J D ECKMAN, INC.		(4) MUMFORD & MILLER CONCRETE, INC.		(5) A P CONSTRUCTION, INC.	
		Unit Price	Ext Amount	Unit Price	Ext Amount	Unit Price	Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE		**Cat Alt Set:**		**Cat Alt Member:**		**LCC:**	
0320 763522	(1)	14,000.00000	14,000.00	5,800.00000	5,800.00	7,500.00000	7,500.00
COAST GUARD SPECIFIC CONDITIONS	LS						
0330 801500	(1)	4,500.00000	4,500.00	16,200.00000	16,200.00	22,500.00000	22,500.00
MAINTENANCE OF TRAFFIC, ALL INCLUSIVE	LS						
0340 811003	160.000	82.00000	13,120.00	84.30000	13,488.00	150.00000	24,000.00
FLAGGER, SUSSEX COUNTY, STATE	HOUR						
0350 811015	40.000	150.00000	6,000.00	105.00000	4,200.00	219.89000	8,795.60
FLAGGER, SUSSEX COUNTY, STATE, OVERTIME	HOUR						
0360 905001	1,236.000	5.50000	6,798.00	3.75000	4,635.00	8.00000	9,888.00
SILT FENCE	LF						
0370 908004	2,353.000	13.00000	30,589.00	8.30000	19,529.90	13.00000	30,589.00
TOPSOIL, 6" DEPTH	SY						
0380 908014	1,583.000	1.50000	2,374.50	1.40000	2,216.20	8.00000	12,664.00
PERMANENT GRASS SEEDING, DRY GROUND	SY						

DelDOT

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal **Contract ID:** T201707602 **Counties:** SUSSEX

Line No / Item ID / Item Description / Alt Set / Alt Member	Quantity and Units	(3) J D ECKMAN, INC. Unit Price	(3) J D ECKMAN, INC. Ext Amount	(4) MUMFORD & MILLER CONCRETE, INC. Unit Price	(4) MUMFORD & MILLER CONCRETE, INC. Ext Amount	(5) A P CONSTRUCTION, INC. Unit Price	(5) A P CONSTRUCTION, INC. Ext Amount
SECTION: 0001 REMOVAL OF EXISTING RR BRIDGE **Cat Alt Set:**				**Cat Alt Member:**		**LCC:**	
0390 908019	771.000	2.00000	1,542.00	2.70000	2,081.70	8.00000	6,168.00
PERMANENT GRASS SEEDING, STREAMBANK	SY						
0400 908020	771.000	3.50000	2,698.50	3.10000	2,390.10	8.00000	6,168.00
EROSION CONTROL BLANKET MULCH	SY						
0410 909004	250.000	42.00000	10,500.00	13.00000	3,250.00	26.00000	6,500.00
TURBIDITY CURTAIN, FLOATING	LF						
Section Totals:			$3,477,905.00		$3,625,093.30		$6,290,373.60
Life Cycle Costs:							
Section Total with LCC:			$3,477,905.00		$3,625,093.30		$6,290,373.60
Contract Item Totals			**$3,477,905.00**		**$3,625,093.30**		**$6,290,373.60**
Contract Time Totals							
Contract Life Cycle Costs Totals			**$0.00**		**$0.00**		**$0.00**
Contract Grand Totals			**$3,477,905.00**		**$3,625,093.30**		**6,290,373.60**

( ) indicates item is bid as Lump Sum

Delaware Department of Transportation

Tabulation of Bids

AASHTOWare Pr

Contract Title: BR 3-928R, Lewes RR Swing Bridge over the Lewes Rehoboth Canal

Contract ID: T201707602

Counties: SUSSEX